



EQUIPMENT DISPLAY
SEPTEMBER 15 – 16, 2018
AUNDH MILITARY STATION, PUNE, INDIA

MADE IN INDIA



**EQUIPMENT
CATALOGUE**





EQUIPMENT DISPLAY
SEPTEMBER 15 – 16, 2018
AUNDH MILITARY STATION, PUNE, INDIA

MADE IN INDIA



CONTENT

Foreword	01
Index	05
Exhibitor & Equipment Profiles	19



EQUIPMENT DISPLAY

SEPTEMBER 15 – 16, 2018

AUNDH MILITARY STATION, PUNE, INDIA

MADE IN INDIA



FOREWORD



FOREWORD

It is an honour for Indian Army to host the first BIMSTEC Multinational Military Field Training Exercise (BIMSTEC MILEX - 2018) and Chiefs' Conclave from September 10 - 16 at Aundh Military Station, Pune. This exercise is themed on 'Counter Terrorism Operations'.

In the recently concluded BIMSTEC Summit in Nepal, the Hon'ble Prime Minister of India Shri Narendra Modi, made a strong pitch for peace and stability and for combating the menace of terrorism in the region. Hence, it is befitting that the aim of this military exercise is to promote strategic alignment among the BIMSTEC member nations and to share best practices in counter terrorism operations in Semi-urban area.

Undoubtedly, BIMSTEC Nations need to establish collective strategies for the common security challenges they face. Furthermore, it is a unique opportunity for the Indian Defence Equipment manufacturers to provide solutions that are suited to the military requirements of the BIMSTEC Nations.

With this background an idea germinated, thereby leading to this focussed equipment display by key Indian Defence Players to the BIMSTEC Nations Army Chiefs and the contingent, concurrent with the military exercise.

I applaud the DRDO, DPSUs, OFB and Industry for displaying the indigenous capability and am confident that the defence equipment displayed during BIMSTEC Meet will not only cater to the military requirements of the Armies of BIMSTEC Nations but also help them in acquiring defence capability.

Jai Hind

D R Soni

Lieutenant General
GOC-in-C of Southern Command





FOREWORD

The flagship 'Make in India' initiative by the Government of India (GoI) not only seeks to reduce our nation's dependence on imported weapons, but also to position India as a hub of defence manufacturing. With the series of reforms undertaken by the GoI in the past few years, India has been taking slow but steady steps towards positioning itself as an exporter of military hardware.

Under the Draft Defence Production Policy 2018, India has set an ambitious defence export target of USD 5 billion by 2025 and become one of the world's top five defence producers. Here is an opportunity for the country to position itself as an economically viable option for BIMSTEC Nations to meet their defence requirements.

As an apex industry body, FICCI has been playing an active role to develop a robust defence industrial base in the country through its various initiatives with stakeholders such as the Ministry of Defence, Armed Forces, DPSUs, Indian private players and Foreign OEMs. At the same time, we have laid significant focus on providing the Indian defence industry avenues for international collaborations and enhance our defence export market.

Continuing our efforts, FICCI is delighted to organise this first ever 'Equipment Display' on the occasion of visits by BIMSTEC Nations' Army Chiefs and their contingent of army officers. The all-round participation by leading DPSUs, major private sector players, ordnance factories, DRDO and academia to showcase their products / solutions is a testimony to our capability in not only meeting requirements of our army, but also those of our friendly nations of the BIMSTEC group. We are confident that the equipment displays will translate into tangible business activities in the near future.

I take this opportunity to acknowledge the support and guidance extended by Army Design Bureau (ADB), Indian Army, towards realizing this initiative.

This equipment display catalogue will serve as a ready reckoner to our distinguished visitors in their procurement decisions from India. FICCI is committed to support this partnership between Indian Industry and BIMSTEC nations.

Dilip Chenoy
Secretary General
FICCI





EQUIPMENT DISPLAY

SEPTEMBER 15 – 16, 2018

AUNDH MILITARY STATION, PUNE, INDIA

MADE IN INDIA



INDEX

INDEX

No.	Company Name	Page No.
ALPHA DESIGN TECHNOLOGIES PRIVATE LIMITED		20
●	UNCOOLED HAND HELD WEAPON SIGHTS	21
●	NIGHT VISION MONOCULAR - IMAGE INTENSIFIER (II BASED)	22
●	RAPTOR REFLEX SIGHT	23
●	UNCOOLED HAND HELD THERMAL IMAGER - BINOCULAR	24
●	PASSIVE NIGHT VISION GOGGLE	25
●	OPTICAL SIGHT	26
●	HAND HELD / HELMET MOUNTED NIGHT VISION DEVICES	27
●	IMAGE INTENSIFIER BASED PASSIVE NIGHT VISION BINOCULARS	28
●	PASSIVE NIGHT TELESCOPIC SIGHT	29
●	CORAL CR II	30
●	TEERVA DRUSHTI	31
●	MARS	32
●	DRUSHTI	33
●	XACT TH	34
●	SOFTWARE DEFINED RADIO (SDR) BASED 8/34 MBPS RADIO RELAY	35
●	UNIT LEVEL SWITCH BOARD MK III	36
●	SOFTWARE DEFINED RADIO (SDR)	37
●	1.2 MTR FLY AWAY VSAT	38
●	TWO WAY MSS TERMINAL	39
●	NAVIC RECEIVER	40
●	DISTRESS ALERT TRANSMITTER	41
ASHOK LEYLAND LIMITED		42
●	GURU 4X4 712	43



No.	Company Name	Page No.
BHARAT ELECTRONICS LIMITED		44
●	I P MODEM	45
●	MRC COMBINER	46
●	SECURE SMART PHONE	47
●	S BAND SATCOM ON THE MOVE (SOTM)	48
●	STARS-V MK III	49
●	CELL JAMMER 5W (CJR05)	50
●	DUAL MULTI-FUNCTION CONSOLES (DMFC)	51
●	MRWS	52
●	LRF EYE-SAFE MODULE	53
●	LRF 312	54
●	LRF EOFCS - 5PPS	55
●	CUSTOMISED POWER PACKS	56
●	BATTERY: BB2590 (LI-ION)	57
●	BATTERY BB390	58
●	PASSIVE NIGHT SIGHT FOR INSAS RIFLE/LMG	59
●	PASSIVE NIGHT SIGHT FOR ROCKET LAUNCHER	60
●	PASSIVE NIGHT VISION BINOCULAR	61
●	PASSIVE NIGHT VISION GOGGLE	62
●	PASSIVE NIGHT VISION MONOCULAR	63
●	ACTIVE ELECTRONICALLY SCANNED ARRAY (AESA - SR) RADAR	64
BEML LIMITED		65
●	BEML TATRA HIGH MOBILITY 6 x 6 VEHICLE (T 815-2TDR32 6x6.1R)	66
●	BEML TATRA HIGH MOBILITY 8 x 8 VEHICLE (T 815-2TER42 8x8.1R)	67
●	BEML TATRA HIGH MOBILITY 8 x 8 VEHICLE (T 815-2TERC2 8x8.1R)	68

No.	Company Name	Page No.
	BHARAT FORGE LIMITED	69
	● DUAL TECHNOLOGY MINE DETECTOR	70
	● ATAGS	71
	CLENSTA INTERNATIONAL PRIVATE LIMITED	73
	● CLENSTA WATERLESS BODY BATH	74
	● CLENSTA WATERLESS SHAMPOO	75
	DEFENCE RESEARCH & DEVELOPMENT ORGANISATION (DRDO)	76
	● AIRBORNE EARLY WARNING AND CONTROL SYSTEM (AEW&C)	77
	● MULTI MODE HAND GRENADE	78
	● BRAHMOS WEAPON SYSTEM	79
	● JOINT VENTURE PROTECTIVE CARBINE	80
	● UNDER BARREL GRENADE LAUNCHER (UBGL) FOR INSAS & AK-47 RIFLE	81
	● PINAKA MK-III GUIDED	82
	● ANTI-SUBMARINE ROCKET	83
	● 500 KG GENERAL PURPOSE BOMB	84
	● 250 KG PRE-FRAGMENTED BOMB	85
	● 122 MM EXTENDED RANGE (ER)	86
	● ADVANCED VLF RECEIVER	87
	● SOFTWARE DEFINED RADIO MAN-PACK	88
	● GAP MEASURING DEVICE MK-III	89
	● LWPLTD	90
	● OPTICAL TARGET LOCATER	91
	● PREEMPTOR	92
	● MODULAR BULLET PROOF JACKET	93

No.	Company Name	Page No.
●	BLAST PROTECTION SUIT	94
●	BULLET PROOF OUTER VEST	95
●	BALLISTIC HELMET	96
●	BOOT ANTIMINE INFANTRY	97
●	DAKSH - PRIMAL	98
●	UXOR	99
●	DAKSH - MINI	100
●	NETRA	101
●	DAKSH -SCOUT	102
●	MOBILE SHELTER NBC	103
●	BAR MINE LAYER	104
●	MINE FIELD MARKING EQUIPMENT	105
●	SHORT SPAN BRIDGING SYSTEM	106
●	ARMOURED AMBULANCE TRACKED (AAT)	107
●	ARJUN MBT MARK I	108
●	LOW LEVEL TRANSPORTABLE RADAR	109
●	WEAPON LOCATING RADAR	110
●	3D LOW LEVEL LIGHT WEIGHT RADAR	111
●	BATTLE FIELD SURVEILLANCE RADAR	112
●	FLR/FCC	113
●	3 D MEDIUM RANGE SURVEILLANCE RADAR	114
●	TORPEDO ADVANCED LIGHT	115
●	LITHIUM ION BATTERIES	116
●	EXPENDABLE DECOY	117
●	AKASH	118

No.	Company Name	Page No.
●	ASTRA	119
●	NAG	120
●	WhAP	121
●	MDC WITH CBRN MINI UGV AND MPD	122
●	E-NASIKA	123
IDEAFORGE TECHNOLOGY PRIVATE LIMITED		124
●	NETRA V-SERIES	125
●	NETRA PRO	126
●	SWITCH HYBRID	127
L&T DEFENCE		128
●	CHEMICAL AGENT DETECTOR	129
●	RAPID DEPLOYED COMMUNICATION SYSTEM	130
●	DUAL TECHNOLOGY MINE DETECTOR	131
MKU LIMITED		132
●	C-4012	133
●	C-7008	134
●	HIGH CUT BALLISTIC HELMET	135
●	MKS-1002	137
●	JCO II E	138
●	JMT IV B	140
●	P-10016 ICW MKS-1002	142
●	MKH/ACH-4	143
●	PASGT	145
●	QUICK RELEASE PLATE CARRIER	147

No.	Company Name	Page No.
●	MKH/VD-20	149
●	MKH/ACH-4	150
●	NETRO NC - 3000 NIGHT VISION BI -OCULAR	153
●	NETRO NM - 3000 NIGHT VISION MONOCULAR	154
●	NETRO TH - 4000 HAND HELD THERMAL IMAGER	155
●	NETRO TH - 4100 THERMAL IMAGING MONOCULAR	156
●	NETRO TW - 4000 THERMAL WEAPON SIGHT	157
●	CERAZONE V	158
●	FLEXAR	159
●	POLYSHILED V	160
●	SPALLIN	161
●	TRANSPARENT ARMOUR	162
ORDNANCE FACTORY BOARD		163
●	RIFLE EXCALIBUR 5.56 MM	164
●	5.56 MM INSAS RIFLE (FOLDABLE BUTT)	165
●	RIFLE 5.56 MM INSAS (FIXED BUTT)	166
●	AMOGH 5.56MM CARBINE (JVPC)	168
●	LMG 5.56 MM INSAS (FIXED BUTT)	170
●	GUN MACHINE 7.62 MM (MAG) 2A1	172
●	ASSAULT RIFLE 7.62 MM [FIXED & FOLDABLE BUTT] (TAR)	174
●	UNDER BARREL GRENADE LAUNCHER 40 MM	176
●	84MM RCL MK-III	178
●	PISTOL AUTO 9 MM 1A	179
●	12 BORE PUMP ACTION GUN	180

No.	Company Name	Page No.
●	0.22" REVOLVER	181
●	.30 - 06 SPORTING RIFLE	182
●	REVOLVER 0.32 (7.65 MM X 23) NIRBHEEK	183
●	155-MM HE-ERFB BB	184
●	155-MM HE-ERFB BT	185
●	125 MM HEAT	186
●	MAIN BATTLE TANK AMMUNITION 120 MM FSAPDS	189
●	MAIN BATTLE TANK AMMUNITION 120 MM HESH	191
●	BOMB 120 MM MORTAR SMOKE PWP	193
●	SHELL 105 MM IFG HE	195
●	BOMB 81 MM MORTAR HE	197
●	84 MM HE 441B	199
●	84 MM HEAT 651	201
●	84 MM ILLUMINATING FFV 545	203
●	84 MM TPT 65	206
●	CARTRIDGE AA 40 MM L-70 PFFC	208
●	CARTRIDGE 30 MM ADEN GUN HE MK 2Z	210
●	CARTRIDGE 30 MM ADEN GUN PRACTICE MK2Z	212
●	30 MM BMP II AMMUNITION HE/T	214
●	30 MM BMP II AMMUNITION AP/T	216
●	30 MM BMP II AMMUNITION HE/I	218
●	CARTRIDGE RIM FIRE .22" BALL	220
●	CARTG. SA .32" REVOLVER / CARTG. SA .32" PISTOL	222
●	CARTG. SA .315"/ CARTG. SA .30" - 06	223
●	CARTRIDGE SA 12 BORE 70 MM PLASTIC ASTRAM	224

No.	Company Name	Page No.
●	CARTRIDGE SA 12 BORE 70 MM PLASTIC MAGNA	226
●	CARTRIDGE SA 12 BORE 65 MM PLASTIC DELUXE	228
●	CARTRIDGE SA 9 MM BALL	230
●	CARTRIDGE SA 7.62 MM BALL M-80	232
●	CARTRIDGE SA 7.62 MM BLANK L.A.	234
●	CARTRIDGE SA 7.62 MM TRACER M-62	236
●	7.62 MM A-7 MK-II BALL AMMN	238
●	INSAS 5.56 MM BALL AMMN	240
●	5.56 TRACER AMMUNITION	242
●	5.56 MM BALL MK N AMMN (SS 109)	244
●	CARTRIDGE 14.5 MM TRAINING AMMUNITION	246
●	CARTG SIGNAL 16MM RED/GREEN/WHITE	247
●	CARTRIDGE SIGNAL 1" RED/GREEN/ILLG.	249
●	CARTRIDGE SA 12.7 MM API AND APIT	251
●	EQUIPMENT 81 MM MORTAR	254
●	MINE PROTECTED VEHICLE	256
●	CRN 91 NAVAL GUN	257
●	EQUIPMENT 120 MM MORTAR	258
●	EQUIPMENT 105/37 IFG E1 AND 105/37 LFG E2	261
PRECISION ELECTRONICS LIMITED		263
●	2MB PCM MULTIPLEXER (Model: PFM-3440M)	264
PUNJ LLOYD RAKSHA SYSTEMS PRIVATE LIMITED		266
●	SMALL ARMS	267
●	X95 5.56 X 45MM 5.45 X 39MM 9X19MM ASSAULT RIFLE CARBINE SMG	268

No.	Company Name	Page No.
●	GALIL SNIPER 7.62 X 51 MM	269
●	TAVOR 5.56X45MM / 7.62X51MM - ASSAULT RIFLE	270
●	NEGEV 5.56 X 45MM I 7.62 X 51MM LIGHT MACHINE GUN	271
●	ACE	272
●	OPTRONICS	273
●	THROUGH-THE-WALL DETECTOR / IMAGING SYSTEMS	274
SIMULATOR DEVELOPMENT DIVISION		275
SM GROUP OF INDUSTRIES		276
●	PERSONAL PROTECTION/BODY ARMOUR SOLUTIONS	277
●	AIRCRAFT/HELICOPTER/VEHICLE/BOAT ARMOUR	278
●	ADVANCED CERAMIC B4C (CARASTOP) PLATES FOR ARMOUR	279
●	TANK AND ARTILLERY MUNITIONS	280
TATA AEROSPACE & DEFENCE		281
●	2KW FUEL CELL SYSTEM	282
●	30W FUEL CELL SYSTEM	283
●	75W FUEL CELL SYSTEM	284
●	MOBILE EMERGENCY COMMUNICATION SYSTEM	285
●	AQUILON UAV	286
●	TIME REFERENCE SYSTEM	287
●	RUGGED COMPUTER	288
●	TACTICAL RF NETWORK PLANNING TOOL	289
●	LIGHT-WEIGHT TACTICAL FIELD COMPUTER	290
●	MOBILE RUGGED COMPUTER	291
●	WEARABLE MOBILE COMPUTER	292

No.	Company Name	Page No.
●	RAJAK TWS THERMAL WEAPON SIGHT	293
●	RAJAK TBC DNL	294
●	RAJAK II-TUBE NVDS	295
TATA MOTORS LIMITED		296
●	MINE PROTECTED VEHICLE (MPV)	297
●	WHEELED AMPHIBIOUS PERSONAL CARRIER (WhAP 8x8)	299
ZEN TECHNOLOGIES LIMITED		301
●	ZEN COMBAT TRAINING CENTRE (ZEN CTC)	302
●	ZEN ADVANCED WEAPONS SIMULATOR (ZEN AWESIM)	303
●	ZEN ANTI TANK GUIDED MISSILE SIMULATOR (ZEN ATGM)	305
●	ZEN TACTICAL ENGAGEMENT SIMULATOR (ZEN TACSIM)	306
●	ZEN SMART TARGET SYSTEM (ZEN STS)	307
●	ZEN MULTI-FUNCTIONAL TARGET SYSTEM (ZEN MFTS)	309
●	MODEL OF ZEN SHOOT HOUSE	310
●	ZEN SHOOTEDGE	311
●	ZEN HAND GRENADE SIMULATOR (ZEN HE36S)	312
●	ZEN CONTAINERIZED TUBULAR SHOOTING RANGE (ZEN CTSR)	313
●	ZEN CONTAINERIZED INDOOR SHOOTING RANGE (ZEN CISR)	314



EQUIPMENT DISPLAY

SEPTEMBER 15 – 16, 2018

AUNDH MILITARY STATION, PUNE, INDIA

MADE IN INDIA



EXHIBITOR &
EQUIPMENT
PROFILES



EQUIPMENT CATALOGUE

ALPHA DESIGN TECHNOLOGIES PRIVATE LIMITED

- Address** : Interface Accolade Building, 09, Service Road,
HAL II Stage, Indiranagar, Bangalore-560008, India
- Website** : www.adtl.co.in
- Head** : H S Shankar
Chairman and Managing Director
- Telephone** : +91-80-42556909/03/04
- Fax** : +91-80-25216541
- Mobile** : +91-9845125765
- Email** : alphacorp@adtl.co.in / shankar@adtl.co.in

ORGANISATION PROFILE:

ALPHA DESIGN TECHNOLOGIES PVT. LTD (ALPHA) has its registered office in Bangalore, India and possesses Industrial Licences for development / manufacture / supply of almost all types of defence electronics, avionics, simulation, UAVs, AFV equipment & systems.

Over the years, ADTL has developed its expertise in Research & Development, manufacturing, quality assurance, evaluation and system integration for various defence products such as Fighter aircraft / Helicopters / UAVs, Avionics equipment including Missile Launch Detection System (MILDS), IFF, Optronics, LRF Based Products, Laser Target Detectors, Thermal Imagers & Fire Control Systems, Navigation, Tactical Communication, Software Defined Radios, Image Conversion, Data & Image Fusion, Radar, RF Seekers, C4ISR Systems, EW, Simulators, Microwave Components & RF Units for Indian and International markets.

The Company has set up state of the art R&D, manufacturing / production centers at Bangalore and Hyderabad to meet the requirements of Land, Ship and Air borne Defence Systems in the Country for Army, Navy, Air Force & Para Military Forces on the basis of direct Contracts from MoD. In addition, Alpha has established strong relationship with key Indian defence organizations like Bharat Electronics Limited (BEL), Hindustan Aeronautics Limited (HAL), Defence Research and Development Organisation (DRDO), Ordnance Factories and with International Customers for Defence Offsets.

Recently, ALPHA has made successful entry into Space segment by winning Contracts from ISRO for Assembly, Integration & Testing (AIT) for Satellites (IRNSS Program) and various ground Receiving Stations including up gradation of the North East States Space Application Centre for the 9 states.

ALPHA is one of the fastest growing Defence Electronics & Avionics design and manufacturing Organisation in the Private Sector. ALPHA offers its services in any / all of the above or any new tasks assigned to it to the full satisfaction of the customer.



UNCOOLED HAND HELD WEAPON SIGHTS



NETHRA Uncooled Thermal Imagers can be used as either hand-held, helmet mount or weapon-mounted sights, for ranges upto 1500 meters with different lens combinations. All the NETHRA family members are characterized by compact design, light weight, crystal clear image and reliability, even under intense operational conditions.

NETHRA-S is a compact helmet / weapon mountable, monocular uncooled thermal imaging sight. NETHRA-S can be operational for more than 6 hours in a single set of batteries and has four operational keys which can be easily accessed to control the basic operations (Polarity, E-Zoom) directly or advanced operations through an onscreen menu. NETHRA-S also has provision for low battery indication and security features to protect misuse of the system.

Main Features

- Crystal Clear Image
- Can be integrated with fire control systems
- Compact and ruggedized design

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

NIGHT VISION MONOCULAR - IMAGE INTENSIFIER (II BASED)



Model : PNVM-14

The Passive Night Vision Monocular - 14 (PNVM-14) is a unique compact, monocular night vision system based on Image Intensifier technology.

It provides a clear bright image under adverse environmental conditions and is ideal for use of military and para-military forces.

It is available in Single or Dual configuration and is also capable of being used with a helmet or without helmet (using a face mask).

It is submersible upto 20 m (optional) and powered by a single 1.5 V AA size battery (Alkaline) that gives an endurance > 24 hours.

It complies with Mil Std-810.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

RAPTOR REFLEX SIGHT



Model : RAPTOR

The battle- proven Mini reflex sight, RAPTOR is a low silhouette sight that offers a hologram like illuminated red aiming reticule with automated, real time brightness optimization.

It is equipped with a unique Always Ready To Fire (ARTF) mechanism that eliminates the need for manual On/ Off operations while minimising energy consumption.

It is the perfect day and night capable solution for infantry, special operations and law enforcement missions.

It has a Field of View > 12 degrees at 70 mm eye relief and is powered by a single 1.5 V AA Sized alkaline battery that provides about 2 months endurance.

Low battery power indication is also located within the field of view. It complies with Mil Std-810.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M:+91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

UNCOOLED HAND HELD THERMAL IMAGER – BINOCULAR



NETHRA-B is an uncooled Hand Held Thermal Imager which can view through dust, smoke, fog, haze, and other battlefield obscurants. NETHRA-B senses only heat and not light, it will not shut down or "bloom" when hit by direct light. NETHRA-B's lightweight design allows it to be used effectively as a Hand Held Thermal Imager (HHTI) for observation, border surveillance applications. NETHRA-B is ergonomically designed and easy to use with its quick access keys to essential functions. Powered by standard rechargeable batteries, it offers maximum autonomy. NETHRA-B's excellent thermal sensitivity provides the operator with outstanding target discrimination and recognition capabilities regardless of light or weather conditions

Main Features

- Uncooled HHTI with Optical Zoom & Manual Focus capabilities.
- Ergonomically Design, Compact, Light Weight & Rugged.
- Can observe target clearly under harshest environmental conditions.
- Simple 3 Key operations with graphical menu on screen.
- Powered up by commercially available batteries.
- Provision for Video & Image Storage.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

PASSIVE NIGHT VISION GOGGLE



Model : NVG-11

The Night Vision Goggle- 11 (NVG-11) is designed to provide enhanced viewing in low light conditions. The NVG uses a XD-4 Image Intensifier tube that operates by amplifying existing light using an electro- optical system. It does not require any artificial light sources.

It has following features

- Rugged
- Compact
- Light weight
- Binocular design
- Superior for extended surveillance
- Protected against excess light exposure
- Water proof
- Easy to operate
- Built in IR illuminator
- Low Battery Indicator

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

OPTICAL SIGHT



Model : Optical Sight 4x22

The Optical Sight is designed for precision aiming even during adverse light and weather conditions. Extremely high light transmission, crystal clear edge to edge image sharpness, robust and ergonomical design, make this sight very effective.

This sight is manufactured to meet the needs of Special Forces / Land Forces and is rugged enough to withstand the rigors of professional usage.

Mount design enables ease of sight's readjustment without necessitating dismounting the sight from the weapon.

Magnification - 4X.

Field of View - 8 Degrees.

Number of illumination levels of reticule - 7. MIL-STD 1913 Interface.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

HAND HELD / HELMET MOUNTED NIGHT VISION DEVICES



Model: NETHRA-B Uncooled Hand Held Thermal Imager

NETHRA is an Uncooled Thermal Sight which can view through dust, smoke, fog, haze and other battlefield obscurants. NETHRA senses only heat and not light, it will not shut down or "bloom" when hit by direct light.

NETHRA's lightweight (under 1.3 kg) design allows it to be used effectively as a Weapon Mounted Sight / Handheld Thermal Sight / Helmet Mounted Sight.

NETHRA series has various products ranging from long range application to light weight applications. NETHRA is ergonomically designed and easy to use with its quick access keys to essential functions. Powered by standard rechargeable batteries, it offers maximum autonomy.

NETHRA's excellent thermal sensitivity provides the operator with outstanding target discrimination and recognition capabilities regardless of light or weather condition.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

IMAGE INTENSIFIER BASED PASSIVE NIGHT VISION BINOCULARS



Model : PNVB 6X

Passive Night Vision Binocular 6X is a unique compact and rugged binocular night vision system based on Image Intensifier technology.

It provides a clear bright image under adverse environmental conditions and is ideal for military and para-military forces.

More than 4200 Nos have already been supplied for use by the Indian Army.

Magnification can be provided from 4x to 6x.

Diopter setting +2 to -4.

Effective range of Detection - 1000 m for group of men, 1200 m for vehicle.

Effective range of Identification - 800 m for group of men, 1000 m for vehicle.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M:+91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

PASSIVE NIGHT TELESCOPIC SIGHT



These Passive night sights for weapon applications are unique compact and rugged binocular night vision systems based on XD-4 Image Intensifier technology. They provide a clear bright image under adverse environmental conditions and are ideal for military and para-military forces. They can be designed for various field of view and for various effective ranges depending on the requirement.

Key features

- Magnifications, x: 6X
- Field of View, deg : >6
- Lens System : 100 mm F/1.5
- Focus Range, m : 5 to infinity
- Eye Relief distance, mm : 25
- Diopter Setting, D : +2 to -4
- Weight, gms : 830g (without Mount)
- Battery Type / Feed voltage, V : AA (two) Rechargeable batteries
- Overall Dimensions : 370x90 x 110 mm

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

CORAL CR II



Coral- CRII is an Advanced Hand-Held 3-5 μ m Light weight Thermal Imaging Camera with continuous Optical Zoom and Targeting Acquisition Capabilities.

Main Advantages & Features

- Advanced Real Time Image Fusion between Day & TI Channel.
- Continuous IR optical and digital zoom.
- Long-range performance.
- Advanced high resolution detector.
- Integral, day CCD cameras, digital magnetic compass, integral GPS.
- Target image and data storage memory.
- Advanced binocular viewer.
- Low acoustic noise.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M:+91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

TEERVA DRUSHTI



Teerva Drushti is a versatile multi-spectral Day, TI, SWIR system for excellent long-range observation and target acquisition. Integrating a long-range zoom, day channel, eyesafe Laser Rangefinder, GPS, magnetic compass, and mounted on a Pedestal/Standalone, Teerva Drushti is an outstanding tool for acquiring targets and engaging fire from long ranges.

Main Features

- Long-range high resolution SWIR, TI, Day Channels.
- Integral DMC, GPS and eyesafe LRF.
- High resolution OLED display; no need for diopter adjustment.
- Remote control option.
- Video recording capability 8 hours.
- Integral target data bank.
- Complete interface to C4I applications.
- Lightweight & completely dismountable.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

MARS



MARS is a versatile family of red dot reflex sights based on the state-of-the-art concept of combining an innovative, high-precision reflex sight with a single or dual-wavelength laser pointer (visible-red and/or IR) for 'round-the-clock' operational response

Main Features

- Reflex Sight and laser aiming lights are boresighted using a single control.
- No extra colour in the field of view owing to high transparency optical transmittance.
- No retro light projected to the enemy.
- Mars IR- 850 nm aiming light (Class 1 according to IEC 825-1), 0.4mW output power.
- Mars visible Red-650 nm aiming light (Class 2 according to IEC 825-1), 1Mw output power.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M:+91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

DRUSHTI



DRUSHTI is an advanced yet simple and lightweight night vision binocular for long-range observation. This low-cost device, that is easy to operate and maintain, makes it an ideal choice for ground applications. When integrated with its optional GPS and Digital Compass, DRUSHTI displays real-time dynamic data of azimuth, elevation and self-position on a high-resolution OLED display. The system can be hand-held or tripod mounted, according to operational needs.

Main Features

- Modular design for future upgrades in any combination of the optional features.
- Ideal for tactical field commanders, special forces, forward observers, HLS and peacekeeping scenarios.
- Observation through fog/smoke/dust
- Built-in continuous zoom or 3 FOVs
- High-resolution OLED display
- Ruggedized metal casing
- High survivability
- Optional Laser Pointer
- Optional Built-In GPS
- Optional Integrated Digital Compass &
- Inclinometer

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

XACT TH



Missions

Thermal Weapon Sight Product Family

- XACT th 64 Short range weapon-mounted or hand-held.
- XACT th 64 Medium range weapon- mounted or hand-held.
- XACT th 65 Marksmen clip-on sight
- Allows engagement from short ranges upto 2 km.

Main Features

- Light-weight and small dimensions.
- Genuine shutter-less uncooled thermal engine.
- Robust aluminum body
- Low battery indication-submersible to 15 meters (optional)
- Complies with Mil-STD-810

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M:+91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

SOFTWARE DEFINED RADIO (SDR) BASED 8/34 MBPS RADIO RELAY



Model : RR 8/34

Software Defined Radio based 8/34 MBPS Radio Relay is an Indigenous, state of the art equipment which provides a powerful communication platform.

This equipment is digital, software controlled, high capacity and operates with line of sight radio.

The Radio Relay is based on IDU & ODU concept which incorporates Frequency Hopping (FH) technique of 1000 hops/sec with at least 16 frequency spots for Electronic Counter-Counter Measures (ECCM).

Supports band 4 (4.4 GHz-5GHz) operations in Point to Point (PTP) and Point to Multipoint (PMP) configuration. Designed to provide current and future requirements of protected data transmission rates of 2 Mbps, 34 Mbps and 100 Mbps in Fixed Frequency (FF) & Frequency Hopping (FH) modes.

It is capable of Transporting different types of signals such as Analog, Digital, Voice/Data/Video over RF links operating through a distance of 25 Kms and above LOS with Single Hop and 40 Kms and above in Repeater mode.

A full duplex digital Engineering Order Wire (EOW) channel is provided for voice communication between the operators which works in both standalone as well as in repeater mode and this communication is secured by encryption.

It is designed to accept the interfaces such as E1, E3, Ethernet and Optical Interfaces which are multiplexed into a single stream and transmitted over RF.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

UNIT LEVEL SWITCH BOARD MK III



Model: ULSB Mk-III

The ULSB MK - III equipment is a small form factor, ruggedized, digital stored program controlled TDM switch designed to function as a unit / sub unit level PBX. Fully automatic and non-blocking, ULSB MK III supports POTS, Magneto, ISDN & E & M voice subscribers. Trunk connectivity is provided using analog and digital (TDM) interfaces. A Universal Card (UTC) provides 12 interface ports, 6 ports fixed for FXS working & balance are ports software configurable for FXS / FXO / TWT / Magneto working in any combination.

The ULSB MK - III is a state-of-the-art unique equipment which employs digital programming controls technology and time switching concept. It has the following features:-

- Modular and non-blocking.
- In built redundancy for greater survivability.
- User friendly MMI, System diagnostics.
- Flexible numbering scheme.
- Audio Visual alarm.
- Call/ Fault Statistics.
- It has versatile operator features.

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

SOFTWARE DEFINED RADIO (SDR)



Model Army SDR

To address tactical Communication requirements of Modern Battlefield, Alpha Design Technologies has developed a family of Software Defined Radio products (Handheld, Manpack and AFV Vehicular Adapter versions).

Key Benefits/Features

- Interoperability with legacy Tadiran Radios
- Operates over multiple frequency bands
- Delivers optimum combination of voice, video and high data rate communication required for mission
- Utilizes a single tactical channel for multimedia transmission
- Features intuitive design for operational efficiency
- Operates over maximum range at highest data rate
- Provides high level of immunity through TRANSEC which works through Orthogonal Synchronous Anti-Jamming scheme and COMSEC
- Ad Hoc networking (MANET) for continuous seamless operation

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

1.2 MTR FLY AWAY VSAT



Fly Away VSAT is a portable Satellite terminal for quick deployment. The VSAT terminal is fully equipped for handling high speed downloads & data transmissions to support voice & video conferencing.

The antenna drive is fully motorized for azimuth & elevation movement. The antenna of size 1.2 Mtr combined with 4 Watt BUC & LNB Provides an EIRP of 48 dBW and min. G/T of 20 dB/K the mount is designed for speed of 3 degrees per second with accuracy of 0.1 degree. The VSAT is equipped with an electronic inclinometer for obtaining true bearing and elevation

Key Features

- Light Weight & rugged design.
- Fast setup time (15 min typical)
- Integrated electronics
- DVB S2 inbound/2048 Kbps outbound
- 4Watt BUC & LNB
- Two cases, Man-portable
- External Power Pack
- Built-in compass & GPS
- IP Voice & Data capability
- Auto/Manual Tracking

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &


raghavendra.aroor@adtl.co.in



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

TWO WAY MSS TERMINAL



- Alpha Design Technologies has designed and developed a low data rate two-way MSS terminal for tracking of small boats.
- MSS based Two-way Data Terminal for Vessel Tracking is an S-band trans receiver with two-way data communications capabilities at programmable bit rates
- Mobile satellite services are known for offering extensive coverage and tracking solutions irrespective of geographic conditions. Two Way MSS Terminal for Vessel Tracking is a maritime solution for tracking bulk numbers of vessels on Ocean waters and their behavioral pattern from a control center. It is a secure way as the communication channel does not use the present dedicated wireless networks for obtaining the location of the vessels under control which in turn can assist the Control Centre Staff in identifying vessels of interests so that necessary prevention measures can be taken as part of a pro-active approach

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M:+91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in



NAVIC RECEIVER



The NavIC receiver is similar to the GPS receiver, but operates in L5 frequency, allocated to the Indian Regional Navigation Satellite System (IRNSS). The IRNSS satellites, in addition to providing timing signals for determination of NAVIC user's position, also transmit 'Emergency Messages' received from ISRO ground stations, to all the IRNSS receivers. These emergency messages, are targeted to different user groups, who receive "alerts" with warning messages from the NavIC satellites. The Navic Messaging Receiver (NMR), can be very effective for fishermen, not only to identify their own position, but also to guide them to potential fishing zones, to give warnings in case of natural calamities and to give alerts if crossing international borders, unintentionally.

The NMR is small in size, consumes low power (Long Battery life) and is very economically priced. The Bluetooth module, inside the receiver, is used to transmit the warning messages acquired from the IRNSS satellites, directly to the smartphone, using an application specially designed for the assigned purpose.

Applications:

- Navigation
- Asset Tracking
- Disaster Alert

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in

DISTRESS ALERT TRANSMITTER



DAT is INSAT based battery operated transmitter which is developed for sea going community. In case of emergency DAT transmit an emergency message which consist of [Boat ID, Boat location, Type of distress and time information] DAT transmits to INSAT-3A satellite in UHF band (402 MHz), Then Satellite relays the signal in C-band (4500 MHz), which is received by Indian coast guard Chennai for rescue operation.

Main Features

- Work at Frequency band 402.5 MHz +/- 500 KHz in steps of 1 KHz
- Power 3 ~ 7W in steps of 1W
- Programmable data rate.
- Excellent Long-Term Stability
- Low Power consumption
- Easy Integration
- Error Reporting
- Software Tunable power and frequency

Contact Person

Raghavendra Aroor

Addl General Manager, Marketing

T: +91-80-4255 6908

M: +91-9650011508

F: +91-80-2521 6541

E: alphacorp@adtl.co.in &

raghavendra.aroor@adtl.co.in



ASHOK LEYLAND LIMITED

- Address** : No.1, Sardar Patel Road, Guindy,
Chennai - 600 032, India
- Website** : www.ashokleyland.com
- Head** : S K Puri
Head - Defence Exports
- Telephone** : +91-124 -4629089
- Fax** : +91-124 -4628010
- Mobile** : +91-9717033641
- Email** : puri.sk@ashokleyland.com

ORGANISATION PROFILE:

Ashok Leyland, flagship of the Hinduja Group, is the second largest manufacturers of commercial vehicles, 4th largest manufacturers of buses in the world and 12th largest manufacturers of Trucks. Headquartered in Chennai, 9 manufacturing plants gives an international footprint - 7 in India. USD 3.2 billion (2016-17) Company, and a footprint that extends across 50 countries, we are one of the most fully integrated manufacturing companies this side of the globe. Ashok Leyland has a product range from 2.5T GVW to 49T GTW in trucks, 16 to 80 seater buses, vehicles for Defence & Special Applications, diesel engines for industrial, genset and marine applications. Ashok Leyland is also the largest vehicle supplier to Indian Army with the supply of Stallion (ALS) range of vehicles / kits for over two decades. The fleet size with the Indian Army of Ashok Leyland vehicles is over 70,000 vehicles. People, planet and profit for all stakeholders, especially our customers is at the core of Ashok Leyland which resonates with our philosophy of "AAPKI JEET, HAMARI JEET".





EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

GURU 4X4 712



Guru 4x4 712 is a light weight, general service logistics vehicle dedicated to operate in different terrains under normal weather conditions. It is fitted with H4 engine, 5 speed gear box, 2 speed AGB, fully floating axles, full air dual line brakes that provide good mobility and mane uverability.

Capability & Physical Characteristics

- GVW - 6.5T
- Engine power - 88 kW @ 2400 rpm
- Wheelbase - 3330 m
- Body type: GS load body with tarpaulin

Contact Person

S K Puri

Head - Defence Exports

T: +91-124 4629089

M: +91-97170 33641

F: +91-124 4629010

E: sk.puri@ashokleyland.com





BHARAT ELECTRONICS LIMITED

- Address** : Corporate & Registered Office Outer Ring Road,
Nagawara, Bengaluru - 560045, India
- Website** : www.bel-india.in
- Head** : Anandi Ramalingam
Director (Marketing)
- Telephone** : +91-80 2503 9300
- Fax** : +91-80 2503 9214
- Mobile** : +91-9902100666
- Email** : anandiramalingam@bel.co.in

ORGANISATION PROFILE:

Guided by a farsighted vision to make the country self-reliant in Defence electronics, Bharat Electronics Limited (BEL) was set up in Bangalore in 1954 by the Government of India under the Ministry of Defence (MoD). From a humble beginning, BEL has come a long way. It is now a Navratna PSU and India's foremost Defence electronics company.

BEL is a multi-product, multi-technology, multi-Unit conglomerate which supplies over 350 products in the areas of Radars, Missile Systems, Military Communications, Naval Systems, Electronic Warfare & Avionics, C4I Systems, Electro Optics, Tank Electronics & Gun/Weapon System Upgrades, Solar Photovoltaic Systems, Electronic Components and civilian products.



IP MODEM



BEL IP Modem is a device to connect two IP networks seamlessly over LOS/Satellite Link. The modem uses latest DVB-S2 technology to provide best use of link bandwidth. Latest generation of FEC codes like LDPC and BCH are used to provide better link margin compared to earlier generation codes of RS and Viterbi. Faster Roll-off rates as low as 0.20 are supported for better channel utilization.

- SCPC DVB-S2 modem with Ethernet Interface
- Compliant to DVB-S2 standard (for Modulation, Error Correction and coding).
- FEC codes - LDPC+BCH
- 100 Mbps raw throughput at 30MSPS symbol rate over 36MHz Channel BW.
- L-Band (950-2150 MHz) operation
- Generic Stream Encapsulation for low encapsulation overhead
- PC based Configuration
- FPGA based Signal processing
- Low power consumption
- SNMP Based Remote Monitoring.

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

MRC COMBINER



The MRC combiner is used for Tropo communication system. This unit receives the diversity signals from the receive antennas and improves the Signal-to-Noise ratio and also removes the frequency selective fading encountered in the Tropo channel. The improved signal is given to a Modem for demodulation.

- Combines up to four receive channel
- SNR improvement is about 8 dB
- Multipath mitigation by Adaptive Equalization
- Wide Dynamic Range RF Input AGC of 70 dB
- Performs Symbol and Carrier Synchronization
- Throughput up to 20Mbps
- Bar Graph based Signal Level Monitor
- FPGA based Signal processing
- SNMP Based Remote Monitoring.

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

SECURE SMART PHONE



BEL in-house secure smart phone provides end to end security between two mobile handsets over 3G GSM/ CDMA network. The secure tactical application works on VOIP (voice over IP) technology to manage the delivery of voice information over the mobile network. BEL's in-house secure smart phone is also provided with secure storage and tamper proofing.

- Android 4.0 (ICS)
- Support for 3G network (GSM / CDMA)
- Secure voice call and Messaging
- End-to-End Encrypted VOIP with Proprietary Encryption
- Supports Clear voice, SMS and browser
- Encryption key is destroyed as soon as the call ends
- Secure voice call requires approximately 8 kbps Bandwidth which makes it suitable for use under low network speed conditions.
- Access Control using Password
- Call establishment using SIP (session initiation protocol)
- Password protection for Crypto data loading
- Local/Remote Key Erasure facility provided
- Customized User Interface

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190


E: imd@bel.co.in



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

S BAND SATCOM ON THE MOVE (SOTM) A JOINT DEVELOPMENT BY DEAL & BEL



Major Features: Fast, Reliable and Secure Communication on the Move & Pause Ruggedized; Withstand in Harsh Environment Low Profile Suitable to mount on any Land based vehicle Work in an Off Road environment Power backup for 1 hour with super silent Genset

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in



STARS-V MK III



STARS-V MK III is a Next Generation, Multi-band, High data rate, IP radio with Mobile Ad hoc Networking (MANET) functionality. The radio works in wide frequency band in V/UHF range of 30 - 512MHz. The radio works in Frequency Hopping (FH) and Fixed Frequency (FF) modes with built-in-high-grade digital secrecy in voice and data modes. The radio is built around latest state of the art hardware using DSP and FPGA.

The radio is backward compatible with STARS-V MK II radio in Clear, Secure and Frequency Hopping modes of operation. The radio is designed as 10W man pack transceiver and has in-built MANET feature supporting up to 64 nodes. The network is self-forming and self-healing and support network throughput up to 1Mbps.

- State of the art software intensive IP radio
- Frequency Range: 30 MHz to 512 MHz
- IP based Mobile ADHOC Networking (MANET) upto 64 nodes
- Self configuring, Self healing network
- Frequency Hopping: 500 Hops / second.
- Data rate: upto 1Mbps network throughput
- Built in encryption
- Waveform loading through Front Panel
- Robust connectivity for n/w centric operations in tactical battle field conditions.
- Simultaneous voice & Data services
- Selective / Group Calling

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

CELL JAMMER 5W (CJR05)



The low power cellular Jammer instantly blocks and paralyzes cell phone operations in CDMA, GSM (900 and 1800 MHz), 3G, Wi-Fi & Bluetooth and 4G bands in limited defined areas. Once the cellular Jammer is on, all types of cellular activities in the surroundings (including incoming and outgoing calls, SMS, picture sending, etc.) are jammed. Effective jamming range depends upon the site terrain and cellular signal strength at the site. The low power equipment is primarily designed considering the health safety standards and Indian working conditions.

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

DUAL MULTI-FUNCTION CONSOLES (DMFC)



Dual Multi-Function Consoles (DMFC) is ergonomically designed single-operator console, built on state of the art technology. DMFC consists of two wide screen displays placed one above the other for display of required information. Touch Input Display (TID) and Keyboard is provided for data entry. Tracker ball allows seamless movement of cursor from primary screen to secondary screen and vice versa.

- Displays: Two 24" displays
- Computing Unit: Server based on latest embedded dual Xeon processor and add-on dual output graphics card for dual Displays. RHEL operating system
- Operating system: RHEL
- Ethernet Switch: Rack mount L2/L3 managed switch for external interface
- Man machine interface (MMI) desk for operator action and selection

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

MRWS



MRWS "Trinetra" is a weapon sight indigenously designed & developed by BEL Pune. It is Compact, Light Weight, Parallax free and Rugged Weapon Sight for instant Target acquisition. "Trinetra" is equipped with Laser Spot Designators, making it an all in one versatile sight for all possible combat operation scenarios.

- Standard Picatinny Mount.
- In-built Visible Laser Spot Designator.
- Infrared Laser Spot Designator (Optional).
- Powered by commercially available battery.
- Lightest in its category.
- Combined Zeroing Mechanism

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

LRF EYE-SAFE MODULE



Eye Safe, Laser Range Finder, Modules comprise of Trans-Receiver and Power supply modules. Designed for integration in EO pay loads to measure the distance of target up to 20 Km accurately and instantaneously. Mechanical mounting reference enables easy alignment with pay load sensors.

- Compact Design and Simple to operate
- Range: Max-20Km, Min-100m with accuracy of $\pm 5m$
- Measuring Frequency: one shot every 10 seconds
- Built in Test facility

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

LRF 312



Laser Range Finder Eye safe Class-1 (LRF-312) is a lightweight LRF designed to measure the distance of target up to 20 Km range accurately and azimuth / Elevation instantaneously.

- Class-1 Eye safe
- Range: Max-20Km, Min-80m with accuracy of $\pm 5\text{m}$
- Measuring Frequency: 5 Hz continuous
- Built-in Compass and Inclinator (Optional)
- Remote readout, Remote Triggering through RS422 / RS232 selectable Serial Interface

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

LRF EOFCS - 5PPS



Laser Range Finder, Eye Safe - EOFCS is compact and light weight equipment, which enables the user to measure distances to non-cooperative targets. It can be integrated with Day or Night Sights and incorporates a CCD camera for bore sighting with other sensors.

- Compact Design and Simple to operate
- Range: Max-20Km, Min-200m with accuracy of $\pm 5m$
- Measuring Frequency: 5 Hz continuous
- Built in Test facility
- Complied to Military Stds

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

CUSTOMISED POWER PACKS



- Customised Power packs for various communication, surveillance and special purpose instruments used by Indian Armed and Paramilitary Forces.
- Both rechargeable and non-rechargeable types (Li-ion, Ni-Cd, Ni-MH, Li-SO₂, Li-MnO₂, LTC).
- Complied to Mil standards.
- Compact, Light Weight and Rugged
- High Energy density and low self discharge rate
- Safe application with efficient Power Mgmt system
- Stable Performance over wide/extended temperature range
- State of charge indicator for rechargeable batteries (Optional)

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

BATTERY: BB2590 (LI-ION)



This battery is compact, lightweight & consists of cylindrical Lithium Ion cells. It is intended for powering Singgars & ATCS, FALCON, KY-57, MXF430, PRC-119 used mainly in NATO countries.

- Rugged & High performance
- Provided with efficient power management system
- Long Cycle Life & High Energy Density
- Wide Operating Temperature Range
- Designed to meet requirements of MIL-PRF-32052

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

BATTERY BB390



This battery is compact, lightweight & consists of Lithium Ion cells. It is intended for powering Communication equipments like Singgars (PRC-119,104), FALCON (PRC-138, 117), MXF430 & other equipments.

- Rugged & High performance
- Built with Safety Vented cells
- Long Cycle Life & High Energy Density
- Wide Operating Temperature Range
- Designed to meet requirements of MIL-PRF-32052

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

PASSIVE NIGHT SIGHT FOR INSAS RIFLE/LMG



Advanced passive night sight is a weapon sight system designed to be mounted on different assault rifles / INSAS Rifle / LMG. Its innovative design enables users to lower the distance between the weapon and sight. LOS resulting more comfortable aiming position. An illuminated Red Cross reticule with switchable brightness levels maintains reticule definition allowing fire control for target engagement.

Features

- Strain free viewing
- II Tube with built in bright source protection, reverse polarity protection & Automatic Brightness Control (ABC)
- 5 positional illumination control resistant
- Light weight, compact and rugged

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

PASSIVE NIGHT SIGHT FOR ROCKET LAUNCHER



Passive Night Sight is a passive night system designed to be mounted on different rocket launchers. Its innovative design enables users to lower the distance between the weapon and sight. LOS resulting more comfortable aiming position. An illuminated red cross reticle with switchable brightness levels maintains reticle definition, allowing fire control for target engagement.

Features

- Strain free viewing
- II Tube with built in bright source protection, reverse polarity protection & Automatic Brightness Control (ABC)
- Light weight, compact and rugged

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

PASSIVE NIGHT VISION BINOCULAR



Passive Night Vision Binocular is a lightweight, durable, water proof and compact night vision device. It is a single tube full field binocular system. It is fitted with XD-4 (Autogated) High Performance Tube and adjustable eyepiece. It is an ideal device for surveillance, patrolling and reconnaissance in the night.

Features

- Full field viewing
- Compact and ergonomic
- Autogated II Tube with built in bright source protection, reverse polarity protection and Automatic Gain Control (AGC)
- Hermetical sealing
- Inter-ocular and Dioptic adjustment
- Infra Red illuminator
- Low battery Indicator
- Bright light cut off facility while exposing high light.
- Water resistant at 1 meter deep for 30 minutes

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

PASSIVE NIGHT VISION GOGGLE



Advanced Passive Night Vision Goggle is a lightweight, durable, water resistant and compact night vision device. It is a single tube full field binocular system. It is fitted with High performance Autogated XD4 II Tube and adjustable eyepiece. It is an ideal device for surveillance, patrolling and reconnaissance in the night.

Features

- Full field viewing
- Compact and ergonomic
- Autogated II Tube with built in bright source protection, reverse polarity protection and Automatic Brightness Control (ABC)
- Hermetical sealing with nitrogen filling and water resistant
- Inter-ocular and Dioptic adjustment
- Infra Red illuminator for map reading
- Low battery Indicator
- Bright light cut off facility
- Operates on 1.5V AA size batteries

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

PASSIVE NIGHT VISION MONOCULAR



Night Vision Monocular is light weight device capable of being used as a hand held viewer, face & helmet mounted for night patrolling and surveillance and night firing. It is easily used as a hand held viewer, face & helmet mounted. It is provided with an Infrared Laser illuminator for use in totally dark environment for recognition of ranges of 125 mtrs or better.

Features

- Strain free viewing
- Military Grade II Tube with built in bright source protection, reverse polarity protection & Automatic Brightness Control (ABC)
- Works with Commercially available Primary / rechargeable btys
- Battery will run at least 8 hrs

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

ACTIVE ELECTRONICALLY SCANNED ARRAY (AESA – SR) RADAR



The BEL's AESA-SR30 is an advanced Active Electronically Scanned Array(AESA) radar effective against the detection and tracking of crawling man, single man, group of men and small, medium and large vehicles. The advanced Electro Optical system enables it to perform passive surveillance throughout day and night. It is a lightweight and man-portable ground-surveillance radar that can be controlled and operated remotely through wired or wireless communication. System versatility allows for tripod, mast, tower or any other elevated static platform. It is highly effective in variety of harsh environments. It provides Superior accuracy, both in range and azimuth, allows for better performance with classification and identification of targets.

- Operates under all-weather conditions
- Very Quick and easy deployment of the system
- Highly reliable system as there are no moving parts
- Remote operation capability
- Enhanced display, PPI and B-Scope, digital map, clutter map and graphics-on-color display
- Automatic TWS
- Target identification via audio Doppler tones
- Auto Classification of targets

Contact Person

General Manager

International Marketing Division

Bharat Electronics Limited

(A Govt. of India Enterprise, Ministry of Defence)

Management Block, Jalahalli P.O, Bangalore - 560 013, India

T: +91-80-2838 5629 / 6031

F: + 91-80-28380190

E: imd@bel.co.in

BEML LIMITED

- Address** : BEML Limited, 5th Floor, Unity Building,
J.C. Road, Bangalore -560002, India
- Website** : www.bemlindia.in
- Head** : R H Muralidhara
Director (Defence Business)
- Telephone** : +91-80-22224458
- Fax** : +91-80-22224456
- Mobile** : +91-9945318237
- Email** : office@dd.beml.co.in

ORGANISATION PROFILE:

BEML Limited (formerly Bharat Earth Movers Limited) was established in May 1964 as a Public Sector Undertaking for manufacture of Rail Coaches & Spare Parts and Mining Equipment at its Bangalore Complex. BEML Limited, a 'Miniratna-Category-1', plays a pivotal role and serves India's core sectors like Defence, Rail, Power, Mining and Infrastructure. The Company started with a modest turnover of Rs. 5 Cr during 1965 and today, thanks to its diverse business portfolio, the company has been able to achieve a turnover of more than Rs.3,500 Cr.

The Company operates under three major Business verticals viz., Mining & Construction, Defence and Rail & Metro. The Company has state-of-the-art manufacturing facilities at Bangalore, Kolar Gold Fields (KGF), Mysore and Palakkad.

Being India's leading Defence equipment manufacturer, BEML Limited keeps the Indian Army and other Defence forces abreast with state-of-the-art military equipment. The company manufactures variants of BEML Tatra vehicle for all terrain operations including Bridge Layer, Field Artillery Tractor, Medium & Heavy Recovery Vehicle, Pontoon Mainstream Bridge Systems, Crash Fire Tenders, Mobile Mast Vehicle, etc.

BEML also supplies Engineering Mine Ploughs, Tank Transportation Trailers, Weapon Loading equipment, Armoured Recovery Vehicle, Mil-rail Coaches and Wagons. BEML plays a stellar role in the country's Integrated Guided Missile Development Project by supplying ground support vehicles. The company has also created a world class test track at its KGF Complex to test Defence equipment and vehicles.



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

BEML TATRA HIGH MOBILITY 6 x 6 VEHICLE (T 815-2TDR32 6x6.1R)



BEML TATRA High Mobility 6x6 Vehicle is used for GS role in Indian Army. This is an all-terrain vehicle intended for transport of personnel and is having a payload capacity of 15700kgs. The vehicle is used for towing trailers on public roads upto 65,000 kg and in off road conditions trailer weighing upto 16,000 kg.

The equipment is provided with a winch for self-recovery and recovery of other vehicles. Also the vehicle is provided with centralized tyre inflation system inside the cabin which enables inflation / deflation of tyres depending on terrain conditions.

Characteristics of Equipment

- GVW – 28000 kgs
- Engine power - 270 kW Euro 3
- Wheelbase - 3270 mm
- Body type: GS load body

Contact Person

A K Srivastav

CGM (Defence Business)

T: +91-80-22963522

M: +91-9902421965

F: +91-80-22963520

E: mi@beml.co.in



BEML TATRA HIGH MOBILITY 8 x 8 VEHICLE (T 815-2TER42 8x8.1R)



BEML TATRA High Mobility 8x8 Vehicle is an all-terrain vehicle used for mounting superstructure such as RADAR systems, Bridge laying system in Indian Army. The vehicle is also used for transport of personnel and is having a payload capacity of 17300 kg. The vehicle is used for towing trailers on public roads upto 65,000 kg and in off road conditions trailer weighing upto 16000 kg.

The equipment is provided with a winch for self-recovery and recovery of other vehicles. Also the vehicle is provided with centralized tyre inflation system inside the cabin which enables inflation / deflation of tyres depending on terrain conditions.

Characteristics of Equipment

- GVW – 32000 kgs
- Engine power - 325 kW Euro 4
- Wheelbase - 2970 mm

Contact Person

A K Srivastav

CGM (Defence Business)

T: +91-080-22963522

M: +91-9902421965

F: +91-080-22963520

E: mi@beml.co.in

BEML TATRA HIGH MOBILITY 8 x 8 VEHICLE (T 815-2TERC2 8x8.1R)



BEML TATRA High Mobility 8x8 Vehicle is an all-terrain vehicle used for mounting superstructure, towing trailers, Bridge laying system in Indian Army. The vehicle is also used for transport of personnel, towing of MBT trailers and is having a payload capacity of 17050 kg. The vehicle is used for towing trailers on public roads upto 65,000 kg and in off road conditions trailer weighing upto 16000 kg.

The equipment is provided with a winch for self-recovery and recovery of other vehicles. Also the vehicle is provided with centralized tyre inflation system inside the cabin which enables inflation / deflation of tyres depending on terrain conditions.

Characteristics of Equipment

- GVW - 32000 kgs
- Engine power - 325 kW Euro 4
- Wheelbase - 2970 mm

Contact Person

A K Srivastav

CGM (Defence Business)

T: +91-80-22963522

M:+91-9902421965

F: +91-80-22963520

E: mi@beml.co.in



BHARAT FORGE LIMITED

Address : Mundhwa
Pune Cantonment - 411036, India

Website : www.bharatforge.com

Head : Rajinder Singh Bhatia

Telephone : +91-20-6704 2868

Fax : +91-20-2682 1250

Mobile : +91-9011050256

Email : mohit.singh@bharatforge.com

ORGANISATION PROFILE:

Bharat Forge Limited (BFL), the flagship company of Kalyani Group is a technology driven global leader in metal forming having transcontinental presence and serving several sectors including automotive, power, oil and gas, construction & mining, locomotive, marine, defence and aerospace. It offers full service supply capability to its geographically dispersed marquee customers from concept to product design, engineering, manufacturing, testing and validation. Combining its competencies in engineering, design and technology with best-in-class, world-scale manufacturing capacities and skills have transformed BFL from a component supplier to an innovation led, end-to-end solutions provider and a dynamic partner to customers, providing 'partner to print' solutions. It is India's largest manufacturer and exporter of automotive components and leading chassis component manufacturer in the world. In its defence profile, BFL has realised major breakthrough in Artillery Systems and continues to vigorously pursue its exploits in AFV, Protected Vehicles, Ammunition, Missiles and AD, and Defence Electronics.



DUAL TECHNOLOGY MINE DETECTOR



The DTMD-BFL is a Dual Sensor Detector comprising of integrated Metal Detector (MD) and Ground Penetrating Radar (GPR).

The electronics of both systems are housed in a compact metal casing. A telescopic pole links the electronics unit to the search head. The search head contains a Metal Detector coil and the GPR antennas. Both systems can be switched ON and used separately or together and will not influence each other.

Both detection signals (MD+GPR) are communicated to the operator acoustically via the integrated loudspeaker.

The acoustic signal of the GPR differs from the Metal Detector signal by a large difference in pitch, i.e. the radar uses a very low frequency tone and the Metal Detector uses a very high frequency tone. Furthermore, the MD and GPR signals have different acoustic features, which facilitate the differentiation of their alarms.

Specifications of Equipment

Measuring principle:	Dual Sensor MD + GPR
Weight	≤ 5kgs (with battery pack)
Telescopic bar length:	≤ 1.7m; adjustable
Power supply:	Rechargeable NiMH batteries
Power consumption:	< 5W
Operation temperature:	-10°C to +42°C

Contact Person

Mohit Singh

Associate Vice President

T: +91-20-6704-2387

M: +91-9011050256

F: +91-20-2682-1250

E: mohit.singh@bharatforge.com

ATAGS



Advanced Towed Artillery Gun System (ATAGS) is an indigenously manufactured 155mm/52 calibre best-in-class artillery system, jointly designed and developed with ARDE (DRDO). Kalyani Group has developed the Gun structure, Gun Control and Automation, Barrel and Breech and Battery Command Post in the ATAGS, thus realizing the total gun system. The futuristic and technically superior breech, with higher service pressure can withstand up to 560Mpa. During the trial firings at Pokhran Ranges, the ATAGS variant developed by Kalyani Group, set a new record by registering the longest ever distance of 48.074 kms, surpassing the maximum ranges of 35-40 kms fired by any artillery gun system in this category. The ordnance including barrel and breech mechanism, on both variants of ATAGS, has been developed at Kalyani Group Advanced Artillery Manufacturing Facility.

Specifications of Equipment

- 155mm 52 Caliber Gun System
- Achieved World Record firing range in the 155mm family - 48.074kms (HE-ERFB-BB) and 38.569 km (HE-ERFB-BT)
- Zero backlash Electrical drives: Hydro-electric gun system
- The system can be able to fire Zone 7 charge
- Fire: any type of ammunition
- Steering: Steer-by-wire method for manoeuvring the artillery
- Self-propelled capability with a speed of 20 kmph
- Ability to ride at Towing vehicle's speed during towed mode
- Deployment time: 1 minute in day, and 1.5 minute in night



- Fully automatic Ammunition Handling System (AHS) enables firing six successive rounds and has manual backup arrangement

Elevation and Traverse

- Elevation: -5° to $+75^{\circ}$ with the speed of $5^{\circ}/s$
- Traverse: $\pm 30^{\circ}$

Rate of Fire

- Burst rate of fire: 4 rounds in 30 Sec
- Intense rate of fire: 16 rounds in 3 min
- Sustained rate of fire: 42 rounds in 1 hr

Contact Person

Mohit Singh

Associate Vice President

T: +91-20-6704-2387

M:+91-9011050256

F: +91-20-2682-1250

E: mohit.singh@bharatforge.com





EQUIPMENT CATALOGUE

CLENSTA INTERNATIONAL PRIVATE LIMITED

Address : 9,10, 4th Floor, BBIF, Synergy Building, IIT Delhi, Hauz Khas
New Delhi -110016, India

Website : www.clensta.com

Head : Puneet Gupta

Telephone : +91-11-26581765

Mobile : +91-9910301069

Email : puneet@clensta.com

ORGANISATION PROFILE:

Clensta International (IIT Delhi Partnered Venture - Providing Waterless Personal Hygiene Solutions and other Innovative products)

Clensta is an Indian startup and in association with IIT Delhi, one of the leading technology institutions in India, has been working to create innovative healthcare solutions to make hygiene accessible for anyone, anytime and anywhere. The inspiration for Clensta came from the visible need to make personal hygiene accessible at locations with scarcity of water. Our mantra of 'clean instantly' is driven by our aim to create products that promote complete and instant cleaning solutions without the use of water and to provide innovative solutions to everyday problems.

We've been fortunate to have receive appreciation by The Honorable President of India Shri Ram Nath Kovind and have also gained recognitions across the U.S. Embassy (Delhi), the Indian Biotech community & many more.

Addressable Concerns

- Hygiene problems for soldiers in extreme weather conditions on ground ship or under water
- Inaccessibility to hygiene at places with scarcity of water
- Personal hygiene problems for disaster hit areas
- Known concerns with sponge bathing for patients
- Maintaining personal hygiene for travel enthusiasts



CLENSTA WATERLESS BODY BATH



Clensta Waterless Body Bath - Alternate bathing solution

Characteristics

- No Water required
- No Alcohol, no SLS & no Gluten free
- Removes body odor
- Makes skin clean and fresh

WATERLESS BODY BATH	
Physical State	Liquid
pH	7 +/- .5
Odour and Appearance	Clear Liquid. Baby Powder #4014 Antiallergenic
Solubility	Soluble in Water

Contact Person _____

Puneet Gupta

CEO & Founder

T: +91-11 - 26581765

M: +91- 9910301069

E: puneet@clensta.com

CLENSTA WATERLESS SHAMPOO



Clensta Waterless Shampoo – Anytime Accessible Hygiene

Characteristics

- No Water required
- No Alcohol, no SLS & no Gluten free
- Removes dirt, dust & oil
- Smooth & shiny conditioned hair

WATERLESS SHAMPOO	
Physical State	Liquid
pH	6 +/- .5
Odour and Appearance	Clean & Fresh # 8515 Antiallergenic
Solubility	Soluble in Water

Contact Person _____

Puneet Gupta

CEO & Founder

T: +91-11 - 26581765

M: +91- 9910301069

E: puneet@clensta.com



DEFENCE RESEARCH & DEVELOPMENT ORGANISATION (DRDO)

- Address** : DPI, DRDO HQrs, DRDO Bhawan
Rajaji Marg, New Delhi 110 011, India
- Website** : www.drdo.gov.in
- Head** : Secretary, Department of Defence R&D
and Chairman, DRDO
- Telephone** : +91-11-23011073
- Fax** : +91-11-23007636
- Email** : dpidrdo@hqr.drdo.in

ORGANISATION PROFILE:

Defence Research & Development Organisation (DRDO) works under Department of Defence Research and Development of Ministry of Defence. DRDO is dedicatedly working towards enhancing self-reliance in Defence Systems and undertakes design & development leading to production of world class weapon systems and equipment in accordance with the expressed needs and the qualitative requirements laid down by the three services.

DRDO is working in various areas of military technology which include aeronautics, armaments, combat vehicles, electronics, instrumentation engineering systems, missiles, materials, naval systems, advanced computing, simulation and life sciences. DRDO while striving to meet the Cutting edge weapons technology requirements provides ample spinoff benefits to the society at large thereby contributing to the nation building.



AIRBORNE EARLY WARNING AND CONTROL SYSTEM (AEW&C)



AEW&C system is a potent force multiplier, providing surveillance, tracking, identification and classification of the Airborne/Sea surface targets. The information from multiple sensors are collated, associated and fused to provide a cogent and comprehensive air situation picture on configurable consoles. Further capabilities include threat assessment and enabling the interception of the hostile targets through guidance of own interceptor.

Characteristics of Equipment

- Active Electronically Scanned Array for Primary Radar(PR)
- Identification of Friend & Foe(IFF) Radar
- Electronic Support Measure(ESM) and Communication Support Measure(CSM) for detection of hostile air defenses
- Satcom & line of sight Voice and Data Communication System
- Self-Protection Suit for safe operation
- Mission Communication System for Air-to-Air, Air-to-Ground V/UHF voice
- Five Operator Workstation and Five rest crew seats
- Extendable Endurance with In-Flight refueling(IFR)
- Dedicated APU's for Mission Avionics
- Fuel Efficient Regional Jet aircraft platform
- Tactical Battle Management Software

Lab Responsible

Centre for Airborne Systems (CABS)
Belur Complex, Bengaluru - 560037

MULTI MODE HAND GRENADE



Multi Mode Hand Grenade is developed to overcome the shortcomings of existing M36 grenade. Multi Mode Hand Grenade can be used in two modes i.e. Offensive mode and Defensive mode depending upon the tactical requirement of users. The two modes can be changed easily from one to another by removing/applying fragmenting sleeve.

Characteristics of Equipment

- Modular design
- Multimode concept: Offensive mode, Defensive mode
- Uniform fragmentation pattern with higher density
- Additional thrower safety (Safety Release Delay Mechanism)
- High reliability and convenient to handle and use.
- Designed delay of 3.5 to 4.5 seconds for detonation after release.
- Safe for Para-dropping in primed condition.
- Ease in priming and un-priming.

Technical Parameters:

Technical Parameters	Mode of Operation	
	Offensive	Defensive
Weight	260 g	495 g
Length	139 mm	139 mm
Diameter	46 mm	63 mm
No. of fragments	Nil	Approx 3800
Lethal Radius	3 - 5 m	8 - 10 m

Lab Responsible

Terminal Ballistics Research Laboratory
Sector-30, Chandigarh - 160003

BRAHMOS WEAPON SYSTEM



BRAHMOS is a two-staged, universal, supersonic cruise missile having flight range of up to 290-km with top speed of Mach 2.8. It operates on 'Fire and Forget Principle', adopting variety of flights on its way to the target. Its cruising altitude could be up to 15 km and terminal altitude to be as low as 10 meters. It can carry conventional warhead weighing 200 to 300 kgs.

Characteristics of Equipment

The BRAHMOS Supersonic Cruise Missile has:-

- 3 times more velocity
- 2.5 to 3 times more flight range
- 3 to 4 times more seeker range
- 9 times more kinetic energy

Lab Responsible _____

BrahMos Aerospace 16, Cariappa Marg, Kirby Place
Delhi Cantonment, New Delhi -110010

JOINT VENTURE PROTECTIVE CARBINE



The next generation MSMC is the Joint Venture Protective Carbine with more accuracy, reliability, endurance, robustness and manoeuvrability. This is a unique calibre (5.56X30mm) weapon for short range operations. Its low recoil provides stabilized firing during rapid firing and can be fired by single hand. It has ambidextrous features for cocking handle and a retractable butt for balanced firing which is most suitable for concealed area operations.

Characteristics of Equipment

- A unique calibre weapon system for CQB operations.
- Compact, Light weight & Robust.
- Highly accurate in single shot & burst mode.
- Semi bull-pup configuration to facilitate single hand firing capability.
- Low weapon recoil ensures stabilized weapon during rapid firing mode.
- Retractable butt for compactness & better balance.
- Three point sling for quick weapon positioning in different firing postures.
- Ambidextrous features in fire selector, Plunger butt lock - enables left as well as right hand firing. Reflex cum visible laser Sight mounted on Picatinny 1913 rail.

Lab Responsible

Armament Research & Development Establishment (ARDE)
Dr. Homi Bhabha Road, Armament Post Pashan, Pune - 411021

UNDER BARREL GRENADE LAUNCHER (UBGL) FOR INSAS & AK-47 RIFLE



40 mm Under Barrel Grenade Launcher (UBGL) developed by ARDE is an add-on attachment to the INSAS and AK47 Rifle. The launcher is made up of aluminium alloy. It can fire all types of grenades up to a range of 400m. The lethal radius of the grenade is 5m. It is effective against enemy soldiers hiding in bunkers or behind walls. It is inducted into Indian Army.

Characteristics of Equipment

- Modular design, three-point attachment to INSAS Rifle
- Applied & Mechanical safety
- Breech loading enables easy loading of grenade
- Pump action makes extraction of cartridge case easy
- Fires common ammunition with in-service MGL
- Fills tactical gap between max range of hand grenade and min range of mortar

Lab Responsible

Armament Research & Development Establishment (ARDE)
Dr. Homi Bhabha Road, Armament Post Pashan, Pune - 411021

PINAKA MK-III GUIDED



Guided Pinaka rocket is an Artillery rocket system having a maximum striking range of 80 km with a precision of < 30 m. With its family of highly lethal warheads it can neutralise wide variety of enemy targets while minimising collateral damage. Guided Pinaka rockets are highly cost effective.

Characteristics of Equipment

- Calibre: 214 mm, Range: 20-80 km, Accuracy < 30 m
- Miniaturized GNC kit housed in warhead ogive
- INS + GPS based Guidance, MEMS INS based Navigation, Canard based Control
- Warheads: Monolithic and sub-munition
- Launched from in service Pinaka launcher system

Lab Responsible

Armament Research & Development Establishment (ARDE)
Dr. Homi Bhabha Road, Armament Post Pashan, Pune - 411021

ANTI-SUBMARINE ROCKET



ARDE has successfully developed the Extended Range Anti-Submarine Rocket (ER-ASR) to enhance the range of existing RGB-60 Anti-submarine Rocket from 5.3 km to 8.5 km. ERASR consists of two motor propulsion systems which can fire the rocket in Short Range mode and Long Range mode to achieve different range capabilities

Characteristics of Equipment

- Physical parameters:
 - Caliber: 212 mm, Length: 1830mm, Mass :113 kg
- Propulsion: Case Bonded Composite Propellant (FORE Motor) and Cartridge loaded Extruded Double Base Propellant (AFT Motor)
- Warhead: Underwater Blast Explosion
- Warhead Composition: Insensitive HE Composition (PBX based)
- Maximum Range: 8.5 km in Long range mode (Ballistic 2 mode) and 3.0 km in Short range mode (Ballistic 1 mode)
- Operating Temperature Range: -5° C to +55° C

Lab Responsible

Armament Research & Development Establishment (ARDE)
Dr. Homi Bhabha Road, Armament Post Pashan, Pune - 411021

500 KG GENERAL PURPOSE BOMB



This bomb is a preformed fragmentation bomb in which 15 mm steel balls are used as fragments. The bomb can be carried on both the Russian and NATO origin aircrafts. The bomb is initiated at a height of 9m using a Proximity Fuze. The Bomb is undergoing qualification.


Characteristics of Equipment

- Dimensions: Length-2380 mm, Dia.-400 mm
- Mass: 470 kg
- Filling: Dentex (116 kg)
- Type: Preformed Fragmentation
- Targets: Parked aircrafts, light armoured vehicles, troop concentrations

Lab Responsible

Armament Research & Development Establishment (ARDE)
Dr. Homi Bhabha Road, Armament Post Pashan, Pune - 411021

250 KG PRE-FRAGMENTED BOMB



This bomb is a preformed fragmentation bomb in which 8 mm steel balls are used as fragments. The bomb can be carried on both the Russian and NATO origin aircrafts. The bomb is initiated at a height of 9 m using a Proximity Fuze. The Bomb is in service and under production at Ordnance Factories.

Characteristics of Equipment

- Dimensions: Length-1425 mm, Dia.-325 mm
- Mass: 250 kg
- Filling: Dentex (33 kg)
- Type: Preformed Fragmentation
- Targets: Parked aircrafts, light armoured vehicles, troop concentrations

Lab Responsible

Armament Research & Development Establishment (ARDE)
Dr. Homi Bhabha Road, Armament Post Pashan, Pune - 411021

122 MM EXTENDED RANGE (ER)



122 mm ER rocket is an indirect fire, free flight artillery rocket system designed to deliver large volume of fire over range of 40 km. These rockets are designed to fire from BM-21 launcher system. Rocket can deliver monolithic PF warhead on target using improved case bonded composite propellant based propulsion system. Wrap around fin stabilizer system provides the desired stability to the rocket throughout its flight.

Characteristics of Equipment

- Calibre: 122 mm
- Range: Minimum 9.3 km, Maximum 40 km
- Weight of rocket: 67.1 kg
- Weight of propellant: 27 kg
- Weight of warhead: 20.5 kg
- Length of rocket: 2937 mm
- Operating temperature range: -30° C to +55° C
- Fuze: Turbo powered, Proximity/ Point Detonating
- Brake ring: 1
- Propellant: HTPB based solid composite
- Nozzle end ignition
- Accuracy & Consistency: 1.5% of Range (Free flight)
- Warhead types: Preformed Fragment (PF)

Lab Responsible

Armament Research & Development Establishment (ARDE)
Dr. Homi Bhabha Road, Armament Post Pashan, Pune - 411021

ADVANCED VLF RECEIVER



Very Low Frequency (VLF) is the means of long-range reliable communication from mainland to distributed ships and submerged submarines. Limited bandwidth of the large transmit antenna is a major challenge in achieving enhanced information transfer rate over this link. Advanced VLF Modulator and Receiver is a solution to this challenge which is able to achieve reliable text data communication up to 400 bps in available 200 Hz bandwidth by use of modern communication signal processing techniques implemented in software on indigenous hardware platform.

Salient Features

- Frequency: 10 – 30 KHz
- Throughput: 400 bps
- Bandwidth: 200 Hz
- GMSK Modulation
- Lossless Data Compression
- Serial data interface
- Soft key controlled user menu
- Size: 2U height, 19" rack mountable

Lab Responsible

Defence Electronics Applications Lab
Raipur Road, Dehradun - 248001

SOFTWARE DEFINED RADIO MAN-PACK



SDR-MP is a portable radio with single channel operation in V/UHF for marine applications. The radio has undergone extensive developer trials with all features integrated including security functions, ECCM, adhoc networking, legacy communication support and secure narrow band & wideband digital voice/data communication waveforms. It has high assurance architecture with customized implementation of SCA (software communication architecture) interfaces.

Characteristics of Equipment

- Frequency: 30-512 MHz
- Services: Voice/Data
- Data Interface: Ethernet
- Networking: Yes (MANET)
- Data rate : upto 512 kbps
- Encryption: Built-in (COMSEC/TRANSSEC)
- Weight: 4 Kg
- Size: 230 mm x 225 mm x 90 mm

Lab Responsible

Defence Electronics Applications Lab
Raipur Road, Dehradun - 248001

GAP MEASURING DEVICE MK-III



Gap Measuring Device (GMD) Mk-III enables measurement of distances between banks of canals, ditches and rivers, for laying bridges.

Characteristics of Equipment

- Night operation with 3rd generation MWIR thermal imager.
- Remote control operation.
- Range/gap/vertical height calculation using digital magnetic compass.
- Display of data in remote as well as in thermal imager.
- Operation with rechargeable batteries.
- Weight below 10 Kg including all accessories.

Lab Responsible

Instruments Research & Development Establishment (IRDE)
Raipur Road, Dehradun - 248008

LWPLTD



The state-of-art diode-pumped Light Weight Portable Laser Target Designator (LWPLTD) enables accurate terminal guidance of laser guided munitions during day and night.

Characteristics of Equipment

- Designation of military targets up to 10 km.
- Night operation with 3rd Gen. MWIR thermal imager.
- Built in range finder.
- Weight below 30 kg including accessories.
- Integrated DMC & GPS within Digital Goniometer.
- Operates with rechargeable Li-ion batteries.

Lab Responsible

Instruments Research & Development Establishment (IRDE)
Raipur Road, Dehradun - 248008

OPTICAL TARGET LOCATER



Optical Target Locator is a portable device for detection of active and passive surveillance systems. It finds application in VIP security, active monitoring and sanitisation of sensitive areas and sniper detection. The equipment can be used for detection of optical targets by viewing a strong glint from their front end optics against the background.

Characteristics of Equipment

- Range: 50m-600m
- FOV: 4 degrees
- Battery: Li-ion rechargeable
- Operation: Day/ Night (Urban)
- Target Detection: Bright Spot against background
- Weight: 1.9 kg (without Battery)
- Size: 240 X 180 X 75mm
- Potential targets : Sniper Sight, NVD, LRF, CCD Camera, Laser Target Designator

Lab Responsible

Laser Science & Technology Centre (LASTEC)
Metcalfe House, Delhi - 110054



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

PREEMPTOR



Reliable and stand-off detectors are mandatory for pre-empting the explosive threats. Raman Spectrum Provides finger print of explosives in terms of Raman Shifted light signals. This technique is capable of detecting multiple species of explosives in a single measurement within few seconds.

Characteristics of Equipment


- Mode of operation: stand-off detection
- Agents for detection: All kind of explosives in the form of liquid and solid, even can detect in mixtures
- Detection Range: 30 cm (extendable to 5 m)
- Sensitivity: 10 % in solid and liquid explosives
- Detection and Identification time: 8 sec
- Database: 50 explosives/their precursors
- Alarm indication: Display of threat and sound alarm
- Weight: 8 kg

Lab Responsible

Laser Science & Technology Centre (LASTEC)
Metcalfe House, Delhi - 110054



MODULAR BULLET PROOF JACKET



The Modular Bullet Proof Jacket has been successfully developed in three sizes which provide protection against specified threat levels.

Characteristics of Equipment

- Provides protection against AK-47 (MSC) and 7.62 SLR bullets with Back Face Signature (BFS) less than 25 mm.
- Front Hard Armour Panel also provides protection against AK-47 (Varangoan Hard Steel Core Bullets).
- Comply with the conditioning protocols of NIJ 0101.06.
- Weight varies from 2.5 Kg to 11.2 Kg depending upon area of protection required against specified threat levels.

Lab Responsible

Defence Materials and Stores -Research & Development Establishment (DMSRDE)
GT Road, Kanpur - 208013

BLAST PROTECTION SUIT



The Blast Protection Suit (BPS) provides the protection against accidental blast of APNM M14 Mines during mine breaching operation.

Characteristics of Equipment

- Developed for mine breaching operation and it consists of
 - Body Armour, Hand Guard, Leg Guard
 - Groin Pad, Neck Guard, Gloves, Helmet with Visor
- Soft Armour Panels consists of Aramid quilt and Hard Armour Panels consists of layered structure of advanced composites.
- Weight: 6.2 Kg

Lab Responsible

Defence Materials and Stores -Research & Development Establishment (DMSRDE)
GT Road, Kanpur - 208013



BULLET PROOF OUTER VEST



BPOV gives 360° protection to upper torso of body from 9 mm SAF Carbine.

Characteristics of Equipment

- The BPOV consist of soft armor panel of (SAP).
- SAP covers area of 4100 cm² which includes upper torso of body.
- BPV gives 360° protection to upper torso of body from 9 mm SAF Carbine.
- The BFS (trauma) received will be less than 25 mm.
- SAP defeats 9 mm SAF carbine from a distance of 5 m.
- Total weight of Bullet Proof Vest is less than 2.5 Kg.

Lab Responsible

Defence Materials and Stores -Research & Development Establishment (DMSRDE)
GT Road, Kanpur - 208013

BALLISTIC HELMET



Designed as per the requirements of para military forces (Indian Armed Forces) to provide adequate protection to head and neck.

Characteristics of Equipment

- Adequate protection to head neck and ear
- Weight below 1.2 Kg for medium size
- Defeats 9 mm SMC bullets from 10 meter distance with trauma (back face signature) below 13 mm under both dry and wet conditions.
- UV & IR absorbing paint

Lab Responsible

Defence Materials and Stores -Research & Development Establishment (DMSRDE)
GT Road, Kanpur - 208013

BOOT ANTIMINE INFANTRY



Boot is used in Combat/ Ammunition design and meant for assaulting troops.

Characteristics of Equipment

- Weight less than 3.0 Kg/pair.
- Indigenously developed technology.
- The boot is suitable for assault operation in plane, desert and mountain regions.
- Performance of the boot has been adjudged superior in comparison to the boots of foreign origin (USA, Israel and Canada).
- The peak pressure of the AP mine (35g HE) is in the order of 45,000 kg/cm² has been attenuated to less than 160 kg/cm², which is safe against amputation level injury.

Lab Responsible

Defence Materials and Stores -Research & Development Establishment (DMSRDE)
GT Road, Kanpur - 208013



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

DAKSH – PRIMAL



'Daksh – Primal' has been the first successful mobile robot for military applications developed in India. The robot has been developed for handling, detecting and defusing Improvised Explosive Devices (IEDs). The robot is electrically powered with an endurance of 3 hours and can be operated from a range of 500m on RF or using a Fiber Optic cable up to 100m in a jammed environment. It can climb stairs and has a six-axis robotic arm capable of lifting IEDs up to 20kg at 2.5m

Characteristics of Equipment

- Stair Climbing
- Steep slope negotiation
- Skid steer for zero turning radius
- Online X-Ray facility
- Robust manipulator arm with six degrees of freedom
- Ability to handle suspected objects up to 20kg from 2.5 m
- Multiple cameras with pan, tilt and zoom
- Wireless operation / fiber optic
- Water Jet Disrupter to defuse the IED

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015



UXOR



The Unexploded Ordnance Handling ROV (UXOR) is developed for handling and defusing Unexploded Ordnance (UXO) at test sites and firing ranges remotely. This Robot is equipped with an Abrasive Water Jet Cutting Machine which is capable of cutting through any ordnance to dismember the fuse. The Robot is equipped with two manipulator arms, one for handling bombs upto 1000kg and the other for smaller ordnance. UXOR is equipped with two different cutting mechanisms to for desired profile cut.

Characteristics of Equipment

- IC engine based remotely operated tracked skid steer loader platform
- Cross country mobility with six hours of endurance
- Range of operation 1 km LOS
- Multiple DOF manipulator to handle UXO's in difficult orientation
- Integrated Abrasive Water Jet Cutting Machine
- GPS based localization
- Carrier Vehicle with Master Control Station,
- Intuitive Control console for operator and Navigator,
- Rugged PTZ camera on hydraulic mast

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

DAKSH – MINI



This remotely operated vehicle (ROV) has been specifically developed for handling IED's inside confined space in trains and aircrafts. The robot can be deployed remotely from a distance of 200 m and can traverse through aircraft and railway aisles. The robot has an endurance of two hours on full charge of the on-board battery. The back-pack based Master Control Station provides the operator mobility to approach the suspected object from close by.

Characteristics of Equipment

- Manipulator upto 2.5 m vertical reach and upto 1m horizontal reach with Lift capability 8 kg
- Mobility: All Terrain and 45 degree slope/stair
- Command and Control: Portable Master Control Station
- Real time Video
- Payloads
 - X-Ray
 - Water Jet Disrupter

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015



NETRA



The Unmanned Aerial Vehicle (UAV) - Netra jointly developed with M/s Idea Forge Technology P. Ltd., is a quadrotor developed for surveillance. The UAV is completely autonomous and capable of surveillance in day or night from a range of 5 km with an endurance of 45 mins. The UAV-'Netra' is also integrated with a miniature radiation sensor for measurement of radiation contamination from air remotely. The UAV -'Netra' is man portable and can be carried in a specially designed backpack with all-weather capability.

Characteristics of Equipment

- Daylight Camera - 10X Zoom
- Optional Thermal Imager
- Inbuilt Radiation Sensor
- Autonomous Operation
- GPS waypoint Navigation
- Encrypted Communication Link
- Return to home on: Low battery, Communication failure

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

DAKSH -SCOUT



This man-portable remotely operated vehicle (ROV) has been specifically developed for surveillance operations. The ROV weighs less than 20 kg and can be carried by a single operator. The ROV can be deployed in cross country or urban terrain and climbs stairs. The on-board multiple day /night cameras provide real time video to the operator on his hand held Control Station. The ROV has a range of 200m LOS on RF. The system is silent and would be an invaluable asset for special operations.

Characteristics of Equipment

- Cross-country mobility
- 40 degree slope negotiation
- Stair climbing capacity
- Multiple on-board cameras for all round view
- Night vision capability using Thermal Imager
- Light weight Li-ion battery pack
- Payload :
 - Optional recoilless water jet disrupter
 - Charge delivery mechanism
 - Additional PTZ /under belly camera

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015



MOBILE SHELTER NBC



Mobile shelter NBC is a collective protection shelter which can carry out tactical functions such as communications, command & control post or medical care centre on mobile platform. Shelter is shielded against NEMP effect and protected against fallout gamma and neutron radiations along with Bio-chemical warfare agents. High mobility of the shelter is achieved by mounting it on VVL Tatra 8 x 8. The shelter provides contamination free over pressure area by isolating it from the external environment and continuously providing clear air using NBC ventilation system.

Characteristics of Equipment

- Sandwich panel wall configuration with protection factor of 1.5 against fallout gamma and neutron radiations
- Designed for 8-10 persons for 96 hours protection
- NEMP protection: 80dB for E-field, 60 dB for H-field, NEMP filters for power, data and control lines
- NBC Monitoring system with indoor and outdoor sensors
- Power supply system: 2 Nos. DG Sets (20kVA each), 1 No. PTO
- Penthouse: 2 Nos of 10.08 sq.m. floor area

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015

BAR MINE LAYER



The Bar mine Layer (MML-SP) equipment can bury anti-tank ND Mk-III mines (Bar mines) in soil at 0-20 cm depth at 6m, 9m or 12m spacing. This equipment is capable of laying minimum 250-300 mines per hour for spacing of 6m in plains, semi deserts and deserts terrains.. All the operations in the equipment are automatically carried out by Electronic controller The system has been equipped with GPS based mine field mapping device which automatically stores location of laid mine. The equipment is built on TATRA 8x8 VVN chassis.

Characteristics of Equipment

- Mine Laying rate: 250-300 mines/hr at 6m spacing
- Inter-mine spacing : 6,9,12 m with 15% variation
- Depth of trench: 0-20 cm
- Mine Storage capacity : 338 nos.
- Operational Area : Plains, Desert and Semi-desert
- Mode of operation : fully automated
- Mine field data recording : GPS based auto- recording
- Crew for operation : 03 Crew and 01 driver
- Operational temperature : 0-45^o C
- Mine Laying on Slopes : Longitudinal 0- 10^o , Transverse 0- 7^o

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015

MINE FIELD MARKING EQUIPMENT



The Mine Field Marking Equipment Mk-II is designed for marking the mine fields at faster rate, semi-automatically with minimal human intervention. It is designed to operate in plains of Punjab, semi desert and desert of Rajasthan. This equipment is designed to erect the pickets at any distance from 10 to 35 m (in the step of 5) on to the ground. It also rolls out the rope from the spools which are to be tied manually to the picket at two different heights. The system is based on HMV

Characteristics of Equipment

- Fencing rate : 1.2 km/hr
- Inter picket spacing : 10 to 30 meter in step of 5
- Depth of picket : 100 mm to 450 mm
- Picket Storage capacity : 500 nos.
- Operational Area : Plains, Desert and Semi-desert
- Mode of operation : Semi automated
- Data recording : Yes
- Crew for operation : 04 Crew and 01 driver
- Operational temperature : 0-45° C

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015

SHORT SPAN BRIDGING SYSTEM



One prototype of 10m short span bridging system consists of Tatra 8x8 chassis (re-engineered with an auxiliary cabin at the rear end for limited driving capabilities) as carrier vehicle. Suitable launching mechanism is mounted on the carrier vehicle to launch a 10m bridge along with a pier system. The launching operation is carried out manually or with an electrical system.

Characteristics of Equipment

- Material : RDE 40M Al alloy
- Carrier Vehicle : TATRA T815 8X8
- Bridge length : 10M
- Load class : MLC 70
- Roadway width : 4 m during use and 3.5m during transportation
- Bridge deck : Level deck with anti-skid surface
- Launch time : 20 Minutes

Lab Responsible

Research & Development Estt (Engrs)
Alandi Road, Dighi, Pune - 411015

ARMOURED AMBULANCE TRACKED (AAT)



Designed for the speedy evacuation of battle field casualties with immediate medical care over a widely dispersed area under armour cover.

Characteristics of Equipment

- Provision for
 - Four stretcher patients (or) Two stretcher & four sitting patients (or) Eight sitting patients.
 - Seating for two medical attendants.
 - Air conditioned with 3 ton ACU.
 - Mobility in all type of terrain, obstacle crossing & amphibious capability.
- Medical Facilities
 - Defibrillator for continuous ECG monitoring, automatic external defibrillation & pacing, NIBP and pulse oxymetry.
 - Ventilator for artificial ventilation.
 - Laerdal suction unit for removal of abdominal fluids.
 - Refrigerator for preserving life saving medicines.
 - Thomas splints & crammers (conventional & inflatable). Urine bottle, Bed Pan & Kidney tray

Lab Responsible

Combat Vehicles Research & Development Estt.
Avadi, Chennai - 600054



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

ARJUN MBT MARK I



Arjun MBT Mk I is Made in India and Made for India. The ARJUN MBT Mk I manifests the latest battle tank technologies that make it a distinct front-runner amongst the array of contemporary Main Battle Tanks (MBTs) of modern armies in world over. Arjun MBT Mk I offers the troops a state-of-the-art tank with superior firepower, high mobility, excellent protection and accommodates four men Crew. Encouraged by its excellent performance at the highly challenging operational conditions in harsh Indian desert environment, Arjun MBT Mk I has been named as "Desert Ferrari" by tank experts.

Arjun MBT Mk I is indigenously designed & developed by DRDO for the National self-reliance in Armoured Fighting Vehicle and inducted into service with two regiments operationalized.

Lab Responsible

Combat Vehicles Research & Development Estt.
Avadi, Chennai - 600054



LOW LEVEL TRANSPORTABLE RADAR



Low Level Transportable Radar, Ashwini is a ground based rotating Active Phased Array Radar System for air space surveillance to detect and track air targets, under hostile EW operational environments. The radar operates either in staring or rotation mode. The radar is based on solid state active aperture phased array with Digital Beam Forming and has electronic scanning capability in both azimuth and elevation. The Radar is fully programmable through an efficient Man-Machine Interface from the Local Operator Work Station (OWS) and remotely from the Operator Work Station Unit in the operations shelter.

Characteristics of Equipment

- Fully Distributed Active Phased Array with DBF
- Multifunction and multi-mode radar
- Rotation and Staring Modes of Operation
- Multi Beam in azimuth and elevation
- Electronic scanning in azimuth & elevation
- Programmable Operational Modes
- Volumetric Surveillance
- Automatic Target Classification
- ECCM
- Target tracking with external Cue

Lab Responsible

Electronics and Radar Development Establishment
(LRDE), DRDO, Bengaluru - 560093

WEAPON LOCATING RADAR



Weapon Locating Radar (WLR) is a coherent, electronically scanned Pulse Doppler radar. The radar automatically locates hostile artillery, mortars and rocket launchers and tracks friendly fire to locate the impact point of friendly artillery fire to issue necessary corrections. The radar detects projectiles with small cross section across the battle space horizon, and is capable to handle simultaneous fire from weapons deployed at multiple locations. The fence concept of placing beam grazing the covered air space makes it impregnable for hostile projectiles without detection.

Characteristics of Equipment

- User-friendly initialisation
- Slewable phased array antenna
- Communication with higher echelons
- Low encamp and decamp time
- Weapon location in high density fire environment
- Adaptive radar resource scheduling
- Digital receiver
- Programmable digital signal processor
- Tracking and weapon location using advanced algorithms

Lab Responsible

Electronics and Radar Development Establishment
(LRDE), DRDO, Bengaluru - 560093

3D LOW LEVEL LIGHT WEIGHT RADAR



ASLESHA is a multifaceted ground based 3D Low Level Light Weight Surveillance Radar for deployment in diverse terrains like plains, deserts, mountain tops and high altitude regions. Aslesha detects and tracks heterogeneous air targets, including helicopters, fighters and UAVs at low and medium altitudes. The radar can scan the valley. It provides accurate range, azimuth and height information for each target with electronically steerable multi-beam technology in elevation. The radar is engineered in multiple packages to enable easy transportability in mountainous terrain by vehicles, group of men, or as an underslung carriage by a helicopter. The remote operation of the radar through Commander Display Unit (CDU) provides safety to the crew during operation. The facility also enables the Commander to deploy the radar at a tactically favorable point.

Characteristics of Equipment

- 3D surveillance of aerial targets at low and medium altitude
- Detection and tracking of fighter aircraft, helicopters, slow moving micro-light aircraft and UAVs
- Track while scan
- Full 3D capability using multi-beam technology
- Integrated IFF and side lobe blanking in high density fire environment
- Enabled for networking with Integrated Asterix protocol
- Fast and Easy to install and decamp Remote operation and display through Commander Display Unit

Lab Responsible

Electronics and Radar Development Establishment
(LRDE), DRDO, Bengaluru - 560093

BATTLE FIELD SURVEILLANCE RADAR



BFSR-SR is a man portable, battery operated Surveillance Radar. The radar has been developed for deployment in the forward areas with the capabilities to detect, track and classify variety of moving ground surface targets. BFSR-SR is a reliable sensor for day and night operations in all weather conditions. The radar is a simple, easy to use and user-friendly surveillance-sensor. It can be installed and effectively put to use within 5 minutes. Audio and visual aids help identify and classify a target decisively. The radar is also a potential ground based e-sensor for Border Security Force, Coast Guard and Police for surveillance of designated areas. The radar would be a very cost-effective perimeter surveillance sensor for airports, large industrial and other infrastructure.

Characteristics of Equipment

- Light weight, man-portable Pulse Doppler radar
- Low probability of intercept
- Digitally coded waveforms with choice of RF channels
- Presentation of ground clutter map/ geographical map in PPI format.
- Ability to detect, track and classify
 - Crawling man
 - Single/group of walking men
 - Moving Light and Combat Vehicles
 - Low flying helicopters
- Audio alarm on new target detection over fenced area
- Audio doppler through head phone/built-in speaker

Lab Responsible

Electronics and Radar Development Establishment
(LRDE), DRDO, Bengaluru - 560093

FLR/FCC



Flight Level Radar, a Multi Function Electronically Scanned Phased Array Radar, is the Primary sensor at the Flight level for Air Defence Weapon System. The FLR has the capability to perform extensive search, track multiple targets and missiles, and to command and guide own multiple missiles concurrently. The Radar system is mounted on two HMV namely Flight Level Radar (FLR) and Flight Control Center (FCC), to provide sensor support for all Air Defence operations. The distributed hardware i.e. Radar in FLR and control center in FCC, provides distributed work environment and facilities to operate the radar from control center. It is engineered to support Weapon System deployment either in group or autonomous configuration. The radar has built-in UHF communication component providing voice and data communication with squadron control center when deployed in a group. Also, Integrated Radio Line Modern (IRLM) provides data communication to the launchers.

Characteristics of Equipment

- Automatic target identification
- Variable track update rates
- Low Side Lobe Antenna
- Frequency Agility
- Pulse Compression
- Automatic threat evaluation and weapon assignment
- Target Engagement and Kill Assessment
- Multi-Sensor data fusion
- Online status data logging, Remote display and user friendly reply
- Networks centric operation

Lab Responsible

Electronics and Radar Development Establishment
(LRDE), DRDO, Bengaluru - 560093

3 D MEDIUM RANGE SURVEILLANCE RADAR



3 D Medium Range Surveillance Radar, Rohini is a ground based mechanically scanning Pulse Doppler radar for air space surveillance to detect and track air targets with reliability, even under hostile EW operational environment. The flexible architecture is a reliable and adaptable technology for multiple applications - early warning for air defence weapon system, air defence sensor at airbases. The radar has advanced technologies like digital receiver, programmable signal processor providing high resolution, accuracy, response and information availability. The radar, packaged on two vehicles, is easy to operate, transportable by air, rail and road, can be deployed and decamped in less than 30 minutes.

Characteristics of Equipment

- Medium range high resolution 3D surveillance
- Integrated IFF with co-mounted antenna
- 7 channel Digital receiver and Signal Processor
- Programmable Signal Processor
- Cross country mobility
- Clutter/Weather/ECM video maps
- Jamming analysis and presentation
- High altitude deployability
- Transportable by Road, Air and Rail
- COTS hardware for maintainability and cost effective surveillance solution

Lab Responsible

Electronics and Radar Development Establishment
(LRDE), DRDO, Bengaluru - 560093

TORPEDO ADVANCED LIGHT



Torpedo Advanced Light (TAL) is capable of launch from ships and helicopters to attack submarines in shallow and deep waters. TAL performs pre-programmed search patterns, detects the target and homes on to the submarine. M/s BDL has produced 25 torpedoes for Indian Navy. Torpedo Advanced Light is being exported to Myanmar Navy.

Characteristics of Equipment

- Propulsion: Electrical, Mg-AgCl Battery
- Contra-rotating propellers
- Homing: Acoustic (Active, Passive and Mixed)

Lab Responsible

Naval Science & Technological Laboratory
Vigyan Nagar, Visakhapatnam-530027

LITHIUM ION BATTERIES



Lithium-ion cell technology has been developed with active materials suitable for high rate application. The batteries are supported by a battery management system to ensure safety. The technology incorporates features of flexible voltage, current and high endurance and is useful for both defence and civilian applications.

Characteristics of Equipment

- Modular construction
- No Hazardous gases
- Integrated Battery Management System (BMS)
- In-situ charging
- Maintenance free

Lab Responsible

Naval Science & Technological Laboratory
Vigyan Nagar, Visakhapatnam-530027

EXPENDABLE DECOY



Expendable Decoy is developed by Naval Science and Technological Laboratory under Project Maareech. The soft-kill system incorporates programmable features to optimize its performance for deceiving and seducing incoming torpedoes thus ensuring maximum torpedo engagement time to protect own ship. The system has been inducted into Indian Navy in 2015.

Characteristics of Equipment

- Modes of operation : Jammer, Echo repeater, Auto
- Depth of operation upto 100mtrs
- Endurance : 8 min
- Effective range : 2000 m
- ToT with M/s BEL
- Export version available

Lab Responsible

Naval Science & Technological Laboratory
Vigyan Nagar, Visakhapatnam-530027

AKASH



Akash Missile System is designed and developed to protect important assets of the country from enemy air attacks (from Fighter Aircrafts, Unmanned Aerial Vehicles and Helicopters, etc.). It has simultaneous multiple-target engagement capability. Country's first indigenous multi-function phased array radar is used to guide the missile.

Characteristics of Equipment

- (a) Dimensions of the missile
- Length : 5.82 m
 - Weight : 710 kg
 - Diameter : 0.35 m
- (b) Capabilities
- Operational Range : 27 km
 - Altitude : 18 km
 - Speed : Mach 2+
 - Single Shot Kill Probability : 88% (Kill probability increases with firing more than 1 missile in sequence).

Lab Responsible

Defence Research & Development Laboratory, APJ Abdul Kalam Missile Complex
Kanchanbagh, Hyderabad - 500058

ASTRA



Astra (Beyond Visual Range Air to Air Missile) is intended to engage and destroy highly maneuvering and supersonic speed air targets. It is powered by a smokeless, single stage, solid fuel propulsion system. It has Inertial-Guidance, Midcourse-Update and Active-Radar-Homing. Astra has "excellent" ECCM to tackle jamming by hostile aircraft and active radar terminal guidance.

Characteristics of Equipment

- (a) Dimensions of the missile
- Length : 3.8 m
 - Weight : 170 kg
 - Diameter : 0.178 m
- (b) Capabilities
- Operational Range : 60+ Km
 - Speed : Mach 4.5+

Lab Responsible

Defence Research & Development Laboratory, APJ Abdul Kalam Missile Complex
Kanchanbagh, Hyderabad - 500058

NAG



'NAG' Missile (3rd Gen, Fire & Forget Anti-Tank Guided Missile) is a 'Fire and Forget', third generation ATGM. The Missile is equipped with indigenous high resolution IIR seeker, which provides passive homing guidance for engaging static/moving Tank Targets. The Seeker is capable of operating during Day and Night. The Missile has Direct & 'Top attack' Capability and Tandem Warhead of the Missile can defeat all types of modern MBTs. Min and Max Ranges of NAG are 500Mtrs and 4-5Km

Characteristics of Equipment

- Diameter : 155 mm
- Weight : 42 kg
- Diameter : 1834 m

Launcher System (NAG Missile Carrier)

'NAG' Missiles are deployed on a dedicated BMP-2 based tracked Infantry Combat Vehicle (ICV) called 'NAMICA'. It is equipped with NBC protection (Nuclear, Biological or Chemical), independent Gunner & Commander Sights, and instant fire suppression system for crew safety.

Features of NAMICA

- 06 Nos. Ready to Fire 'NAG' Missiles on the Launcher Platform
- Amphibious Capability
- Hunter-Killer Capability
- Independent Commander's Panoramic Sight for surveillance
- Equipped with Land Navigation System (LNS)
- Silent watch capability (Day & Night)
- 4-man Army Crew

Lab Responsible

Defence Research & Development Laboratory, APJ Abdul Kalam Missile Complex
Kanchanbagh, Hyderabad - 500058

WhAP



WhAP is an 8x8, Wheeled Armoured Platform which can be configured for variety of combat & combat support roles such as Armoured Personnel Carrier, Infantry Combat Vehicle, Recce & Support Vehicle and Command Post vehicle etc. The vehicle is amphibious with hydrojets. It is incorporated with advanced features such as high power engine with automatic transmission, driveline with hydrogas suspension and run flat tyres, modular ballistic and blast protection.

The prototypes have been successfully configured with 30mm turret and 7.62mm RCWS. The platform can accommodate different types of armaments such as ATGMs and other Mission modules / payloads.

Characteristics of Equipment

- Configuration : 8 x 8
- Power pack : 600 hp Diesel Engine
- Driveline : All Live axles with independent suspension (Hydro gas)
- GVW of platform : 21.5 t—with baseline protection of 7.62 AP
- Speed
 - On road : 90 – 100 km/h
 - Cross country : 35 - 40 km/h
 - Speed in water : 8 kmph
- Gradient : 30°
- Ballistic : Modular as per STANAG
- Mine protection : 8 kg TNT - STANAG level III
- Armament : Medium calibre manned turret and RCWS ,12.7 & 7.62 mm RCWS, ATGM etc

Lab Responsible

Vehicle Research & Development Establishment
PO: Vahan Nagar, Ahmednagar - 414006

MDC WITH CBRN MINI UGV AND MPD



Mobile CBRN Detection & Communication Vehicle (MDC) along with CBRN Mini UGV & MPDS is required for early detection of CBRN warfare agents & to communicate to the competent authority for further action. MDC Vehicle comprises of NBC sensor system, communication system, NBC Filtration system, Mini Unmanned Ground Vehicle (UGV), Multi Purpose Decontamination System (MPDS), Power Source (Genset), UPS etc. All these systems have been integrated in various compartments of MDC vehicle.

Characteristics of Equipment

- Integrated N&C sensor system” for detection of N&C agents in environment.
- “Communication system” to communicate information to appropriate authority for planning further actions.
- “Mini Unmanned Ground Vehicle (UGV)”
 - Mini-Tracked platform with four flippers
 - Max speed : 6 km/hr
 - Stairs climbing - Step Height : 18 cm, Depth : 25 cm
 - Day and Night Vision system
 - GPS/INS based integrated Navigation system
 - Wireless communication link Range : up to 500 m Near LoS and 1 km LoS
 - Endurance : 2 hours
- “NBC filtration system” to supply NBC filtered air to occupants inside the communication compartment and to driver in driver cabin through face mask.
- “Multipurpose Decontamination System (Self powered)” for decontamination operation

Lab Responsible

Vehicle Research & Development Establishment
PO: Vahan Nagar, Ahmednagar - 414006

E-NASIKA



Electronic sensing of hazardous chemical vapors at very low concentration levels is becoming increasingly important in present day security and surveillance scenario. Several technologies are being developed around the world to detect hazardous vapor content. SSPL, Delhi has developed e-Nasika (electronic nose) system which is capable of detecting Chemical Warfare (CW) agents in chemical war scenario. The developed system is light weight, hand held and battery operated with capability of detecting the CW agents up to ppb level. It can also sense the presence of various hazardous chemicals (TICs and TIMs) at low concentration (ppb level) with least false alarm and quick response times.

Characteristics of Equipment

- Compounds Targeted : Nerve, Blister, Blood & Choking Agents, TICs, TIMs
- Analysis Time : < 1 minute
- Compound Identification : Automatic
- Sensitivity : Nerve (ppb), Blister (ppb), Blood (ppm), Choking (ppm)
- Size : 30 x 10.5 x 12 cm³
- Weight : ~ 3 kg with batteries
- Continuous Operation : > 12 hours duration

Lab Responsible

Solid State Physics Laboratory (SSPL)
Lucknow Road, Timarpur, Delhi - 110054

IDEAFORGE TECHNOLOGY PRIVATE LIMITED

- Address** : EL-146 TTC Industrial Area, Electronic Zone, MIDC Mahape,
Navi Mumbai - 400 710, Maharashtra, India
- Website** : www.ideaforge.co.in
- Head** : Naveen Navlani
GM (Defence Business)
- Telephone** : +91-22-2767 0001
- Fax** : +91-22-2767 0707
- Mobile** : +91-8800611771
- Email** : info@ideaforge.co.in

Organisation Profile:

ideaForge Technology was founded in 2007, by a team of dynamic graduates from Indian Institute of Technology, Bombay. In 2009, it created the then world's smallest and lightest autopilot at 10 grams, and Technically Collaborated with Defence Research and Development Organization (DRDO) to co-create NETRA. Today, the company is a global technology leader in the VTOL Micro and Mini UAV space, and is also the market leader of the defence and internal security UAV market in India.

ideaForge has a large client base consisting of Defense & Internal Security agencies, as well as Government bodies which employ and procure UAVs. It has also begun introducing UAVs in the industrial segment; delivering drone-based solutions for industries involved in Agriculture, Mining, Energy, Environment and others, and is the first in the country to develop LiDar-mounted UAVs. The company has delivered more than 600 UAVs to various forces, and has trained more than 1100 pilots.

It is a vertically integrated company which is equipped with in-house R&D, manufacturing, software, services and training operations. This provides the flexibility to customize products to deliver end-to-end UAV solutions and services to the industrial and commercial sectors.

NETRA V-SERIES

Endurance Champion Global Class Leading Flight-times with IP53 Qualification & HD Live Transmission for Use in Most

Demanding Application used for:

- Inspection
- Security & Surveillance
- Area Mapping and 3D

Modelling

- Traffic Management
- Crowd Management
- Disaster Response

Characteristics/Specifications

- Surveillance Grade Endurance: Up to 60 min with HD payload @1000AMSL
- Range (LoS): 4-5 Km
- Weight: < 3 Kg with max payload
- Wind Resistance: 24.3 knots (45 KMPH)
- Ingress Protection: IP53 Rated for Dust Resistance
- Max Operating Altitude: 400m AGL
- Max Launch Altitude: 3000m AMSL
- Vehicle Size: < 1m X 1m
- Daylight Payload HD with 10X optical zoom
- Fully Encrypted Data Streaming
- Thermal Payload

Contact Person

Naveen Navlani
GM (Defence Business)
T: +91-22-2767 0001
M: +91-8800611771

F: +91-22-2767 0707
E: naveen.navlani@ideaforge.co.in

NETRA PRO



Rugged & Powerful Octa-Copter for Maximum Fail-safes & Versatility, even in extreme conditions used for:

- Security & Surveillance
- Supply Drops
- Area Mapping & 3D
- Modeling
- Traffic Management
- Crowd Management
- Disaster Response
- Extreme Environment
- Operations
- Inspection

Characteristics of Equipment (Capability & Physical Characteristics in bullet points)

Endurance: Up to 45 mins with payload @1000AMSL

- Range (LoS): 4Km
- Weight: & 6Kg with max payload
- Wind Resistance: 24.3 knots (45 KMPH)
- Ingress Protection: IP53 Rated for Dust Resistance
- Max Operating Altitude: 400m AGL
- Max Launch Altitude: 3000m AMSL
- Vehicle Size: & 1m X 1m
- Daylight Payload Resolution: HD with 10X optical zoom
- Fully Encrypted Data Streaming
- Thermal Payload
- HD Mapping Payload

Contact Person

Naveen Navlani

GM (Defence Business)

T: +91-22-2767 0001

F: +91-22-2767 0707

M: +91-8800611771

E: naveen.navlani@ideaforge.co.in

SWITCH HYBRID



- VTOL Hybrid for Terrain Independent Area
- Dominance with Long Range & High Flight-time
- Long Range Continuous Border
- Patrolling
- Counter - Insurgency
- Disaster Response
- Radiometric & Black Hot / White Hot
- Thermal Images
- Security & Surveillance
- Area Mapping & 3D Modeling
- Extreme Environment
- Operations

Characteristics of Equipment (Capability & Physical Characteristics in bullet points)

Endurance: 120+ minutes

- Range (LoS): 10Km
- Weight: <6Kg with max payload
- Wind Resistance: 24.3 knots (45 KMPH)
- Ingress Protection: IP53 Rated for Dust Resistance
- Max Operating Altitude: 1Km
- Max Launch Altitude: 3000m AMSL
- Vehicle Size: <2.5m X <1.5m
- Daylight Payload Resolution: HD with 20X optical zoom
- Fully Encrypted Data Streaming
- Thermal Payload
- HD Mapping Payload

Contact Person

Naveen Navlani

GM (Defence Business)

T: +91-22-2767 0001

M: +91-8800611771

F: +91-22-2767 0707

E: naveen.navlani@ideaforge.co.in



L&T DEFENCE

- Address** : G4, 2nd Floor, Gate , Saki Vihar Road
Powai Campus, Mumbai 400072, India
- Website** : www.larsentoubro.com
- Head** : Jayant D Patil
Whole Time Director (Defence Business) and
Member of the Board, Larsen & Toubro Ltd
- Telephone** : +91-22-67052969
- Fax** : +91-22-67054160
- Email** : defence@larsentoubro.com

ORGANISATION PROFILE:

Larsen & Toubro (L&T) is a multi-billion Dollar technology, engineering, construction, manufacturing and financial services conglomerate, with global operations. A strong customer - focused approach and constant quest towards maintaining top-notch quality, have enabled L&T to attain and sustain leadership in its major lines of businesses over seven decades.

L&T Defence, a group company of Larsen & Toubro, is one of India's leading companies for supply of Defence Equipment and Systems in the private sector, with over 30 years of experience in this field. The Company provides indigenous, design-to-delivery solutions across the defence spectrum - from surveillance to strike capabilities, and mobility platforms essential to enhance their effectiveness.

L&T Defence also offers specialised turnkey defence construction solutions like underground structures, military bases, storage depots, smart infrastructure and modernisation of existing facilities. L&T's infotech business provides seamless integration of solutions that enhance both administrative and tactical efficiency of the armed forces.

L&T Defence has nine (09) dedicated manufacturing facilities, across the country, which leverages on the latest design and manufacturing technologies.



CHEMICAL AGENT DETECTOR



L&T Defence in association with DRDE, Gwalior have developed India's first indigenous chemical warfare agent detector. The detector simultaneously samples Chemical Warfare Agents (CWAs) and Toxic Industrial Chemicals (TICs) in positive (G) and negative (H) mode.

Useful during both war and peacetime, the detector is available in two variants: Fixed Chemical Agent Detector (FCAD) and Portable Chemical Agent Detector (PCAD). These detectors are capable of sensing very low concentrations of the following types of chemical warfare agents in different temperature and humidity conditions:

- Nerve Agents
- Blood Agents
- Blister Agents
- Choking Agents.

Characteristics of Equipment

- Rugged, compact and easy to carry
- Operational on 18V - 32V DC supply as well as 230V/50Hz AC
- Analysis time of less than 60 sec and recovery time of less than 180 sec
- Expandable library of CWAs and TICs to update new agents
- Compliance with JS55555 and MIL STD 461E
- Customizable and upgradable Software.

Contact Person

Marketing Team

T: +91-80-66936565

F: +91-80-66936333

E: secmkt@larsentoubro.com

RAPID DEPLOYED COMMUNICATION SYSTEM



L&T defence has developed state-of-the-art man-portable communication system for rapid deployable exercises, tactical military operations, humanitarian aid and disaster relief operations. It enables communication inter-operability between digital and analog systems, mobile and static and over multiple media types.

Characteristics of Equipment

- Indigenously designed and developed
- Ruggedized for military usage
- Commercial grade AES 256 security
- Integrated radio gateway system
- 220V AC/ 48VDC

Contact Person

Marketing Team

T: +91-80-66936565

F: +91-80-66936333

E: secmkt@larsentoubro.com

DUAL TECHNOLOGY MINE DETECTOR



DTMD is an advanced technology, combining leading-edge Ground Penetrating Radar (GPR) and a high-performance Metal Detector (MD). The unit has been designed specifically for use in the most challenging military and humanitarian demining operations..

Characteristics of Equipment

- Zero or low false alarms rate
- Detects metal-free mines and IEDs
- Ultra-high sensitivity
- Easy operation
- Alarm: visual bar graph and audio signal
- Simultaneous operation of metal detector and GPR possible
- Lightweight

Contact Person

Marketing Team

T: +91-80-66936565

F: +91-80-66936333

E: secmkt@larsentoubro.com



MKU LIMITED

Address : 13, Gandhi Gram, GT Road Kanpur, UP, 208007, India
Website : www.mku.com
Head : Neeraj Gupta
Telephone : +91-512 7102710
Fax : +91-512 7102727
Mobile : +91-9005094900
Email : protection@mku.com

ORGANISATION PROFILE:

MKU is a leading manufacturer of light weight personal armour, platform armour, night vision and thermal devices for armies and law enforcement agencies.

With 3 decades of experience and proven ahead of the curve technology, MKU has gained the trust of more than 230 forces in over 100 countries. It offers more than 1000 solutions for over 100 types of threats and has provided protection to over 2 million soldiers and 2000+ platforms (land, air and naval) till date.

MKU has 4 manufacturing facilities across India and Germany with in-house labs for ballistic and environmental testing and a class 10,000 clean room for assembly of electro-optic devices. MKU's facilities are ISO 9001-2008, AS-9100 Rev 'C' and BA9000 certified. It a registered supplier to UN & NATO and is the only company in India to have received the stringent NIJ 0101.06 certification from the National Institute of Justice, USA for body armour.



C-4012



Cerazone+ armour inserts are manufactured using highly mass efficient and advanced ceramics like silicon carbide & boron carbide (the third hardest material known to man). These are light and offer better comfort during prolonged usage.

Product	:	Cerazone
Model	:	C-4012
Size	:	25 cm X 30 cm (± 3 mm)
Nature	:	Stand Alone
Shape	:	Top Cut, Single Curve
Weight	:	2.5 Kg \pm 50 gm
Thickness	:	19 mm (± 2 mm)
Protection Level	:	Level III+ as per NIJ 0101.04

Bullet

- 7.62 x 39 mm AP

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799



C-7008



Cerazone+ armour inserts are manufactured using highly mass efficient and advanced ceramics like silicon carbide & boron carbide (the third hardest material known to man). These are light and offer better comfort during prolonged usage.

Product	: Cerazone +
Model	: C-7008
Size	: 25 cm X 30 cm (± 3 mm)
Nature	: Vest Dependent
Shape	: Top Cut, Single Curve
Weight	: 2.2 Kg \pm 50 gm
Thickness	: 15 mm (± 2 mm)
Protection Level	: Level IV as per NIJ 0101.04

Bullet

- 7.62 x 63 AP (M2AP)

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799

HIGH CUT BALLISTIC HELMET



High Cut Ballistic Helmet

HCBH (High Cut Ballistic Helmet) are designed to allow maximum sensory & situational awareness to soldiers as they offer an unobstructed field of view and increased ambient hearing capabilities.

HCBH helmets from MKU provide excellent ballistic and impact protection and are compatible with a wide range of devices like Night Vision Devices (NVD's), Communication equipment, Nuclear-Biological-Chemical (NBC) equipment, etc.

Features

- Maximum sensory & situational awareness
- Superior Ballistic protection
- Excellent
 - Mechanical rigidity, toughness
 - Ergonomics
 - Heat insulation
- Resistant to
 - Temperature extremes
 - Water & moisture (Non-absorbent)
 - Flame & UV
- Suitable for snow, deserts, hills, plains and positive buoyant during amphibian/marine operations
- Compatible with add on devices like NV devices, CRBN and communication sets.

Protection Level

- Level III A (9mm) testing as per NIJ 0106.01
- V50-650 M/Sec

Color

- Black (Color customization is possible)

Size & Weight of Helmet

Size	Weight
Medium	1.15 gm \pm 50 gm

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

MKS-1002



INSTAVEST, from MKU, is a revolutionary ballistic jacket which incorporates an advanced Quick Release System.

A soldier can divest the vest in a single pull action in less than a second.

Its remarkable design makes it the simplest quick release ballistic over-vest which can be recouped and reassembled in less than 30 seconds. The Quick Release System uses no cables or wires and is ambidextrous in nature.

Design Features

- Donning and doffing in an instant for quick response. It divests in less than a second and can be assembled and donned in approx. 30 seconds.
- Light weight, flexible and extremely comfortable.
- Advanced load distribution system.
- Fully adjustable at waist & shoulder for a precise and comfortable fit.
- Detachable groin, collar and shoulder.
- Incorporates a rifle butt rest for enhanced comfort during operations.
- Compatible with hydration packs, ammunition pouches & other gears.
- Rear drag strap handle.
- D-rings to carry bulky items.
- Manufactured using breathable, fire retardant, water repellent advanced fabrics.
- Inner lining for air ventilation

Protection Areas

- Front, back, side, collar, groin and shoulder

Size and Weight

- Large: 5 Kg \pm 100 gm

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

JCO IIE



Concealable Vest

Model: JCO IIE

Concealable Vest from MKU is ideal for persons who are constantly under threat and want unobtrusive protection gear. The concealed Body Armour has been specially designed for elite & special forces for protection against handgun ammunition.

Special Features

- Excellent ergonomics
- Maneuverability
- Ease and comfort to wear
- Highly Flexible
- Ultra Thin
- No ride up
- Better ventilation

Design Features

- Specially designed to conceal the vest when worn under uniform or shirt.
- Unobtrusive / Concealable protection that ensure peace of mind
- Front and back overlapped to provide side protection.
- Soft Armor panel will be encased in the heat sealed material to protect from moisture.
- Inner mesh lining for ventilation and sweat absorption.

Protection Level of vest

- Level IIIA (9mm) as per NIJ 0101.04

Protection Area

- Front, Back and Sides.

Colors

- Black and White

Dimensions & Weight

Size	Weight of vest
Large	1.5 Kg \pm 100 gm

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

JMT IV B



Tactical Military Over-vest

JMT IV B

Ideal for tactical operations, Tactical Military Over-vests from MKU are manufactured using Polyethylene/ Aramid or hybrid materials. External fabric is optimized for camouflage. Designed for easy mobility while providing optimum protection and maximum comfort over prolonged usage, they are capable of offering protection of up to NIJ Level III-A.

Enhanced protection against ammunition like AK-47, 7.62 NATO, 5.56 mm. etc. can also be achieved by upgrading these over-vests with Armor Plates available separately.

Design Features

- Ergonomic construction and design for maximum protection, flexibility and movement
- 2 front & side utility pouches
- Reinforced front & back pockets for Armor Plates
- Water proof & UV resistant ballistic panel covers to provide enhanced safety in adverse conditions
- Adjustable shoulders for a snug and comfortable fit
- Water repellant, removable and washable outer carriers for enhanced durability and performance of over-vests
- Offering enhanced protection by including protection for neck and groin without compromising on mobility
- Detachable and foldable groin guard that does not impede free movement of the wearer during operations
- Adjustable collars

- Unique inner waist belt helps in even distribution of weight of the over-vest

Protection Level

- Level IIIA as per NIJ 0101.04

Protection Area

- Front, back, Sides, Collar & Groin

Sizes & Weight

- Large: 4.03 Kg \pm 100 gm

Colors



Olive Green |Olive Drab |Sand |Black |U N Blue |Navy Blue|
(Also available in Camouflage pattern)

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

P-10016 ICW MKS-1002



NIJ 0101.06 certified Vest dependent Polyshield plates from MKU offer best protection at the lowest possible trauma. The plate provides level III protection in combination with level IIIA Soft Armor Panels. These plates are manufactured using the best materials and state-of-art manufacturing technologies. The plate has undergone rigorous testing standards as laid down by the Department of Justice, USA. The single curve geometry ensures ease of movement & operations whilst maintaining highest levels of protection.

Polyshield Armor Plates from MKU offer excellent multi-hit capabilities and are safe from secondary fragments upon impact. They do not crack and are resistant to UV radiations, water, sunlight & temperature changes. Acids and oils have no effect on them. MKU is one of the very few armor manufacturers in the world with capacity & technology to produce these Armor Plates in the high volumes necessary for national requirements.

Model	:	P-10016 ICW MKS-1002
Size	:	250 mm X 300 mm (±5mm)
Nature	:	Vest Dependent**
Front/Back	:	Can be used as front or back plate
Finish	:	PU Coated Polyester Cover
Weight	:	1.4 Kg (±50 g.)***
Thickness	:	19 mm (±2 mm)
Protection Level	:	Level III Certified as per NIJ 0101.06
Ammunition	:	7.62 x 51 Lead Core (NATO BALL, M80)
Warranty	:	7 years*

*conditions apply

** (The Plate is ICW Soft Armor Panel (MKS-1002), for details refer technical Paper MKS-1002

*** Also available in Shooter Cut Shape

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

MKH/ACH-4



ACH (Advanced Combat Helmet)

Model: MKH/ACH-4

ACH (Advanced Combat Helmets) are slowly replacing the PASGT helmets worldwide, due to better design and compatibility with various critical equipment & devices used by a modern soldier. They are designed to allow maximum sensory & situational awareness to soldiers as they offer an unobstructed field of view and increased ambient hearing capabilities.

ACH helmets from MKU provide excellent ballistic and impact protection and are compatible with a wide range of devices like Night Vision Devices (NVD's), Communication equipment, Nuclear-Biological-Chemical (NBC) equipment etc. These helmets are available in special suspension systems which allow a soldier to carry out their missions more effectively when wearing body armor.

Features

- Maximum sensory & situational awareness
- Superior Ballistic protection
- Reduced operational fatigue
- Excellent
 - Mechanical rigidity, toughness
 - Impact protection
 - Ergonomics
 - Ricochet damage control
 - Heat insulation

- Resistant to
 - Temperature extremes
 - Water & moisture (Non-absorbent)
 - Flame & UV
- Manufactured using non-toxic materials
- Suitable for snow, deserts, hills, plains and positive buoyant during amphibian/marine operations
- Compatible with add on devices like NVD, CBRN and communication sets etc.

Protection Level

- Level IIIA (9mm) as per NIJ 0106.01

Colors



Olive Green |Olive Drab |Sand |Black |U N Blue |Navy Blue|
(Also available in Camouflage pattern)

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799



PASGT



PASGT

The PASGT (Personal Armour System Ground Troops) helmet was developed by the U.S. Army to address the inadequate protection and other problems of the conventional steel helmet. MKU PASGT Helmet is an adaptation of the standard US Military PASGT Helmet with unique protection properties. The shell is constructed using superior aramid composites which are layered and bonded with impregnable resin for exceptional ballistic and fragmentation protection.

PASGT Helmets from MKU are lightweight and employ the latest processes and material advancements along with optimal protection, comfort and insulation for all situations and weather conditions. They adequately exceed fitting, suspension and ventilation factors as specified by armies worldwide.

Features

- Manufactured strictly as per US Military PASGT shape and style.
- Made of advanced aramid composite materials.
- Full frontal protection.
- Designed for ideal mass distribution which minimizes lag during head movement
- Two-component Aliphatic Polyurethane paint protects from de-contamination after exposure to chemical agents & provides better outdoor exposure resistance
- Superior ballistic protection
- Excellent
 - Mechanical rigidity, toughness
 - Impact protection
 - Ergonomics
 - Ricochet damage control

- Heat insulation
- Resistant to
 - Temperature extremes
 - Water & moisture (Non-water absorbent)
 - Flame
 - UV
- Manufactured using non-toxic materials.
- Suitable for snow, deserts, hills, plains and positive buoyant during amphibian/marine operations.

Protection Level

- Level III A, (.44 Mag) As per NIJ 0106.01

Colors



Olive Green |Olive Drab |Sand |Black |U N Blue |Navy Blue|
(Also available in Camouflage pattern)

Suspension System

- MKH/PA-4

Weight & Size

- Large – 1.48 Kg ± 50 gm

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799



QUICK RELEASE PLATE CARRIER



Quick Release Plate Carrier manufactured by MKU offers enhanced protection and ergonomics. Manufactured with light-weight materials, these Plate Carriers are extremely comfortable while in use even after prolonged usage.

Unique features

- **Quick release**
- **Unisex design**

Design Features

- Plate carrier consists of Quick release mechanism for faster release.
- Special rugged O-ring to **quickly release the carrier**.
In emergency situation, carrier is **released just by pulling the O-ring with gloved hands** which releases the vest at four points.
- Unique design ensures **fast and quick reassembly**.
- All around **laser cut MOLLE provision** to carry the extra pouches and accessories.
- Ergonomic design ensures comfort while driving the vehicle. Also does not restrict the movements while aiming with hand gun and rifle even while wearing the helmet.
- Cushioned waist-belt at inner side for extra comfort.
- Plate Carriers is **adjustable at sides and shoulders**
- Additional **Drings on both shoulders** to attach or hold the rifle or longgun & other combat gears.
- **Hook Loop and Velcro provision** on upper torso (front & back) and sides to hold radio wire & hydration bag water-tube etc.
- **Soft cushioning pads** at shoulders for comfort during prolonged usage.
- **Extra Soft material at neckline and armhole** for wearing comfort while aiming

and head movements.

- ***Specially designed, reinforced drag handles*** with adjustable ladder system for varied applications.
- The plates are covered with water resistant fabric which ensures protection against moisture.
- The Cover comes apart and goes back as easily and as quickly as possible (shoulder+ sides)
- Mesh with Foam provides breathability, Air Circulation, perspiration and Cushioning
- CPPB is as comfortable as possible, even during extended wear.
- This mechanism is ambidextrous in nature i.e. can be released either with left or right hand
- The strong and rugged emergency release is made of highly durable material which ensures operations through out the life of the vest

SIZE: Medium

Weight of Plate Carrier: 2.9Kg \pm 50 gm

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

MKH/VD-20



DETACHABLE BULLET RESISTANT VISOR (MKH/VD-20)

This visor from MKU is designed to enhance ease of use. It allows the user to wear and take of the attached visor over/from the helmet quickly and easily.

VISOR	Protection Level	STANDARD	WEIGHT
Bullet Resistant	Level III A (9 mm)	NIJ 0106.01	1.55 ± 50 gm

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com



MKH/ACH-4



Bolt Free Helmet

Model : MKH/ACH-4

MKU has pioneered in developing a very unique mechanism which helps in **Trauma Reduction by over 40%** compared to standard helmets.

Traditional helmets though provide protection against bullets and fragments but not very efficient against Resulting Trauma due to their impact which causes Back Face Deformation which transfers considerable trauma to the head that may result in brain injuries and skull fractures.

The **RHT Technology** developed by MKU is to reduce the Trauma on Ballistic helmets due to bullet hit to make the helmet safer for wearer.

Unique Features

- Reduced Trauma
- No drill, No hole

Performance

- Uniform Ballistic protection
- Excellent
 - Mechanical rigidity, toughness
 - Heat insulation
- Resistant to
 - Temperature extremes, Water & moisture
 - Flame & UV

Design Features

- Designed for ideal mass distribution which minimizes lag during head movement for better comfort

- Joint less Rubber edging protecting the outer contour
- Four point system for snug and stable fitting.
- Non allergen materials used.
- Two-component Aliphatic Polyurethane paint protects from de-contamination after exposure to chemical agents & provides better outdoor exposure resistance
- No metal parts negating secondary fragmentation
- Allow use of Communication system, Gas Mask & NVD

Suspension System


- Modular pad suspension system : Consists of 7 pads (self-configurable system)
- Combination of trapezoidal, oblong & round pads provide extra comfort & stability
- Easy adjustment mechanism for snug fit

Protection Level

- 9m, Testing as per NIJ 0106.01

Size & Weight of Helmet

- Small:
- Medium:
- Large:
- X-Large:



RHT is a break down helmet technology that substantially reduces the resultant trauma over 40% compared to standard helmet for protection against 9 mm ammunitions fired through handgun.

Trauma in helmets, upon bullet hit, is a known concern amongst all the forces in the world. As per studies, head injuries due to trauma in helmets may result in permanent damage to the brain.

After years of research, MKU is proud to announce a successful breakthrough RHT Technology which helps in reducing the back face deformation created due to bullet hit

in helmets. With RHT Technology, the resulting trauma is less when tested against 9 mm bullets as per HPW-TP-0401.01 standards. The advanced technology not only protects against the handgun ammunitions but also reduces the resulting Trauma to protect against hidden head injuries.

The bolts mounted on the outer shell of the helmet act as lethal secondary fragments due to bullet hit that endanger the soldiers wearing it. Ballistic helmet must be free from bolts to provide uniform protection all around the outers of the helmet shell.

Bolt free helmets from MKU feature a shell which is based on no-drill concept that not only provides enhanced comfort but also increases protection against ballistic threats.

bolt free

-  No Holes, No Bolts
-  No unprotected areas
-  No secondary fragmentation risk
-  No metal parts
-  Uniform protection across the Helmet shell



Bullet approaching helmet



Bullet hits on helmet



Bullet is stopped due to uniform ballistic shell

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

NETRO NC - 3000 NIGHT VISION BI -OCULAR



NETRO NC - 3000 is a long range Single Tube Biocular night vision goggle that combines a high quality image intensifier tube with two eyepieces. It is a Lightweight and efficient night vision goggle with IP68 water resistance certification with excellent resolution and a wide field of view.

Feature

- Multipurpose, can be used as Helmet Mounted, Head Mounted or Hand Held.
- Light Weight, Waterproof and Rugged Bright Light Cut-off Conforms to MIL Standards.
- All weather capability water proof, dust proof and corrosion free Easy to maintain.
- Magnification: 1x
- Field of View: 45° (min).
- Diopter Adjustment: -6 to +4 diopter.
- Operating Temperature: -40°C to +55°C.
- Environmental Standards: MIL-STD-810G compliant.

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799

NETRO NM - 3000 NIGHT VISION MONOCULAR



NETRO NM - 3000 is a multi functional, rugged, waterproof ultra-Lightweight night vision monocular. It is an ideal surveillance and observation device that can be either held in the hand or mounted on the head, helmet or weapon

Feature

- Light Weight, Waterproof and Rugged Bright Light Cut-off Conforms to MIL Standards
- All weather capability -water proof,dust proof and corrosion free Easy to maintain
- Magnification: 1x
- Field of View: 45° (min)
- Diopter Adjustment: -6 to +4 diopter.
- Operating Temperature: -40°C to +55°C.
- Environmental Standards: MIL-STD-810G compliant.

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799

NETRO TH - 4000 HAND HELD THERMAL IMAGER



NETROTH - 4000 from MKU is a combat-proven hand held Thermal Imager.

Modern Design with Military Ruggedness

Rugged & waterproof, NETRO-TH-4000 is a MIL-SPEC 810-G compliant device capable of effectively operating under harshest environment. The NETRO-TH-4000 comes with high quality thermal sensor.

Feature

- Conforms to MIL Standards and Sturdy.
- Intuitive Joystick Control.
- Device is easy to Maintain.
- All weather capability water proof, dust proof and corrosion free.
- Simple Twist & Go (T&G) Battery Packs. Comes with both a Rechargeable Pack and an alternative T&G converter pack for use with AA Batteries (6 x AA Batteries).
- Video output system is available

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

NETRO TH - 4100 THERMAL IMAGING MONOCULAR



NETRO TM -4100 from MKU is a combat-proven Thermal Imaging Monocular.

Modern Design with Military Ruggedness

Rugged & waterproof, NETRO TM-4100 is a MIL-SPEC 810 compliant device capable of effectively operating under harshest environment. The NETRO TM-4100 comes with high quality thermal sensor.

Range Estimation Scale

NETRO TM-4100 offers superiority range estimation scale combined with the well graduated reticule facilitates.

Feature

- Conforms to MIL Standards
- In-built system for marking range
- Real time video output
- Easy to maintain
- All weather capability-water proof, dust proof and corrosion free
- External Video Output: PAL
- Operating Temperature: -40°C to +55°C.
- Environmental Standards: MIL-STD-810G compliant.

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India

T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

NETRO TW - 4000 THERMAL WEAPON SIGHT



NETRO TW-4000 thermal weapon sight is equipped with a high resolution thermal imaging camera and an in-built system for marking range. It is MIL-1913 compatible and can be mounted on a range of weapons including small arms and heavier guns.

Feature

- Conforms to MIL Standards
- In-built system for marking range
- Real time video output
- Easy to maintain
- All weather capability -water proof, dust proof and corrosion free
- External Video Output: PAL
- Operating Temperature: -40°C to +55°C.
- Mounting: MIL-STD-1913 picatinny rail
- Environmental Standards: MIL810G compliant.

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

CERAZONE V

MKU OFFERS THE FOLLOWING RANGE OF CERAZONE SOLUTIONS FOR THE ABOVE THREATS:



Cerazone panels from MKU are made using a wide range of ceramics including advanced ceramics and various fiber combinations. They are cost effective, offer multi hit capability and can be pre-engineered into different shapes. Cerazone solution from MKU consist of wide range of Ceramics like Alumina, Sic, B4C etc as per the mission requirement.

Cerazone panels offer protection against most current threats including

- NIJ 0108.01 Level IV
- STANAG 4569 AEP-55 (Level II to IV)
- EN 1522 Level FB-5 to FB-7

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India


T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com



FLEXAR



Manufactured using Aramid fibers and special rubber materials, Flexar panels are light weight and flexible. They are resistant to corrosion & chemicals, are water repellent and can perform in high temperature zones. They can also be used as 'Fragmentation Blankets' for floors and back of the vehicle seats. They are excellent backing materials for ceramite armour panels and negate mortal damage(s) to the occupants due to secondary fragmentation from armor piercing rounds or IED projectiles when they hit the primary armor or vehicle hull.

Flexar panel offer protection against

- Up to NIJ 0108.01 Level IIIA
- Up to EN 1522 Level FB-4

Properties

- Fabric Type: Plain weave
- Density: 1.44 g/cm³
- Tensile Strength: 2.3 Nm/dtex
- Breaking Strength: Warp direction: min 16.2 N/5 cm, Weft direction: min 17.4 N/5 cm
- Flammability: Tested and certified as per "IS-11871-1986; method B" (Inclined) not to ignite.
- Heat Resistance: The maximum working temperature for Flexar panels is 800 due to rubber matrix.

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799

POLYSHILED V



Made using UHMWPE (Ultra High Molecular Weight Polyethylene), Polyshield panels demonstrate high buoyancy and offer multi hit capability. These panels are resistant to cracks, UV radiation, moisture, acid, oil and corrosion and have exceptional FST (Fire,Smoke,Toxicity) properties.

Polyshield panels offer protection against

- NIJ 0108.01 Level IIIA to III+
- EN 1522 Level FB-4 to FB-7

Properties

- Melting Range: 150 C - 200 C
- Flammability: Non flammable
- Temperature Resistance: -40 C to 0 +65 C
- Chemical Resistance: Resist almost all chemicals
- UV Resistance: No effect
- Moisture Resistance: Inert to moisture

Contact Person

MKU Limited 13, Gandhi Gram

Kanpur - 208 007 (UP) India


T: +91-512-3026700

F: +91-512-3026799

E: protection@mku.com

SPALLIN

SOFT ARMOR SPALL LINERS OFFER PROTECTION AGAINST 1.1 GR FSP, 2.8 GR FSP, 7.62 MM FSP, 12.7 MM FSP (TESTED IN ACCORDANCE WITH STANAG 2920).



Occupants of armoured vehicles face additional threats from steel fragments and splinters generated upon impact of high energy projectiles on the steel shell and reinforcements of the vehicle. Spall liners help contain and prevent such fragments from striking the occupants. Spall liners also offer noise and heat insulation and can be cut and drilled using standard equipment.

MKU offers UHMWPE, Aramid and E-Glass spall liners for combat vehicles, ships and aircraft. These not only provide protection from steel fragments and splinters but also provide excellent reinforcement to the areas and parts of the vehicle that carry structural load due to the high compressive properties of the material. Glass spall liner offer high resistance to corrosion, are light weight and provides good ballistic protection.

Benefits of Spall Liner

- Ideal for protection from all kinds of secondary fragments.
- Easily to install by the crews on due to the unique modular designs of the kit and patented attachment systems.
- Available in either rigid or flexible options as per requirement.
- Unaffected by moisture that might seep into the vehicle.
- Excellent noise and heat insulation properties.

Contact Person

MKU Limited 13, Gandhi Gram
Kanpur - 208 007 (UP) India
T: +91-512-3026700
E: protection@mku.com

F: +91-512-3026799

TRANSPARENT ARMOUR



MKU transparent armor (BP Glass) solutions are built to offer protection against the highest threat levels (in no spall configurations). These are manufactured to strict quality standards and are tested for optical distortion, secondary image separation, boiling, radiation, moisture, temperature cycles and ballistic performance. They can withstand temperature changes from -40 oC to +72 oC and are available for a wide range of protection levels.

Transarm panels offer protection against

- NIJ 0108.01 Level IIIA to IV
- EN 1522 Level FB-4 to FB-7
- STANAG 4569 Level I to IV

Property

- Melting Range: 150 C - 200 C
- Flammability: Non flammable
- Temperature Resistance: -40 C to +65 C
- Chemical Resistance: Resist almost all chemicals
- UV Resistance: No effect
- Moisture Resistance: Inert to moisture



Contact Person

MKU Limited 13, Gandhi Gram
 Kanpur - 208 007 (UP) India
 T: +91-512-3026700
 E: protection@mku.com

F: +91-512-3026799



ORDNANCE FACTORY BOARD

- Address** : **All Correspondence/Letters to be addressed to:**
The Secretary, Ordnance Factory Board, Ayudh Bhawan,
10-A, S. K. Bose Road, Kolkata - 700001, India
- For Export:**
Marketing & Export Division [ICE Div]
Ordnance Factory Board
Ayudh Bhawan, 10-A, S. K. Bose Road
Kolkata - 700001, India
- Website** : www.ofbindia.gov.in
- Head** : DGOF & Chairman, Ordnance Factory Board
- Telephone** : +91-33-22430472-0476, 33-22485077-5080,
33-22489121-9127
- Fax** : +91-33-22482927
- Email** : sec.ofb@nic.in; export.ofb@nic.in

ORGANISATION PROFILE:

The Indian Ordnance Factories organisation - a family of 41 Ordnance Factories under the aegis of its corporate headquarters **Ordnance Factory Board, Kolkata** - possesses the unique distinction of over 200 years experience in defence production. We are engaged in production, testing, logistics, research, development and marketing of a comprehensive product range in the area of land, sea and air systems.

The patronage we receive both in India and abroad speaks of our quality of products and services. Undoubtedly, we are the force behind armed forces.

Indian Ordnance Factories is the oldest and largest industrial setup which functions under the Department of Defence Production of the **Ministry of Defence**. The ordnance factories form an integrated base for indigenous production of defence hardware and equipment, with the primary objective of self reliance in equipping the armed forces with state of the art battlefield equipments.



RIFLE EXCALIBUR 5.56 MM

Derived from the famous INSAS weapon systems of India which have been tested in large scale infantry combat, anti-terrorist and mob control situations, this weapon is called the INSAS EXCALIBUR MARK-I incorporates, in addition to the features of earlier INSAS Weapons, certain characteristics which makes it truly the ultimate sword- THE EXCALIBUR. The reasons for calling it Excalibur are that it incorporates the features of a weapon which is rugged for battlefield engagements and at the same time capable of being light and easy to handle during low intensity conflict and CQB situations. It has ergonomically designed with folding butt and can fire 20-30 rounds magazines. It is also fitted with picaatinny rails for mounting of opto electronic devices.



Specifications

Calibre	5.56mm
Length-Butt Folded/Butt Extended	665mm/895mm
Weight without Magazine	3.81 kg.
Weight with Full Magazine	4.03 kg
Weight of Empty Magazine	0.09 kg.
Magazine Capacity	20/30 rounds
Length of Barrel	400 mm
Barrel Chamber and Bore	Chrome Plated
Rifling (No. of Grooves/Twist/Direction)	6/1 turn in 200 /RH
Sight (Front /Rear/ Range Graduation/Radius)	Post type/aperture/200 mm & 400mm/475mm
System of Operation	Gas operated
Mode of Fire	i). Single Shot ii) Automatic
Rate of Fire (rounds/min)	650 to 700
Effective range	400 m

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

5.56 MM INSAS RIFLE (FOLDABLE BUTT)

It resembles 5.56 mm Assault Rifle Fixed Butt in all other features except that the Fixed Butt is replaced with a foldable type of Butt to shorten the overall length and it does not include automatic mode of firing.

It is most suitable for combat from ICV and in Para Troopers role.



Technical Data

Calibre	5.56mm
Length in folded condition	750 mm
Weight of weapon	
Without magazine	4.25 kgs.
With full magazine	4.6 kgs.
Recoil Energy	4.43 Joules
Barrel Chrome plated	
PNS/Daylight Telescope	Provided
Range 400 m	
Mode of Firing	Single shot, three round burst. Gas operated.

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

RIFLE 5.56 MM INSAS (FIXED BUTT)

Accurate lightweight rifle, compact and handy, suitable for terrestrial and maritime assignments.

Gas-operated rifle can fire in single shot and three round burst (TRB) for conservation of ammunition. A simple action of lever change allows selection of single shot, TRB and safe position.

Additional mechanical safety is provided by means of safety sear and built-in delay in breech mechanism.

Easy to assemble and dismantle, chrome-plated barrel and chrome-plated pin firing ensures maintenance free long life.

Compatible with NATO standard ammunition 5.56 x 45 mm SS 109, M 193.

Quick mounting of Passive Night Sight/ Daylight Telescope.

Stock, Pistol Grip and Hand Guard made of impact resistant plastic in leaf brown colour.

Magazines are made of translucent UV stabilised polycarbonate Resin.

Multipurpose bayonet functions as Saw, Wire cutter, Bottle opener, Knife, Screw driver, Hammer and Dagger.

Eliminator Flash is designed to adopt Blank firing attachment.

Block gas and grenade sight provided for firing multimode grenade and M-36 grenade.

Provision of mounting of 40 mm under Barrel Grenade Launchar.

Provision of fitment of Day light Telescope and passive night sight.



Specifications

Calibre (mm)	5.56	
Muzzle Velocity (m/s)	900	
Length of Rifle (mm)	Without Bayonet	960
	With Bayonet	1110
Weight of Rifle (Kg)	4.15	
Without Magazine & Bayonet		
Effective Range (m)	400	
Range for Grenade (m)	200	
Multi Mode	150	
M 36		
Magazine Capacity (Rounds)	20	



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

Cyclic Rate (Rounds/min)	600 to 650
Trigger Pull (Kg)	2.10 to 4.00
Recoil Energy (Joules)	4.43
Rifling.	6 grooves R.H 1 in 200 mm.
Sight	Fore sight : Post Type Rear sight : Aperture type
Type of fire	Single, 3 Round Burst

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>



AMOGH 5.56MM CARBINE (JVPC)

- AMOGH Carbine 5.56 mm is specially designed and developed for close quarter battle (CQB) role.
- It fires 5.56 x 30 mm ammunition specially developed for carbine role.
- The weapon is ergonomically designed, light in weight, easy to carry, handle, operate and maintain
- Barrel of the weapon is chromium plated for longer life.
- It has ambidextrous lever change operation.
- It is provided with Reflex sight & Bayonet as accessories.



Specifications

Calibre	5.56 mm (5.56 x 30 mm ammunition)
Length of Weapon - (a) Butt Folded	575 mm
	- (b) Butt Extended 800 mm
Weight - Weapon (without Magazine)	2.95 kg
Weight - Magazine (empty)	80 gms
Weight - Cartridge	8.0 gms
Effective Range	200 m
Rate of Fire	700 rpm
Sight Radius	420 mm
Feed	30 rd Box Magazine
Operation	Gas operated
Mode of Fire	Single & Auto
Mechanism	Rotary bolt. Closed Breech
Rifling	6 Groves, 1 : 200mm
Sight	1. Open Sight
	2. Reflex Sight
Muzzle velocity	700 m/sec
Safety	1. Applied
	2. Mechanical



EQUIPMENT CATALOGUE

Barrel

Length of Barrel	330 mm
Bore Diameter	H - 5.612 mm L - 5.577 mm
Number of Rifling Grooves	6
Twist of Rifling Grooves	Right Hand
Lead of Rifling Grooves	1 Turn in 200 mm

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>



LMG 5.56 MM INSAS (FIXED BUTT)

Role

- The weapon is used for providing covering fire during assault by infantry.

Function

- LMG 5.56 mm is a gas operated weapon with rotating bolt locking system which can fire in S.S./Auto system



LMG: Technical Data

Nomenclature	Unit	LMG 5.56 mm INSAS (Fixed Butt)
Calibre	mm	5.56
Wt. w/o Magazine	kg	6.23
Wt. w/loaded Magazine	kg	6.73
Length Overall	mm	1050
Barrel length	mm	535
Sight Radius	mm	475
Magazine Capacity	Rds	30
Fire selection	Rds	SS/Auto
Rate of fire (cyclic)	Rpm	650
Effective range	m	700
Muzzle velocity	m/s	925
Muzzle energy	J	1780
Recoil energy	J	2.75

Safety

The system is provided with mechanical & applied safety.

General Characteristics of LMG 5.56 MM INSAS

- i. Light weight weapon
- ii. Commonality of parts amongst the LMG and Rifle, 5.56 mm INSAS.
- iii. Weapon is very compact, easy to handle, operate and simple to maintain.
- iv. Weapon robust enough to withstand rough usage.
- v. Furniture made of Plastic materials
- vi. Foldable Butt version also available to suit paratroopers.
- vii. Barrel Bore Chrome plated for high Barrel life and ease of maintenance.



- viii. Provided with mount for day light telescope & passive night sight.
- ix. Provision for mounting on tripod on armed vehicles for Anti-Air Craft role & Monopod for fixed line firing.

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>



GUN MACHINE 7.62 MM (MAG) 2A1

The weapon is designed to serve the role of a medium machine gun and is fired from a tripod mounting. It is fully automatic, air cooled, belt fed, gas operated weapon capable of a sustained high rate of fire in bursts. The gun fires from open breech thus preventing any explosion of a cartridge (cook off) after prolonged firing. The gun is provided with a heavy/light barrel, the bore and chamber of which are chromium plated. The weapon is supplied with a gun barrel and a spare barrel which can be quickly and easily changed to avoid over heating which causes cook off and reduction in barrel life. The gun is fed from left to right with belts of disintegrating link which are ejected to the right. Empty cartridge cases are ejected downwards.



Specification

Calibre	7.62 mm
Weight of Gun	11 Kgs
Overall length	1048 mm
Rate of Fire	Adjustable 600 to 1000 rounds /Minute
Max Range	1800 M
Belt	Disintegrating Link
Total No of Components	219
Sight Rear Aperture Graduated	Steps of 100 M
Folded Down	200 to 800 M
Extender	800 to 1800 M
Barrel :	
i) Length of Barrel	545 mm
ii) Bore Dia	H 7.655/L 7.61mm
iii) Number of Grooves	4
iv) Pitch of Rifling	1 Turn in 305 mm
v) Twist of Rifling	Right Hand



Ammunition

7.62 mm NATO Ball Ammunition

Contact

Marketing & Export Division

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>



ASSAULT RIFLE 7.62 MM [FIXED & FOLDABLE BUTT] (TAR)

Role

The weapon is ideal for counter insurgency using 7.62 X 39 mm ammunition. It is robust enough to withstand rough usage. Barrel of the weapon is Chromium plated for longer life. The rifle is also provided with a Hold open device for cooling and inspection of chamber & Lock retainer which makes opening & closing of cover easy.



Function

Assault Rifle 7.62 mm is a gas operated weapon with rotating bolt locking system which can fire in single shot / auto mode.

Technical Characteristics

1. Calibre	7.62 mm		
2. Length	Fixed Butt	900 mm	
	Foldable Butt	Butt Extended	890 mm
Butt Folded		660 mm (Bottom Folding)	
3. Weight (without magazine & Sling Assy.)	Barrel	414 mm	
	Fixed Butt	3.08 Kg.	
	Foldable Butt	3.27 Kg.	
4. No. of Riffling Grooves	4		
5. Operating	Gas, Selective Fire (Auto)		
6. Locking	Rotary Bolt		
7. Feed	30 Rds. Box Magazine		
8. Sight	Fore-Pillar.		
	Rear-'U' Notch, Graduated, Ramp type 100-800		
9. Effective Range	400 M		
10. Sight Radius	376 mm		
11. Rate of Fire (cyclic)	600 Rds / Min		
12. Muzzle Velocity	670 M/S		
13. Muzzle Energy	1750 J		

Safety

The system is provided with mechanical and applied safety

Salient Features

- Fires 7.62 x 39 mm ammunition.
- An ideal weapon for counter insurgency.
- Compact design, easy to carry, handle, operate and maintain.
- Robust enough to withstand rough usage.
- Chromium plated barrel for longer life of weapon.
- Hold open device for cooling and inspection of chamber.
- Available in fixed butt and bottom folding butt version.

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

UNDER BARREL GRENADE LAUNCHER 40 MM

A low weight, low recoil, long range and accurate Under Barrel Grenade Launcher ideal for use with Rifles 5.56 mm and with Rifles AK-47 type.

The device offers an ideal blend of features and ergonomic comfort to the soldier.



Features

1. Can be fitted on Rifles 5.56 mm as well as on Rifles AK-47 type
2. 3-point attachment to Rifle gives rigidity for fitment
3. In-built safety to prevent accidental firing
4. Breech loading enables easy loading and unloading of ammunition
5. Pump action along with conventional extractor makes extraction and ejection for cartridge case easy
6. Location for trigger enables firing for both Rifle and UBGL without change in firing posture
7. Hard anodizing on all aluminium alloy components for wear resistance and for better thermal barrier properties
8. Low recoil ammunition enables shoulder firing
9. Simple and easy operated ladder sight
10. Provision of Beta light source for firing in low light conditions
11. Fires ammunition common with Multi Grenade Launcher
12. Wide choice of ammunition for different roles
13. Available in stand-alone version also

Technical Information

Calibre	40 x 46 mm
Effective Range	28 to 400 m (approx)
Loading	Breech Loading
Barrel Length	350 mm
Barrel Rifling	6 grooves RH
Overall length	450 mm
Weight of Launcher	1.5 kg



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

Muzzle velocity	70 m/s
Recoil energy	17 Joule
Safety	In built safety for trigger operation and barrel locking

Sighting System

Foresight	Post Type
Backsight	Ladder Sight with 50m steps
Indirect Firing (300m/400)	Illuminated bubble sight
Night firing	Sights Illuminated with Tritium source

Ammunition

Type of Grenade	HE, HEDP, RP, SMK, TPT
Length of complete round	103 mm
Length of projectile	82 mm
Fuze Arming	9 to 28 m
Lethal Radius	5 m
Mass	
• Complete round	230 gm
• Projectile	180 gm
• Fragment	120 mg

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>



84MM RCL MK-III

Preamble

The 84 mm RCL CARL-GUSTAV M3 (henceforth called the M3, or the weapon) is of the breech loaded and laterally percussion fired type. The barrel consists internally of a steel liner. Around this liner a laminate of epoxy and carbon fibre is wound. The weapon is recoilless as part of the propellant gases escape rearwards through the venturi, equalizing the recoil force.



The weapon can be fired from the standing, kneeling, sitting and prone positions.

The normal sight of the weapon is the telescopic sight, the open sights being an auxiliary means of aiming.

Technical Datas

Weight of transport package packed with weapon and accessories	29 Kg
Dimension of transport package	1173x453x268 mm
Weight of weapon complete with telescopic sight and bipod	10 Kg Approx
Weight of telescopic sight	0.75 Kg. (1.7 lb)
Weight of bipod	0.25 Kg. (0.6 lb)
Length of gun	1065 mm (41.9 in)
Practical rate of fire	about 6 RPM

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

PISTOL AUTO 9 MM1A

A Personal and special service weapon capable of semi-automatic fire. It is a recoil operated, magazine fed, self-loading pistol in which the breech is positively locked at the moment of firing. It is not fully automatic. The trigger has to be pressed and released for each shot. When all the cartridges have been fired and the magazine is empty, the mechanism is held in the open position by the action of the slide.



Specification

Calibre	9mm
Weight with magazine empty	0.935 kg
Weight with magazine loaded	1.075 kg
Length Over all	205 mm
Barrel length	120 mm
Magazine Capacity	13 rounds
Ammunition used	Cartridge SA Ball 9 mm MK.2z(Parabellum)
Rifling	6 grooves, 1 turn in 254 mm, R.H.
Muzzle Velocity	396.23 m/sec.
Number of components	54
Range	50 mts

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

12 BORE PUMP ACTION GUN

The 12 Bore Pump Action Gun has been specially developed for use as a security weapon. It is a single barrel breach loading weapon superior to 12 Bore DBBL. It is provided with a tubular magazine, which holds 4 nos. of 12 Bore Cartridges and is placed parallel to and below the barrel. Extraction, loading and cocking of the cartridges take place in a single 'pump action' by operating handle, sliding along the magazine. Due to rapid reloading by pump action and spread of shots, it is an ideal weapon for counter ambush tactics.



Specifications

Weapon	Single Barrel Breach Loading
Calibre	12 Bore (18.578 mm to 18.628 mm)
Chamber	70 mm (2-3/4")
Length of Barrel	I. Civilian use - 510 mm (20") NPB II. Military / Police - 478 mm (18") PB
Ammunition	12 Bore 2.5" OR 12 Bore 2.75"
Magazine Capacity	4 Rounds
Weight	3.05 kgs.

Applications

- Banks security
- Anti insurgent applications
- Industrial security
- Personal security
- Sporting Arm
- Anti Riot role by use of Rubber Ball non-lethal ammunition

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

0.22" REVOLVER



Calibre	0.22"	
Weight	380 gms	
Barrel length	66 mm	
capacity	8 rounds	
Ammunition	0.22" x 24.8 mm	
Grip	Wooden	
Overall size	Length	187 mm
	Width	116 mm
Range	20 Metres	
Action	Single and Double both	
Pin Firing	Floating	

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 2103 / 2248 5077-80

E: ofbtrade@dataone.in

F: +91-33-2248 1748/2210 8235

w: <http://www.ofb.gov.in>



.30 - 06 SPORTING RIFLE

.30 - 06" Sporting Rifle is a precision & accurate Bolt Action Refle incorporating the latest modular design and ergonomics features. The weapon uses 0.30" Rimless ammunition and provided with adjustable Rear & Foresight. Dovetail for accommodating optical sight can be mounted on the top of Body of the Rifle. The weapon has also provided with positive mechanical safety.



Specifications

Calibur	0.30"
Bolt Type	Direct Lug Locking with the Barrel
Total Length	1125 mm
Barrel Chrome Flash with 4 Grooves	
Trigger Pull	1.5 Kg (Max)
Magazine Capacity	3 Rounds
Weight	3.0 Kg
Sight	
(I) Fore Sight	Adjustable ramp type
(II) Rear Sight	Adjustable ramp type from 100m to 400m graduation in step of 100m
Range	400 m

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
 10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 2103 / 2248 5077-80

E: ofbtrade@dataone.in

F: +91-33-2248 1748/2210 8235

w: <http://www.ofb.gov.in>

REVOLVER 0.32 (7.65 MM X 23) NIRBHEEK

Role

Light weight, easy to handle weapon, suitable for personal safety.

Function

32 (7.65 mm) Revolver is capable of firing 6 rounds, loaded in revolving chamber. Misfiring of a round does not affect next firing.



Safety

Positive location of main spring eliminates malfunctioning and additional safety feature provided to prevent accidental firing

General Characteristics of Revolver 0.32 (7.65 MM)

- I. Simple in design & sturdy in construction
- II. Positive location of main spring eliminates malfunctioning
- III. During non-functioning of weapon, springs are not under fatigue
- IV. Misfiring of a round does not effect next firing
- V. Accuracy aimed at high standards
- VI. High grade of alloy steel with heat treatment achieve durability
- VII. Interchangeability of parts ensured
- VIII. Provided with additional feature of safety to prevent accidents

Technical Data

Nomenclature	Revolver 0.32 (7.65 mm)	
Calibre	7.65 mm	
Weight (Without Ammunition)	0.7 kg	
Length of Revolver	177.8 mm	
Effective length of Barrel Bore	76.2 mm	
Rifling	Six Grooves R.H. 1 Turn/380 mm	
Sights	Fore Sight	Blade
	Back Sight	'U'
Feed	Revolving Chamber, 6 Rounds	

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
 10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 2103 / 2248 5077-80

E: ofbtrade@dataone.in

F: +91-33-2248 1748/2210 8235

w: <http://www.ofb.gov.in>

155-MM HE-ERFB BB

Purpose

Rapid and accurate firing at long ranges to attack the ground targets.



Characteristics

Mass of Shell without Fuze	45.2 to 47.77 Kg.
Overall length of Shell	861 mm
HE Composition	TNT - 99%
	N.C - 0.5%
	PNT - 0.2%
	HNS - 0.3%
Compatible Fuzes	PDM - 572 CI & M85 P13 A3
Compatible Charge	Charge 8 & Charge 9

Performance

Maximum Range	38.4 Km
Maximum Chamber Pressure	345 ± 8 Mpa
Storage Temp.	210C ± 20C
Operating Temp.	- 200C to 600C
Shelf Life	10 years

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
 10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.com>

155-MM HE-ERFB BT

Purpose

Rapid and accurate firing at long ranges to attack the ground targets.



Characteristics

Mass of Shell without Fuze	42.84 to 45.34 Kg.
Overall length of Shell	843 mm
HE Composition	TNT - 99%
	N.C - 0.5%
	PNT - 0.2%
	HNS - 0.3%
Compatible Fuzes	PDM - 572 CI & M85 P13 A3
Compatible Charge	Charge 8 & Charge 9

Performance

Maximum Range	30 Km
Maximum Chamber Pressure	345 ± 8 Mpa
Storage Temp.	210C ± 20C
Operating Temp.	- 200C to 600C
Shelf Life	10 years

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
 10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.com>

125 MM HEAT

125 mm Ammunition is used with tank T-72 as main gun ammunition. The gun 125 mm is having smooth bored barrel, sophisticated sighting system and automatic loading gear ensures high effective rate of fire order of 8 rounds/ min and total 39 rounds are carried in the tank.

The Ammunition is of separate loading type to suit auto loader and is fin stabilised.

The complete round comprises of two main points.

- | | |
|----------------------|----------------------------------------------------------------------------------------------------|
| a) Cartridge | It comprises of semi-combustible cartridge case, Primer
GUV-7 and propellant with two igniters. |
| b) Shell 125 mm HEAT | It comprises of Fuze B-15, filled shell, Tail unit Assy.,
Distance Tube and Tracer. |



Role

The main role of this ammunition is for direct fire against tank, SP gun, mortar and heavy armoured targets. It is effective against targets fitted with protective devices such as skirting plates and grids. It can also be used against concrete bunkers. The shell is aerodynamically stabilised by means of 6 fins initially folded which open in flight.

Function

- a) On firing, set back plunger of the fuze sets back and the ball gets rolled out from the cavity and unlocks the shutter. At the same time, set forward plunger also sets back. Due to taper on the plunger the ball moves in the cavity of the shutter and locks it in unarmed position.
- b) During flight, when set back force ceases, set forward plunger re-asserts to its original position aided by the spring and set forward force, causing the ball to roll out, thus unlocking the shutter. The shutter slides in the armed position by torsion spring making detonator and crystal unsorted.
- c) On impact, nose of the fuze is crushed in and the impact on piezo crystal generates an electric pulse which is passed to the detonator in the shutter. The detonator functions and detonation wave is passed to the booster. The booster pellet is positioned at the bottom of the lower pellet. A conical resonator having central hole accommodating the tip of the copper cone is placed at the base of the filling embedded in the lower pellet and thus the resonator helps in effective jet formation of detonation wave.

Specification / Characteristics

a)	Mass of complete round	29.0 kgs
b)	Muzzle velocity at +15°C	905 m/s
c)	I. Maximum Range	4000 m
	ii. Point blank Range	960 m
d)	Armour thickness defeated at	
	I. Normal attack	500 mm
	ii. 60 degree angle of attack	220 mm
e)	Max. chamber pressure at +15°C (True)	353 Mpa

Quality

Strict quality measures is adopted during filling and assembly. Added to this, functioning proof is carried out in association with Service Quality Assurance Agency.

Safety

- a) Piezo crystal is shorted in unarmed position of the shutter thus making the fuze safe for handling, storage and transportation.
- b) The detonator is shorted and this prevents passage of electric impulse if accidentally developed, during handling, storage and transportation.

Besides above, multiple mechanical safety arrangements have been provided in the fuze to ensure total safety during handling and transportation.

Reliability

The ammunition has high degree of reliability due to electrical/percussion alternative available in the Primer design. It is highly consistent and accurate due to the basic design features and strict quality control at all stages of production.

Shelf Life

The shelf life for individual items are as follows :

Cartg. Case	05 Years (Prov)
HE from shell	15 Years
Propellant	10 Years
Primer GUV-7	05 Years
Fuze B-15	10 Years
Tracer	07 Years

Packing

One cartridge is packed in a metallic container hermetically sealed which is further packed finally along with one shell in a wooden box.

Stowage Dimension

Stowage dimension of wooden box is 863 mm x 540 mm x 292 mm. & Steel box drg. no. C-52A - 755 mm x 430 mm x 230 mm.



EQUIPMENT CATALOGUE

Hazard Classification

Compatibility	F
Hazard Division	1.1
Fire fighting classification	1

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.in>



MAIN BATTLE TANK AMMUNITION 120 MM FSAPDS

Use of MBT Ammunition of 120mm Calibre became inescapable in the modern warfare and is the answer to counter attack the enemy. The combustible Cartridge Cases/Primers have been introduced in order to derive optimum performance advantages as compared to conventional brass Cartridge cases at high chamber pressure specially in FSAPDS/Proof shot Rounds

Three versions are available

- a) FSAPDS
- b) Proof shot representing FSAPDS
- c) HESH



Brief Description

Rd 120mm FSAPDS (Fin Stabilized Armour Piercing Discarding Sabot) as a primary ammunition.

Role

Capable of defeating NATO Targets up to 4000 Mtrs distance.

Specification

a) Length of complete round	994mm
b) Weight of complete round	20.2 Kgs
c) Type of propellant	NQ/M 119
d) Weight of Propellant Charge (Normal)	8.3 Kgs
e) Weight of	
1. SCCC Liner	0.780 Kgs
2. Steel Cup	3.4 Kgs
3. Primer	0.490 Kgs
f) Weight of projectile	6.8 Kgs
g) Weight of Bursting Charge	–
h) Type of Primer	SCP Mk II B
i) Tracer	No. 33
j) Fuze	–
k) CG (From Base cup)	425 mm
l) Muzzle Velocity	1650 m/s
m) EFC value	1.00

Performance Characteristics

1 st Rd. HIT probability should be 90%.

Quality Standard

Same as above

Shelf Life

10 years

Packing

Firstly, the round is packed in paper roll cylinder and the cylinder is then packed in the wooden box with casing in two halves being used for cushioning.

Stowage Dimension

The external dimension of the boxes with batten is 1225 mm x 360 mm x 360mm and each box occupies a space of 0.16 Cu. M. One round is packed in one box.

Hazardous Classification

Compatibility group	E
Hazardous Division	1.2
Fire Fight Division	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.in>

MAIN BATTLE TANK AMMUNITION 120 MM HESH

Use of MBT Ammunition of 120 mm Calibre became inescapable in the modern warfare and is the answer to counter attack the enemy. The combustible cartridge Cases/Primers have been introduced in order to derive optimum performance advantages as compared to brass cartridge cases at high chamber pressure.

Three versions are available

- a) FSAPDS
- b) Proof shot representing FSAPDS
- c) HESH



Brief Description

Rd. 120 mm HESH (High Explosive Squash Head)

Role

Capable of engaging targets up to 2500 Mtrs. should be capable of defeating 135 mm RHA plate up to 1100 Mtrs distance

Specification

a) Length of complete round	998 mm
b) Weight of complete round	22.2 Kgs
c) Type of propellant	AP/S 400-120
d) Weight of Propellant Charge (Normal)	3.3 Kgs
e) Weight of	
1. SCCC Liner	0.780 Kgs
2. Steel Cup	3.4 Kgs
3. Primer	0.620 Kgs
f) Weight of projectile	14.4 Kgs
g) Weight of Bursting Charge (RDX: WAX 88:12)	2.95 Kgs
h) Type of Primer	L1A4 MK II
i) Tracer	No. 30
j) Fuze	L29A3 base
k) CG (from Base cup)	552 mm
l) Muzzle Velocity	736 m/s
m) EFC value	0.33

Performance Characteristics

Should be accurate up to 1100 mtrs. and it should be capable of engaging targets up to 2500 mtrs.

Shelf Life

10 years

Packing

Firstly, the round is packed in paper roll cylinder and the cylinder is then packed in the wooden box with casing in two halves being used for cushioning.

Stowage Dimension

The external dimension of the boxes with batten is 1225 mm x 360 mm x 360 mm and each box occupies a space of 0.16 Cu. M. 1 round is packed in one box.

Hazardous Classification

Compatibility group	E
Hazardous Division	1.1
Fire Fight Division	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.in>

BOMB 120 MM MORTAR SMOKE PWP

Role

The Bomb is basically smoke type screening ammunition in the combat field, creating a dense smoke screen and facilitating tactical deployment of own troops and vehicles evading from enemy firing.



Function

The Bomb is fired from 120mm Mortar, smooth bore, muzzle loading weapon. The direct action percussion fuze initiates the Bomb to burst at the target instantaneously and generate the white smoke uniformly. The Bomb can generate the white screening smoke at the target for a period of 20 secs and the time required for the build up of the smoke is 5 secs.

Specification /characteristics

- | | |
|----------------------------|------------|
| a) Mass of the filled bomb | 13.225 kgs |
| b) Muzzle velocity | 331 m/sec |
| c) Max range | 6512 m |

(Variable ranges can be achieved by adjusting no. of augmenting cartridges)

Advantages

- a) The Bomb is capable of screening the area with dense white smoke uniformly without any pillaring effect.
- b) The design adopted in the Fuze Mechanism prevents the fuze from premature arming when air dropped

Quality

Strict quality measures are adopted during all stages of manufacture of components, filling assembly and packing. Each component used is proved/inspected separately before being released for filling/assembly. In addition, functioning, /dynamic proof is carried out in association with Service Quality Assurance Agency. The Bomb is filled and assembled in lots of 2000 Nos.

Safety

Multiple Mechanical Safety devices have been provided in the Fuze to ensure total safety in handling and transportation.

Reliability

- a) The Mortar 120mm has got a high angle of fire and high degree of accuracy.
- b) Due to the simple design of the direct action percussion Fuze, the Bomb is capable of functioning in all conditions.

Shelf Life

The shelf life of filled Bomb is 10 years.

Packing

The packing consists of one inner packing and an outer packing. The inner packing is water proof laminated paper container in which one Bomb is packed. Two such containers are packed in a sturdy steel box. The laminated paper container used is capable of protecting the Bomb in all adverse weather conditions.

Stowage Dimension

The Stowage dimensions of the packed steel box are 800 mm x 349 mm x 177mm to hold two bombs.

Gross weight of the package is 44 kgs

Hazard Classification

The Bomb is classified in

Compatibility group	H
Hazard Division	1.2
Fire Fighting Classification	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

SHELL 105 MM IFG HE

Role

IFG HE ammunition is one of the six different types of projectiles fired from the 105 mm Indian field gun. This ammunition is employed to demolish army concentrations, fortifications, bunkers and many other defence installations. This is suitable for use both in the plains as well as mountains.



Function

105 mm IFG HE ammunition is filled with high explosives, (TNT) and is fitted with fuze 117 MK 20. On hitting the target, the fuze functions and ultimately denotes the explosive charge. The stability of the ammunition is achieved by the spin.

Characteristics and Specification

a) Mass of the filled shell	16.97 kgs max
b) Muzzle velocity	591 M/sec (normal charge) 710 M/sec (super charge)
c) Maximum range	17600 m (Variable range can be achieved by using different types of cartg cases such as normal charge and super charge)

Special Features

Because of the greater range, high firepower and mobility of IFG, the ammn. can be very effectively used both in plains and mountains. The ammn. can be fired at all angles of elevation. To adjust the range, different types of charges such as normal charge and super charge are used.

Safety

Mechanical safety devices are incorporated in the fuze to avoid any premature functioning of the fuze during manufacture, handling and transportation.

Reliability

The IFG weapon has a very high angle of fire and is capable of a very high degree of accuracy. The high angle firing capability enables the gun to be fired as a howitzer.

Shelf Life

The shelf life of the filled ammunition is 30 years.

Packing

The packing consist of an inner container and outer package. Two shells packed in



EQUIPMENT CATALOGUE

laminated paper containers, are further packed in a wooden/steel boxes with suitable packing fitments to ensure snug packing.

Stowage Dimension

The stowage dimensions of one box wooden/steel (holding two shells in laminated container) is 741 mm x 210 mm x 352 mm.

Hazard Classification

The filled & packed shells are classified in

Compatibility group	F
Hazard division	1.2
Fire Fighting classification	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.com>



BOMB 81 MM MORTAR HE

General

This bomb is used in 81 mm Mortar which is a light smooth bore, muzzle loading weapon having high angle of fire and capable of a high degree of accuracy. It is a platoon weapon of the infantry. The equipment can be dismantled into 3 loads and can be carried by 3 men. It can be used for firing in battlefields, mountain warfare or air borne operations.



This bomb is a high explosive bomb streamlined in shape and is of the fragmentation type. It is fin stabilized and has fuze 162MK-8 at the forward end and a tail unit at the rear. Tail unit takes one primary and eight secondary cartridges. The bomb body is made out of steel (specifications JSS 9510-1). 81 mm Mortar bomb has a special feature i.e. it has 0 to 8 charges i.e. a total of 9 charges.

Physical Characteristics

Total length of Ammunition	379 mm
Max. dia of bomb	80.8 mm
Mass	4.2 ± 0.125 kg (without primary) and augmenting cartridges
Explosive filling	705 ± 5 gm T.N.T.
Explosive filling in primary cartridges	7.8 gm NGB 051

Performance Characteristics

Muzzle velocity	295 m/s
Max . Range	5000 Metres
Rate of firing	6 to 8 rounds per minute with Relaying and 20 rounds per Minute without relaying.

Special Features

The fuze assembled with the bomb is a direct action detonating type. The design adopted in the fuze prevents premature arming when air dropped.

Quality

Strict quality checks are observed during various stages of production. The bomb body as well as other components are proved / inspected before separately being taken for filling and assembly. Added to this, functional proving is carried out in association with the Services Quality Assurance Organisation. The bombs are filled and assembled in lots of 2000 Nos.

Safety

The fuze and other components design ensures total safety during handling and transportation .

Reliability

The Mortar has got a high angle of fire and is capable of high degree of accuracy. Due to the simple design of the direct action percussion fuze, the bomb is capable of functioning in all conditions.

Shelf Life

The shelf life is 30 years.

Packing

The packing consists of inner and outer packages. The inner package is a HDPE/LDPE carrier which accommodates two bombs and provides protection during transport and storage in all climatic conditions. This carrier is then packed a sturdy metallic carrier which holds two HDPE/LDPE carriers containing four bombs.

Stowage Dimensions

Package Dimensions	460 mm x 300 mm x 240 mm
Gross weight	25 kgs
Volume	0.033 Cu. m

Hazard Classification

Compatibility group	F
Hazard Division	1.2
Fire fighting classification	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

84 MM HE 441B

General

This ammunition is fired from Gun 84 mm RCL Carl Gustaf M2 from the shoulder. The cartridge combines some of the characteristics of Rocket and Artillery ammunition in its design. The ammunition is of fixed type and is spin established. This ammunition is intended for use against troops in the open and in slit trenches, machine gun posts soft skinned transport vehicles and similar types of targets. It is fitted with a combined mechanical time and impact fuze.



The design of the ammunition parts and functioning are like Artillery components excepting that the rear of the cartridge case is closed by a plastic blow out disc (base plate) which allows rearward escape of the propellant gas to make it recoilless and the ignition of the propellant is by a side-located percussion cap and an igniter composition.

The cartridge case is made of light aluminium alloy drawn to specification BS 1470 grade 6082 TF or IS 736 grade 64430 WP. At the rear, it is formed with a flange which is cut away over a length to take a guide while loading the round in the gun. At about 90 degree from the cut away flange a hole with two diameters is provided on the body of the cartridge case to take the percussion cap. The shell body is made of steel to specification DIN 17200 Code 25 Cr Mo 4 with carbon percentage 0.26 to 0.29. It encloses two inserts of neoprene rubber containing about 850 steel balls, the inserts surrounding the HE charge RDX/TNT. While filling the HE (RDX/TNT) a central cavity in two diameters is made to take two booster pellets and the time and impact fuze FFV447. The shell body takes the driving band of copper. The shell body is so designed that the danger area for rearward fragments from the point of burst is small. Propellant is NGB204 which is a ballistite propellant. The fuze FFV 447 is dual-purpose fuze of both impact and mechanical time types. This ammunition is of Swedish design and is manufactured to Government of India, Ministry of Defence Specification Number CQA0312 and Drawing No.F1301-115201C.

Physical Characteristics

Total length of ammunition	380 mm
Total mass of ammunition	3.1 kgs
Mass of projectile	2.3 kgs
Propellant (ACM)	0.4 kg
Explosive filling in primer (cap)	0.13 gms (Composition VH 2 & Zirconium)
Explosive filling in Igniter	15.0 gms (Composition Z47B & NC 110)

Explosive filling in Projectile	0.40 kg
Explosive filling in Fuze	3.08 gms
Net explosive content	803.36 gms.

Performance Characteristics

Muzzle velocity	240 m/s
Practical firing range upto	1000 m
Time of flight to 700 m	3.4 sec

Special Features

The weapon is of recoilless type and can be fired from the shoulder. It is assembled with a dual purpose fuze. On bursting of the projectile, the steel balls 850 (Nos) act as splinters.

Safety

The fuze does not get armed unless it is spun at 3500 rpm and thus the ammunition is safe during all stages of operation, storage and transport.

Reliability

Due to its sound design and careful manufacture, the ammunition is very reliable for use in combat field environment.

Shelf Life

The shelf life of the ammunition is 10 years

Packing

Two rounds are packed in twin containers made up of injection moulded tube of high density polyethylene. Three such twin containers (total 6 rounds) are packed in one wooden crate.

Stowage Dimension

Packing box size	660 mm x 463 mm x 356 mm
Gross weight	40.0 kgs
Net weight	24.6 kgs
Volume	0.108 cu.m

Hazard Classification

Compatibility group	F
Hazard division	1.2
Fire fighting class	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.com>



84 MM HEAT 651

General

This ammunition is fired from Gun 84 mm RCL Carl Gustaf M2 from the shoulder. The cartridge combines some of the characteristics of Rocket and Artillery ammunition in the design. The ammunition functions on the principle of shaped charge. The ammunition is of Swedish design.



The 84 mm HEAT ammunition is used against all types of armoured fighting vehicles, landing crafts, concrete bunkers and similar types of targets. In addition to its good penetrating power against these targets, the fragments of shell body have a high lethal effect on troops in close proximity to the target.

The ammunition is of fixed type. The design of the ammunition parts and functioning are like artillery components excepting that the rear of the cartridge case is closed by a plastic blow out disc (base plate), which allows rearward escape of gases, and ignition of propellant is by a side located percussion cap and an igniter composition. Cartridge case is made of light aluminium alloy drawn to specification BS 1470 Grade 6082TF or IS 736 Grade 64430 WP. At the rear, it is formed with a flange, which is cut away over a length to take a guide while loading in the gun. At about 90 degree from the cut away flange a hole with two diameters is provided on the body of the case to take the percussion cap. The shell body is made of light alloy to specification BS 1474 Grade 2014 ATF or IS 1285 Grade 24345 WP. Fuze FFV 651 is of Swedish design. Propellant NGB 204 is a ballistite propellant. This ammunition is manufactured to Government of India, Ministry of Defence Specification No. CQA 0310 and drawing number F1321-204571E.

Physical Characteristics

Total length of ammunition	538 mm (Approx)
Total mass of ammunition	2.8 kgs (Approx)
Mass of projectile	1.6 kgs (Approx)
Propellant (ACM)	0.36 kg (Approx)
Explosive filling in primer (cap) (Composition VH 2 & Zirconium)	0.14 gms (Approx)
Explosive filling in Igniter (Composition Z47B & NC 110)	15.0 gms
Explosive filling in Projectile	0.5 kg (Approx)
Explosive filling in tracer	1.4 gms (Approx)
Explosive filling in fuze	20.2 gms
Net explosive content	896.746 gms

Performance Characteristics

Muzzle velocity	305 m/s
Killing range against moving target	450 m
Killing range against static target Penetration	550 m
a) Homohard armour (normal attack)	400 mm
b) RCC target	1000 mm

Special Features

The weapon is of recoilless type and can be fired from the shoulder. In addition to its anti-tank role, anti-personnel role is also being achieved due to splinters of the shells.

Safety

The electric detonator remains off-centre during all stages of operation and this remains disconnected from the explosive train.

Reliability

Due to its sound design and careful manufacture, the ammunition is very reliable for use in combat field environment.

Shelf Life

The shelf life of the ammunition is 10 years

Packing

Two rounds are packed in twin containers made up of injection moulded tube of high density polyethylene. 4 such twin containers (total 8 rounds) are packed in one wooden crate.

Stowage Dimension

Packing box size	742 mm x 538 mm x 315 mm
Gross weight	45.5 kgs
Net weight	22.5 kgs
Volume	0.126 cu.m

Hazard Classification

Compatibility group	F
Hazard division	1.2
Fire fighting class	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.com>

84 MM ILLUMINATING FFV 545

General

This ammunition is fired from Gun 84 mm RCL Carl Gustaf from the shoulder. The cartridge combines some of the characteristics of Rocket and Artillery ammunition in its design. The ammunition is of Swedish design.



The illuminating round has been designed to meet the requirement for a very quick illumination of target areas, offering facilities for all types of direct fired weapons and guided anti-tank weapons to engage, Armoured fighting vehicles, support weapons etc. The illuminating round is also intended to facilitate for the sub-units of the battalion, supply of their own illumination of battle field, even continuous, when required. The ammunition is of the fixed type. The design of the ammunition parts and functioning are like Artillery components excepting that the rear end of the cartridge case is closed by a plastic blow out disc(base plate), which allows rearward escape of the propellant gas so as to make the weapon recoilless and the ignition of the propellant is by a side-located percussion cap and an igniter composition.

The cartridge case is made of light aluminium alloy drawn to specification BS-1470 Grade 6082 TF or IS 736 Grade 64430 WP. At the rear of the cartridge case, it is formed with a flange which is cut away over a length to take a guide while loading the round in the gun. At about 90 degrees from the cut away flange a hole with two diameters is provided on the body of the cartridge case to take the percussion cap. The shell body is made of light aluminium alloy to specification BS 1474 Grade 2014A or IS 736 Grade 64430 WP. The shell body accommodates the canister illuminating candle and the parachute assembly. The shell also accommodates the time combustion fuze FFV 64C, at the nose. The shell base is made up of light alloy with six equispaced circumferential holes to fix the base plate and body together with fixing screws. The shell is spin established. Propellant NGB 204 is a ballistite propellant. This ammunition is manufactured to Government of India, Ministry of Defence Specification No. CQA 3815 and drawing number F1301-055361 K.

Physical Characteristics

Total length of ammunition	450 mm
Total mass of ammunition	3.1 kgs
Mass of projectile	2.2 kgs
Propellant (ACM)	0.4 kg

Mass of Illuminating composition	0.5 kg
Explosive filling in primer (cap) (Composition VH 2 & Zirconium)	0.13 gm
Explosive filling in Igniter (Composition Z47B & NC 110)	15.0 gms
Explosive filling in fuze	17.68 gms
Net explosive content	932.81 gms

Performance Characteristics

Muzzle velocity	260 m/s
Range of burst	300 to 2100 m
Height of burst	200 m (approx)
Illuminated area, diameter	400- 500 m
Rate of descent	5 m/s (approx)
Candle power	6,50,000 candela
Burning time	30 ± 5 sec

Special Features

The weapon is of recoilless type and can be fired from the shoulder. The ammunition can be effectively used at any range between 300 m to 2100 m by elevating the gun to 20 degrees or 25 degrees.

Safety

The fuze is provided with a rubber hood and a safety pin. The rubber is for protection against atmospheric condition during storage and transport. Before firing, both the rubber hood and the safety pin is removed and the fuze is set.

Reliability

Due to its sound design and careful manufacture, the ammunition is very reliable for use in combat field environment.

Shelf Life

The shelf life of the ammunition is 10 years

Packing

Two rounds are packed in twin containers made up of injection moulded tube of high density polyethylene. Three such twin containers (total 6 rounds) are packed in one wooden crate.

Stowage Dimension

Packing box size	660 mm x 463 mm x 356 mm
Gross weight	40.0 kgs
Net weight	24.6 kgs
Volume	0.108 cu.m



EQUIPMENT CATALOGUE

Hazard Classification

Compatibility group	G
Hazard division	1.2
Fire fighting class	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.com>



84 MM TPT 65

General

This ammunition is fired from Gun 84 mm RCL Carl Gustaf M2 from the shoulder. This ammunition is ballistically identical to the 84 mm HEAT round. Except for a tracer, there is no other explosive in the shell. This round is provided in order to save on the costlier HEAT rounds. The soldier is trained on this round and all the practice firings are mostly done by using the TPT rounds. This ammunition is of Swedish design.



This ammunition is of fixed type. The design of the ammunition parts and functioning are like Artillery components excepting that the rear of the cartridge case is closed by a plastic blow out disc (base plate) which allows rearward escape of the propellant gases and the ignition of the propellant is by a side-located percussion cap and an igniter composition. Cartridge case is made of light aluminium alloy drawn to specification BS 1470 grade 6082TF or IS 736 grade 64430WP. At the rear, it is formed with a flange which is cut away over a length to take a guide while loading the round in the gun. At about 90 degree from the cut away flange, a hole with two diameters is provided on the body of the cartridge case to take the percussion cap. The shell body is made of light aluminium alloy to specification SISAI4250-10 or DEF30A (a) : LM 24M Propellant NGB 204 is a ballistite propellant. This ammunition is manufactured to Government of India, Ministry of Defence Specification No. CQA0311 and Drawing No.F1301-047740J.

Physical Characteristics

Total length of ammunition	535 mm
Total mass of ammunition	2.6 kg
Mass of projectile	1.8 kg
Propellant (ACM)	0.4 kg
Explosive filling in primer (cap)	0.13 gms (Composition VH 2 & Zirconium)
Explosive filling in Igniter	15.0 gms (Composition Z47B & NC 110)
Explosive filling in Tracer	1.4 gms
Net explosive content	416.53 gms

Performance Characteristics

Muzzle velocity : 305 m/s

Special Features

The weapon is of recoilless type and can be fired from the shoulder.

Safety

As no explosive filling is involved in the shell filling, the ammunition is safe during manufacture, transit and storage.

Reliability

Due to its sound design and careful manufacture, the ammunition is very reliable for its end use.

Shelf Life

The shelf life of the ammunition is 10 years.

Packing

Two rounds are packed in twin containers made up of injection moulded tube of high density polyethylene, 4 such twin containers (total 8 rounds) are packed in one wooden crate.

Stowage Dimension

Packing box size	742 mm x 538 mm x 315 mm
Gross weight	45.5 kgs
Net weight	22.2 kgs Approx
Volume	0.126 cu.m

Hazard Classification

Compatibility group	C
Hazard division	1.3
Fire fighting class	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-248 9027 / 248 2103 / 248 5077-80

E: ofbtrade@dataone.in

F: +91-33-248 1748/210 8235

w: <http://www.ofbindia.com>

CARTRIDGE AA 40 MM L-70 PFFC

General Description

The 40/70 PFFC IM 212, HE Pre Formed Fragmentation with Tungsten Cubes, has been designed for firing in the 40 mm L70 BOFORS and BREDA 40 L70 guns. It is meant for use against aircraft and sea skimmer missile threats the 40/70 PFFC IM 212 (Pre Formed Fragmented Cubes) fitted with Proximity Fuze Fb 40.



Characteristics

1. Calibre	0.29 gms
2. Length, complete round	45.0%
3. Weight, complete round	55.0%
4. Weight, shell & fuze	2.3%
5. Weight of explosive	2.0%
6. Type of explosive	
7. Muzzle velocity at +21°C	
8. Max. chamber pressure at +21°C	
9. Applicable Fuze	
10. Primer	
11. Cartridge Case	
12. Type	
13. Weight of Fuze	
14. Propellant	
15. Self destruction	
16. Pre formed Fragments	
Number	525 approx.
Shape	Cube
Single weight	0.40 g
17. Function	
Percussion	After 500 m approx.
Proximity mode function	After 800 m approx.



EQUIPMENT CATALOGUE

Mechanical Safety range 50 m min.

The ammunition is able to operate in severe climatic conditions

Operating temperature -20°C to 50°C

Storage temperature -40°C to 60°C

The round has a minimum shelf life of Ten (10) years provided that it is stored in its original container and it is stored under the following ambient conditions:

Temperature Between $+10^{\circ}\text{C}$ to 30°C

Humidity Between 25% and 60%

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



CARTRIDGE 30 MM ADEN GUN HE MK 2Z

General

This ammunition is fired from 30 mm Aden Gun mounted on HF24, Hunter and Mystere aircraft. This ammunition consists of a projectile and a cartridge case, which are issued, stored and loaded together as one complete round, that is as fixed ammunition. 30-mm ammunition is supplied belted in lengths of 30 rounds, made up of L.H feed or R.H feed.



The cartridge case made from solid drawn brass, and in the centre of its base is a recess, which houses an electric cap. The recess is provided with a fire hole. Around the base is an extractor groove, and adjacent to the groove is a shoulder by which the cartridge is positioned in the chamber of the gun. The projectile consists of a steel shell to which is screwed a percussion fuze No. 933. This ammunition is manufactured to Government of India, Ministry of Defence Specification No. AIR 1385G and drawing No. ARM 1107 B1.

Physical Characteristics

Total length of ammunition	7.874 inch mm
Mass of complete round	432.0 gms 10 gms
Mass of explosive in projectile	52.5 gms
Mass of propellant (NRN No. 141/A.H)	46.0 gms
Mass of filled fuze	29.5 gms

Performance Characteristics

Velocity at 27.5 m from muzzle	780.8 m/s \pm 12.2 m/s
Accuracy at 457.2 m	609.6 mm MFM
Rate of fire	1200-1400 rds/min

Safety

The ammunition is absolutely safe during manufacturing, storage and transportation as the fuze is provided with adequate safety arrangements to eliminate the possibility of premature initiation. Care should be taken that the electric cap is not struck as a blow is liable to cause the cap to function.

Reliability

Due to its sound design and careful manufacture, it is very reliable for use in combat field environment. It is most effective and reliable in its role as air to air combat, air to ground support, against radar installations, fuel dumps, soft skin vehicles etc.

Shelf Life

Shelf life of this ammunition is 10 years

Packing

29 rounds are fitted in one belt + 1 round in loose condition. The belt along with the loose round is packed in one steel box H60.

Stowage Dimension

Size of the box	355 mm x 241 mm x 315 mm
Gross weight	27.2 kg
Net weight	12.96 kg
Volume	0.026 cu m

Hazard Classification

Cartridge is classified in	
Compatibility group	C
Hazard division	1.2
Fire fighting classification	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

CARTRIDGE 30 MM ADEN GUN PRACTICE MK2Z

General

This ammunition is fired from 30mm Aden Gun mounted on HF24, Hunter and Mystere aircraft. This is most modern and optimum Air Ammunition calibre for training/practice. This ammunition consists of a projectile and a cartridge case. The projectile consists of a cylindrical steel body into which is screwed an aluminium alloy firing plug. The firing plug is dumb-bell shaped, one end having a blunt nose, a curved taper and a thread to screw into the body. The Cartg case contains a propellant charge of approx. 46 gms of nitrocellulose and potassium sulphate boosted by primer instead of only a propellant charge of approximately 30 gms of Nitro-cellulose & Potassium sulphate. The primer is a bag of silk gauze containing approximately 10 gms of N.P.P 160 Powder and is located over the fire hole in the case. The ammunition is manufactured to Government of India, Ministry of Defence. Specification No. AIR1383H and Drawing No. ARM 1106B1



Physical Characteristics

Total length of ammunition	7.874 inch
Mass of complete round	432 gms ± 20 gms
Mass of explosive filling	45 gms approx

Performance Characteristics

Velocity at 27.5 m from muzzle	780.8 m/s ± 12.2 m/s
Accuracy at 457.2 m	609.6 mm of MFM
Rate of fire	1200-1400 rds/min

Safety

The ammunition is absolutely safe during manufacturing, storage and transportation in all conditions. Care should be taken in that the electric cap is not struck, as a blow is liable to cause the cap to function.

Reliability

Due to its sound design and careful manufacture, it is very reliable for use in combat field environment. It is most effective and reliable in its role in air to air combat, air to ground support, against radar installations, fuel dumps, soft skin vehicles etc.

Shelf Life

Shelf life of this ammunition is 10 years.

Packing

29 rounds are fitted in one belt + 1 round in loose condition. The belt along with the loose round is packed in one steel box H60.

Stowage Dimension

Size of the box	355 mm x 241 mm x 315 mm
Gross weight	27.2 kg
Net weight	12.96 kg
Volume	0.026 cu m

Hazard Classification

Cartridge is classified in	
Compatibility group	C
Hazard division	1.2
Fire fighting classification	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

30 MM BMP II AMMUNITION HE/T

General

30 MM Ammunition is fired from 30 mm automatic Gun 2A42 mounted on infantry combat vehicle BMP II as the main armament. The gun has double belt feed system, one belt with armour piercing tracer round and the other with both High Explosive Incendiary and HE Tracer rounds generally in ratio of 4:1. The gun is designed for single shot firing as well as automatic firing at slow and rapid rates.



30 MM HE/T ammunition is a fixed type of ammunition and is intended for use against man power and non armoured ground and aerial targets.

Physical Characteristics

Total length of ammunition (High)	291.84 mm
Total length of ammunition (Low)	288.45 mm
Mass of Complete Round	0.826 kg (Approx)
Mass of projectile	0.385 kg \pm 0.006 Kg
Mass of propellant	0.120 kg (Approx)
Mass of bursting charge	0.0116 kg

Performance Characteristics

Muzzle Velocity	960 m/s \pm 10 m/s
Mean pressure of propellant	3600 Kg/cm ²
Self destruction time of fuze	9.0 to 14.0 sec
Maximum Range	
(a) At ground target	4000 m
(b) At aerial target/altitude	2000 m
(c) Slant range	2500 m
(d) Tracer burning time	9.0 sec

Special Features

HE/T projectiles are equipped with fuze A670M designed to explode on impact with the target and it can cause self destruction of the shell if it misses the target.

Quality

The raw material used for components are tested by independent Quality Assurance

Wing. Major components are test-fired and only passed proof components are taken into final assembly of ammunition. The final round is dynamically proved for i) Velocity ii) Pressure iii) Safety & functioning at low rate of fire and high rate of fire and (iv) Failure free functioning, during time & visibility of tracer.

Safety

Adequate mechanical safety arrangements are provided for safety during handling and transportation.

Reliability

Due to its sound design and careful manufacture, the ammunition is very reliable for use in combat field environment.

Shelf Life

The shelf life of this ammunition is 7 years

Packing

30 rounds are packed in one steel box H-60, a hermetically sealed metallic container.

Stowage Dimension

Packing box size	355 mm x 241 mm x 315 mm
Estimated weight of box	35.12 kgs/box
Net weight of box	24.9 kgs/box
Volume	0.027 cu metre

Hazard Classification

This ammunition is classified in

Compatibility group	F
Hazard Division	1.2
Fire fighting classification	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

30 MM BMP II AMMUNITION AP/T

General

30 MM Ammunition is fired from 30 mm automatic Gun 2A42 mounted on infantry combat vehicle BMP II as the main armament. The gun has double belt feed system, one belt with armour piercing tracer round and the other with both High Explosive Incendiary and HE Tracer rounds generally in ratio of 4:1. The gun is designed for single shot firing as well as automatic



firing at slow and rapid rates.

30 MM AP/T ammunition is a fixed type of ammunition and is intended for use against light armoured targets and weapon emplacements.

Physical Characteristics

Total length of ammunition (High)	292.84 mm
Total length of ammunition (Low)	289.39 mm
Mass of Complete Round	0.853 kg Approx.
Mass of Projectile	0.40 kg 0.006 kg
Mass of propellant	0.128 kg Approx.

Performance Characteristics

Muzzle Velocity	970 m/s \pm 10 m/s
Mean pressure of propellant	3600 Kg/cm ²
Maximum Range	
(a) At ground target	4000 m
(b) At aerial target/altitude	2000 m
(c) Slant range	2500 m
(d) Tracer burning time	3.5 sec

Special Features

Armour piercing projectile provides armour piercing effect behind the armour due to fragmentation of armoured target as well as the steel body of shell. The tracer gives visibility of its path upto a range of 2500 m.

Quality

The raw material used for components are tested by independent Quality Assurance Wing. Major components are test fired and only passed proof components are taken into final assembly of ammunition. The final round is dynamically proved for i) Velocity

ii) Pressure iii) Safety & functioning at low rate of fire and high rate of fire and iv) Failure free functioning, burning time & visibility of tracer.

Safety

Adequate mechanical safety arrangements are provided for safety during handling and transportation.

Reliability

Due to its sound design and careful manufacture, the ammunition is very reliable for use in combat field environment.

Shelf Life

The shelf life of this ammunition is 7 years.

Packing

30 rounds are packed in one steel box H-60, a hermetically sealed metallic container.

Stowage Dimension

Packing box size	355 mm x 241 mm x 315 mm
Estimated weight of box	36.0 kgs/box
Net weight of box	25.59 kgs/box
Volume	0.027 cu m

Hazard Classification

This ammunition is classified in

Compatibility group	E
Hazard Division	1.2
Fire fighting group	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

30 MM BMP II AMMUNITION HE/I

General

30 MM Ammunition is fired from 30 mm automatic Gun 2A42 mounted on infantry combat vehicle BMP II as the main armament. The gun had double belt feed system, one belt with armour piercing tracer round and the other with both High Explosive Incendiary and HE Tracer rounds generally in ratio of 4:1.

30 mm HE/I ammunition is a fixed type of ammunition and is intended for use against main power and non armoured ground and aerial targets 30 mm Gun is designed for single shot firing as well as automatic firing at rapid & slow rates.



Physical Characteristics

Total length of ammunition (High)	292.84 mm
Total Length of ammunition (Low)	289.45 mm
Mass of Complete Round	0.833 kg
Mass of projectile	0.389 kg \pm 0.006 kg
Mass of propellant	0.122 kg
Mass of bursting charge	0.0485 kg \pm 0.001 kg

Performance Characteristics

Muzzle Velocity	960 m/s \pm 10 m/s
Mean pressure of propellant	3600 Kg/cm ²
Self destruction time of fuze	9.0 to 14.0 Sec

Maximum Range

a) At ground target	4000 m
b) At aerial target	2000 m
c) Slant range	2500 m

Special Features

HE/I projectiles are equipped with fuze A670M designed to explode on impact with the target and it can cause self destruction of the shell if it misses the target.

Quality

The raw material used for components are tested by independent Quality Assurance Wing. Major components are test-fired and only passed proof components are taken into final assembly of ammunition. The final round is dynamically proved for i) MV ii.)

Pressure iii) Safety & functioning at low rate of fire and high rate of fire.

Safety

Adequate mechanical safety arrangements are provided for safety during handling and transportation.

Reliability

Due to its sound design and careful manufacture, the ammunition is very reliable for use in combat field environment.

Shelf Life

The shelf life of this ammunition is 7 years.

Packing

30 rounds are packed in one steel box H-60, a hermetically sealed metallic container.

Stowage Dimension

Packing box size	355 mm x 241 mm x 315 mm
Estimated weight of box	35.43 kgs/box
Net weight	24.99 kgs/box
Volume	0.027 cu m

Hazard Classification

This ammunition is classified in

Compatibility group	F
Hazard Division	1.2
Fire fighting Group	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

CARTRIDGE RIM FIRE .22" BALL

General

The cartridges are of rimmed type. The complete cartridge consists of a cartridge case with rimfire composition, propellant charge and bullet. The rimfire makes thus a cartridge without a percussion cap. It is rimmed out to hold the initiatory composition. The striker of the rimfire rifle is placed eccentric to the axis of the barrel, so that when the rifle is fired, it pinches the rim and thus fires the cartridge. The bullet is made of lead antimony alloy and is unjacketed. The bullet is round nosed and formed with three circumferential grooves.



Physical Characteristics

Total length of Ammunition	25 mm (approx.)
Total mass	3.54 g
Mass of bullet	2.60 g (approx.)
Mass of Initiatory composition	26 to 29 mg

Performance Characteristics

Velocity at 9 m	305 ± 23 m/s
Mean Figure of Merit at 23 m	95% within 19 mm circle dia.

Quality

Various strict quality checks are adopted during manufacture. All the components are proved and inspected separately in empty stages before they are taken for filling/Assembly. Functional proof is carried out in association with Services Quality Assurance Organisation.

Shelf Life

The shelf life of the Ammunition is 18 years

Packing

100 cartridges are packed in one Carton ASA No. 48 MK -1 and 4 such Cartons in one polythene bag and 11 polythene bags are packed in one Case Wood Packing 6A.

Stowage Dimension

Package dimensions	398 mm X 233.5 mm X 211.5 mm
Gross Weight	20 Kgs (approx.)

HAZARD CLASSIFICATION

Compatibility group	S
Hazard Division	1.4
Fire fighting classification	4

0.22" RIM Fire Ammunition

Type of Ammunition	Velocity At 9 Metres	Accuracy	
		Mean figure of merit at 25 yds (23 m)	Distance between two distant shots in a target of 5 rounds at 50 Metres
22 " RF Short	925 ± 50 ft. /Sec (282 ± 15.2 m/Sec)	Min. 95% with in ¾" dia (19 mm) circle	
.22 " RF Long	1000 ± 75 ft. /Sec (305 ± 23 m/Sec)	Min. 95% with in ¾" dia (19 mm) circle	
.22 " RF Tracer	1000 ± 75 ft. /Sec (305 ± 23 m/Sec)	Min. 95% with in 1 ½" dia (38 mm) Circle	
.22 " RF for Precision Shooting	1050 ± 16.4 ft. /Sec (320 ± 5 m/Sec)	-	Min 1" (2.5 cm)

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 2103 / 2248 5077-80

E: ofbtrade@dataone.in

F: +91-33-2248 1748/2210 8235

w: <http://www.ofb.gov.com>

CARTG. SA .32" REVOLVER

CARTG. SA .32" PISTOL



	Velocity at 30 ft.	Accuracy	Pressure	
		at 30 Yds	at 40 Yds	
.32" Long revolver	775 ± 24 ft./Sec (236 ± 7.6 m/Sec)	MFM 2.1" (5.33 cm)	MFM 2.8" (7.11 cm)	4.724 kg/ mm ² or (46.4 MPa) (MEAN MAX.)
.32" short revolver	700 ± 25 ft./Sec (213 ± 7.6 m/Sec)	MFM 2.1" (5.33 cm)	MFM 2.8" (7.11 cm)	
.32" Pistol	950 ± 50 ft./Sec (290 ± 15.2 m/Sec)	MFM 2.1" (5.33 cm)	MFM 2.8" (7.11 cm)	

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 2103 / 2248 5077-80

E: ofbtrade@dataone.in

F: +91-33-2248 1748/2210 8235

w: <http://www.ofb.gov.com>

CARTG. SA .315"/ 8 MM BALL

CARTG. SA .30" - 06



Cartridge	Velocity	Accuracy	Pressure
0.315"/8 mm	2000 ± 50 ft/sec (610 ± 15.2 m/ Sec) at 90 ft. (27.4 m)	3.5" (9 cm) Max at 200 Yards (183 m)	Mean not to exceed 18.0 TSI single not to exceed 19.0 TSI
.30"- 06	850 ± 10 m/ sec at 27.4 m	8 cm Max at 185 m	278 Mpa

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 2103 / 2248 5077-80

E: ofbtrade@dataone.in

F: +91-33-2248 1748/2210 8235

w: <http://www.ofb.gov.com>

CARTRIDGE SA 12 BORE 70 MM PLASTIC ASTRAM

General

This cartridge can be fired from all types of 12 Bore guns having 70 mm or more chamber length. This is a superior cartridge compared to other types of 12 bore cartridges and is used for shooting sports. Smokeless propellant powder and non-corrosive caps are used in the cartridge. Hardened lead shots give a good impact



on the target. The body is made of special grade plastic tubes to withstand higher pressures and achieve higher velocity compared to paper cartridges. The use of plastic power piston with pouch provides better gas sealing and higher accuracy, i.e. better pattern of shots on target.

Physical Characteristics

Case	Made from bi-axially oriented HDPE plastic tubes
Primer	Mercury fulminate based compo (23 to 29 mg)
Projectile	Lead-Antimony alloy shots (Chilled)
Propellant	Double base shotgun propellant (1.7 to 2.1 g)
Propelling system	LDPE plastic power piston with pouch
Cartg. Length	58 mm
Empty Case Length	70 mm
Weight of Lead shots	32 g
Cartg. Weight	48 g Approx
Shot size	From biggest no. 1 (3.63 mm) to smallest no. 9 (2.02 mm)
No. of Shots	113 in size 1 to 652 in size 9
Type of Closure	Star Crimping

Ballistic Characteristics

Parameter	Measure
Pressure	Max 54.0 Mpa at 1" & Max 29.4 Mpa at 6"
Velocity at 9 mtr from muzzle	350 +/- 15 m/s
Accuracy at distance of 27 m	Min 56% of pellets in a circle of dia. 760 mm on target, Min 90% when fired from choke barrel.

Identification Marks on Cartridge

A) Brass head:

Mark	Meaning
KF	Manufacturing Unit - Ammunition Factory Khadki.
12	12 Bore Cartg

B) Case: Shot No, Shot weight & Brand name are printed on the cartg. case.

Quality

All components like cases, propellant and percussion caps undergo strict quality checks and are proof tested before use in the manufacture of the cartridges. The manufacture of the cartridges in automatic loading machines in controlled atmosphere ensures uniform and highly consistent quality in the cartridges. Finished cartridges are subjected to further inspection and proof testing to ensure quality of performance.

Packing

25 cartridges are packed in multicoloured paper carton. Then 5 such Cartons are packed in polythene bag & heat sealed. Two such bags are packed in one corrugated paper box. Thus each corrugated box contains 250 cartgs.

Dimensions of one corrugated box : 330 x 240 x 130 mm

Gross weight of one packed corrugated box : 13.0 Kg approx

Shelf Life

If properly stored in packed condition, expected shelf life is around 5 years. Ammunition should be kept in a cool and dry place, and protected against direct sunlight and rain.

Hazard Classification

Explosive Classification : 1.4S

Fire Fighting Classification : Clause 1

Precaution for Use/ Firing

Weapon should be in good condition. Only authorised & trained personnel should fire the cartridges. Barrel should be cleaned every time after firing. Periodical checks of weapon with gauges are essential to ensure that its CHS, SP and FPI are within the limits.

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



CARTRIDGE SA 12 BORE 70 MM PLASTIC MAGNA

General

This cartridge can be fired from all types of 12 Bore guns having 70 mm or more chamber length. This is generally used for scaring away of animals, protection of crops and hunting. Smokeless propellant powder and non-corrosive caps are used in the cartridge. Use of hardened lead shots gives a good impact on the target.



The body is made of special grade plastic tubes to withstand higher pressures and achieve higher velocity compared to paper cartridges.

Physical Characteristics

Case	Made from bi-axially oriented HDPE plastic tubes
Primer	Mercury fulminate based compo (23 to 29 mg)
Projectile	Lead-Antimony alloy shots (Chilled)
Propellant	Double base shotgun propellant (1.7 to 2.1 g)
Propelling system	LDPE plastic power piston without pouch
Cartg. Length	65 mm
Empty Case Length	68 mm
Weight of Lead shots	34 g
Cartg. Weight	50 g Approx
Shot size	From biggest no. BB (4.08 mm) to smallest no. 9 (2.02 mm)
No. of Shots	84 in size BB to 695 in size 9
Type of Closure	Turn over

Ballistic Characteristics

Parameter	Measure
Pressure	Max 54.0 Mpa at 1" & Max 29.4 Mpa at 6"
Velocity at 9 mtr from muzzle	350 +/- 15 m/s
Accuracy at distance of 27 m	Min 56% of pellets in a circle of dia. 760 mm on target

Identification Marks on Cartridge:

A) Brass head:

Mark	Meaning
KF	Manufacturing Unit - Ammunition Factory Khadki.
12	12 Bore Cartg

B) Case: Shot No, Shot weight & Brand name are printed on the cartg. case.

Quality

All components like cases, propellant and percussion caps undergo strict quality checks and are proof tested before use in the manufacture of the cartridges. The manufacture of the cartridges in automatic loading machines in controlled atmosphere ensures uniform and highly consistent quality in the cartridges. Finished cartridges are subjected to further inspection and proof testing to ensure quality of performance.

Packing

25 cartridges are packed in multicoloured paper carton. Then 4 such Cartons are packed in polythene bag & heat sealed. Two such bags are packed in one corrugated paper box. Thus each corrugated box contains 200 cartgs.

Dimensions of one corrugated box : 330 x 240 x 130 mm

Gross weight of one packed corrugated box : 10.5 Kg approx

Shelf Life

If properly stored in packed condition, expected shelf life is around 5 years. Ammunition should be kept in a cool and dry place, and protected against direct sunlight and rain.

Hazard Classification

Explosive Classification : 1.4S

Fire Fighting Classification : Clause 1

Precaution for Use/ Firing

Weapon should be in good condition. Only authorised & trained personnel should fire the cartridges. Barrel should be cleaned every time after firing. Periodical checks of weapon with gauges are essential to ensure that its CHS, SP and FPI are within the limits.

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



CARTRIDGE SA 12 BORE 65 MM PLASTIC DELUXE

General

This cartridge can be fired from all types of 12 Bore guns having 65 mm or more chamber length. This is generally used for scaring away of animals, protection of crops and hunting. Smokeless propellant powder and non-corrosive caps are used in the cartridge. Use of hardened lead shots gives a good impact on the target. The body is made of special grade plastic tubes to withstand higher pressures and achieve higher velocity compared to paper cartridges. This cartridge is similar to the plastic 'special' cartridge but has a bigger brass head on the body.



Physical Characteristics

Case	Made from bi-axially oriented HDPE plastic tubes
Primer	Mercury fulminate based compo (23 to 29 mg)
Projectile	Lead-Antimony alloy shots (Hardness 13 VPN, Type-Chilled)
Propellant	Double base shotgun propellant (1.7 to 2.1 g)
Propelling system	LDPE plastic power piston without pouch
Cartg. Length	60 mm
Empty Case Length	65 mm
Weight of Lead shots	30.1 g
Cartg. Weight	45 g Approx
Shot size	From biggest no. BB (4.08 mm) to smallest no. 9 (2.02 mm)
No. of Shots	74 in size BB to 616 in size 9
Type of Closure	Turn over

Ballistic Characteristics

Parameter	Measure
Pressure	Max 54.0 Mpa at 1" & Max 29.4 Mpa at 6"
Velocity at 9 mtr from muzzle	320 +/- 15 m/s
Accuracy at distance of 27 m	Min 56% of pellets in a circle of dia. 760 mm on target

Identification Marks On Cartridge

A) Brass head:

Mark	Meaning
KF	Manufacturing Unit - Ammunition Factory Khadki.
12	12 Bore Cartg

B) Case: Shot No, Shot weight & Brand name are printed on the cartg. case.

Quality

All components like cases, propellant and percussion caps undergo strict quality checks and are proof tested before use in the manufacture of the cartridges. The manufacture of the cartridges in automatic loading machines in controlled atmosphere ensures uniform and highly consistent quality in the cartridges. Finished cartridges are subjected to further inspection and proof testing to ensure quality of performance.

Packing

25 cartridges are packed in multicoloured paper carton. Then 5 such Cartons are packed in polythene bag & heat sealed. Two such bags are packed in one corrugated paper box. Thus each corrugated box contains 250 cartgs.

Dimensions of one corrugated box : 330x240x130 mm

Gross weight of one packed corrugated box : 12.5 Kg approx

Shelf Life

If properly stored in packed condition, expected shelf life is around 5 years. Ammunition should be kept in a cool and dry place, and protected against direct sunlight and rain.

Hazard Classification

Explosive Classification : 1.4S

Fire Fighting Classification : Clause 1

Precaution for Use/ Firing

Weapon should be in good condition. Only authorised & trained personnel should fire the cartridges. Barrel should be cleaned every time after firing. Periodical checks of weapon with gauges are essential to ensure that its CHS, SP and FPI are within the limits.

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

CARTRIDGE SA 9 MM BALL

Role

These cartridges are of rimless type and are used with 9 mm pistol or 9 mm Machine Carbine Sten. This cartridge consists of cartridge case, percussion cap, propellant charge and a bullet. This case is of solid drawn brass. At the base of case, a cap chamber with an anvil and two fire holes are formed. A groove is provided on the case for easy extraction of the fired case. The cap is filled with VH2/E1 composition. The cap is secured in the cap chamber and annulus of cap is lacquered to seal the cap and the cap chamber. The bullet is round nosed and consists of Lead-antimony core in an envelope of gilding metal. The cartridge case is tightly coned on to it.



Physical Characteristics

i)	Total length of Ammunition	H-29.69 mm L-28.91 mm
ii)	Total mass of Ammunition	11.94g ± 0.65 g
iii)	Maximum diameter	9.96 mm
iv)	Explosive filling in case	0.450 g (approx) propellant SPA-2 or propellant NC-688
v)	Cap Composition	23mg VH2 compo E1 compo

Performance Characteristics

i)	Mean velocity at 18 m. from muzzle	397 ± 15m/s
ii)	Accuracy	75.2 mm Mean Figure of Merit at 45 m
iii)	Pressure	Mean 201 Mpa Individual 215 Mpa No single round should exceed 216 Mpa.

Special Features

This Ammunition can be used with Pistol and Machine carbine. Its main role is defence rather than attack.

Quality

Various strict quality checks are adopted during manufacture. All the components are proved/inspected separately in the empty stage before they are taken for filling/assembly. Functional proof is carried out in association with Services Quality Assurance Organization.

Safety

The cartridges are absolutely safe as required for service role since the caps are tested for both sensitivity and insensitivity before assembly.

Reliability

The Ammunition lot is tested as per international norms to give adequate reliability.

Shelf Life

The shelf life of Ammunition is 7 years.

Packing

35 cartgs. are packed in carton 23 A and such 32 cartons are packed in a H2A box (steel)

Overall dimensions Box H2A

Length (approx.)	311 mm
Width (approx.)	156 mm
Height (approx.)	194 mm and such four boxes are packed in steel carrier 6A/L.

Stowage Dimensions

Package Dimensions	667 mm X 327 mm X 205 mm
Gross weight	39 kgs (approx)

Hazard Classification

Compatibility group	S
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



CARTRIDGE SA 7.62 MM BALL M-80

Role

The cartridge SA 7.62 mm Ball M-80 is used in antipersonnel role by infantry and is fired from :

- a) Semi Automatic Rifle
- b) Light machine gun
- c) Medium machine gun



Physical Characteristics

(a) CARTRIDGE

Calibre	7.62x51 mm
Mass	25.40 gm
Length	71.12 mm

(b) CASE

Type	Rimless, Brass 70:30, Bottle Necked, Boxer
Mass	12.3 gm
Length	51 mm

(c) BULLET

Type	Guiding Metal envelope FMJ, Steel insert & lead core
Mass	9.65 gm
Length	29.46 mm

(d) PROPELLANT

Type	Ball Powder
Mass	3.0 gm

(e) PRIMER

Type	Boxer
Mass of Compo	0.042 gm

Performance Characteristics

- (a) Pressure Average 348 Mpa (Max)
- (b) Mean Velocity from 558 mm Barrel at 25 m from muzzle 817 ± 9 m/s.
- (c) Consistency (Mean Figure of Merit at 550 m) 19 cm or less
- (d) Extreme temperature performance -53 to +72 deg C

Shelf Life

The shelf life of ammunition is 18 years.

Packing

Type of Packing	Qty/Box	Qty/Carrier	Weight of carrier Pkd. Ammn
Bandolier Pkd	400 Rds.	1600 Rds.	62 Kgs
CTN Packed	600 Rds.	2400 Rds.	80 Kgs
Belted	235 Rds.	940 Rds.	41 Kgs

This carrier provides protection during transportation and storage.

Stowage Dimension

For CTN & BDR H2A Box size- 311X156X194 mm

For CTN & BDR Carrier (6A/L) size- 667X327X205 mm

For Belted Ammn Box H5A size- 255X182X90 mm

For Belted Ammn Carrier (7A/L) size- 428X300X206 mm

Hazard Classification

Compatibility group	5
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

W: <http://www.ofb.gov.com>



CARTRIDGE SA 7.62 MM BLANK L.A.

General

The 7.62 mm blank cartridge is used for gunnery training purpose. It is also used for simulated fire, gun salutes, signaling etc.

This cartridge is fired from a Light Machine Gun (LMG) or rifle for training, signaling gun salutes etc.



Physical Characteristics

Length	68.07 mm
Mass of Ammn.	13.63 g.
Diameter	10.16 mm
Powellant	Powder SPA II or NC 688 (0.844 g.)

Cap Composition

F - 1 Mixture	32 mg.
Net explosive content	0.876 g.

Special Features

- 1) The cartridge is very useful for the purpose of gunnery Training.
- 2) Without any injury to the troops under training, it gives live simulation.
- 3) Comparatively it can be produced at less cost than Ball Ammunition.

Quality

Strict Quality measures are adopted during various stages of production. Mouth of filled cartridge case is crimped and sealed with a special type of Ammunition Protective Composition to prevent ingress of moisture. Empty caps are proved/inspected separately before being taken for loading and assembly. After loading, functional proof is carried out. The cartridges are filled and assembled in lots between 50,000 Nos. and 1,00,000 Nos.

Safety

The cartridges are absolutely safe to handle and so designed that they do not function even during rough manual handling.

Reliability

Even though these are meant for training purposes, the reliability is at par with Ball cartridge in functioning.

Shelf Life

Shelf life of filled cartridge is 10 years.

Packing

The packing consists of inner and outer packages. The inner package is carton 8A (50 cartgs. are packed in one carton). 30 cartons 8A are packed in 6 polythene bags. These polythene bags are packed in case wood package 7A (CWP 7A).

The wooden box (i.e.CWP 7A) holds total 1500 cartridges.

Stowage Dimension

Package Dimensions	460 mm X 268 mm X 319 mm
Gross weight	29.00 kg. (approx)

Hazard Classification

Compatibility group	S
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

CARTRIDGE SA 7.62 MM TRACER M-62

Role

The cartridge SA 7.62 mm Tracer M-62 is used for location of target/trajectory during night, incendiary effect and signaling purposes, and to be fired from :

- a) Semi Automatic Rifle
- b) Light machine gun
- c) Medium machine gun



Physical Characteristics

(a) CARTRIDGE

Calibre	7.62 x 51 mm
Mass	25.08 gm (Max.)
Length	71.12 mm

(b) CASE

Type	Rimless, Brass 70:30, Bottle Necked, Boxer
Mass	12.3 gm
Length	51 mm

(c) BULLET

Type	Guiding Metal envelope FMJ, Pyro Composition & lead core
Mass	9.14 gm (Max.)
Length	34.29 mm (Max.)

(d) PROPELLANT

Type	Ball Powder
Mass	2.8 gm

(e) PRIMER

Type	Boxer
Mass of Compo	0.047 gm (Max.)

Performance Characteristics

(a) Pressure Average	348 Mpa (Max)
(b) Mean Velocity from 558 mm Barrel at 25 m from muzzle	817 + 9 m/s.

- (c) Consistency (Mean Figure of Merit at 550 m) 38 cm or less
- (d) Tracing Characteristics Up to 13.7 m-dimzone 91.4 m-777.2 m bright crimson red trace
- (e) Extreme temperature performance -52 to +72 deg C

Shelf Life

The shelf life of ammunition is 10 years.

Packing

Type of Packing	Qty/Box	Qty/Carrier	Weight of carrier Pkd. Ammn
CTN Packed	600 Rds.	2400 Rds.	80 Kgs
Seq Belt (Four Ball + One Tracer)	235 Rds.	940 Rds.	41 Kgs

This carrier provides protection during transportation and storage.

Stowage Dimension

For CTN & BDR H2A Box size- 311X156X194 mm

For CTN & BDR Carrier (6A/L) size- 667X327X205 mm

For Belted Ammn Box H5A size- 255X182X90 mm

For Belted Ammn Carrier (7A/L) size- 428X300X206 mm

Hazard Classification

Compatibility group	S
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

7.62 MM A-7 MK-II BALL AMMN



Cartridge 7.62 mm A-7 MK-II Ball Ammn is used in antipersonnel role by infantry and is fired from Semi-automatic AK 47 Rifle

Physical Characteristics

- | | |
|----------------|------------------------------------------------------|
| (a) CARTRIDGE | |
| Calibre | 7.62mm |
| Mass | 18.75 g average |
| Length | 56mm max |
| (b) CASE | |
| Type | Rimless, Brass 70:30, Bottle Necked, Boxer |
| Mass | 8.00 g approx |
| Length | 38.7 mm max |
| (c) BULLET | |
| Type | Gilding Metal envelope FMJ, Steel insert & lead core |
| Mass | 7.85 g average |
| Length | 27.0 mm max |
| (d) PROPELLANT | |
| Type | Ball Powder |
| Mass | 1.420 g (as assessed) |
| (e) PRIMER | |
| Type | Boxer |
| Mass of Compo | 47 mg max |

Performance Characteristics

- | | |
|----------------------------------------------------------|------------------|
| (a) Pressure Average | 335 Mpa (Max) |
| (b) Mean Velocity from 558 mm Barrel at 25 m from muzzle | 610 m/s |
| (c) Consistency (Mean Figure of Merit at 300 m) | 30 cm or less |
| (d) Extreme temperature performance | -40 to +52 deg C |

Shelf Life

The shelf life of Ammunition is 18 years

Packing

20 Cartgs are packed in one Carton and 36 such cartons in one H2A Box, hermetically sealed. One carrier size (6 A/L) contains 4 H2A boxes. Box H2A size - 311 x 156 x 194 mm and Carrier 6 A/L size - 667 x 327 x 205 mm

Hazard Classification

Compatibility group	S
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

INSAS 5.56 MM BALL AMMN



Cartridge (INSAS) 5.56mm Ball Ammn is used in antipersonnel role by infantry and is fired from;

- a) Semi-automatic INSAS Rifle
- b) INSAS LMG

Physical Characteristics

- | | |
|----------------|------------------------------------------------------|
| (a) CARTRIDGE | |
| Calibre | 5.56 x 45 mm |
| Mass | 12.85 gm |
| Length | 60.00 mm |
| (b) CASE | |
| Type | Rimless, Brass 70:30, Bottle Necked, Boxer |
| Mass | 6.7 gm |
| Length | 45.0 mm |
| (c) BULLET | |
| Type | Guiding Metal envelope FMJ, Steel insert & lead core |
| Mass | 4.16 gm |
| Length | 24.5 mm |
| (d) PROPELLANT | |
| Type | Ball Powder |
| Mass | 1.64 gm |
| (e) PRIMER | |
| Type | Boxer |
| Mass of Compo | 0.025 gm |

Performance Characteristics

- | | |
|----------------------------------------------------------|---------------|
| (a) Pressure Average | 335 Mpa (Max) |
| (b) Mean Velocity from 558 mm Barrel at 25 m from muzzle | 890 m/s. |



EQUIPMENT CATALOGUE

- (c) Consistency (Mean Figure of Merit at 457 m) 16.5 cm or less
(d) Extreme temperature performance -53 to +52 deg C

Shelf Life

The shelf life of Ammunition is 18 years.

Packing

20 Cartgs. are packed in one Carton and 40 such cartons in one H2A Box, hermetically sealed. One carrier size (6 A/L) contains 4 H2A boxes. Box H2A size - 311 x 156 x 194 mm
Carrier 6 A/L size - 667 x 327 x 205 mm

Hazard Classification

Compatibility group	5
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



5.56 TRACER AMMUNITION

ROLE:

Cartridge (INSAS) 5.56mm Tracer Ammn is used for location of target/ trajectory, incendiary effect and signalling and is fired from;

- a) Semi-automatic INSAS Rifle
- b) INSAS LMG.



Physical Characteristics

- | | |
|----------------|----------------------------------------------------------|
| (a) CARTRIDGE | |
| Calibre | 5.56 x 45 mm |
| Mass | 13.00 gm |
| Length | 60.00 mm |
| (b) CASE | |
| Type | Rimless, Brass 70:30, Bottle Necked, Boxer |
| Mass | 6.5 gm (Min.) |
| Length | 45.0 mm |
| (c) BULLET | |
| Type | Guiding Metal envelope FMJ, Pyro composition & lead core |
| Mass | 4.4 gm |
| Length | 28.8 mm |
| (d) PROPELLANT | |
| Type | Ball Powder |
| Mass | 1.60 gm |
| (e) PRIMER | |
| Type | Boxer |
| Mass of Compo | 0.025 gm |

Performance Characteristics

- | | |
|----------------------------------------------------------|-----------------------|
| (a) Pressure Average | 330 Mpa (Max) |
| (b) Mean Velocity from 558 mm Barrel at 25 m from muzzle | 865 m/s. |
| (c) Consistency (Mean Figure of Merit at 457 m) | not exceeding 33.0 cm |
| (d) Matching of trajectory at 457 m | not exceeding 33.0 cm |



- (e) Tracing Characteristics Up to 13m-dimzone 125m-700m
bright crimson red trace
- (d) Extreme temperature performance -52 to +52 deg C

Shelf Life

The shelf life of Ammunition is 18 years.

Packing

20 Cartgs. are packed in one Carton and 40 such cartons in one H2A Box, hermetically sealed. One carrier size (6 A/L) contains 4 H2A boxes.

Box H2A size - 311 x 156 x 194 mm

Carrier 6 A/L size - 667 x 327 x 205 mm

Hazard Classification

Compatibility group	S
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



5.56 MM BALL MK N AMMN (SS 109)

The Cartridge 5.56 mm Ball Mk N is equivalent to 5.56 mm NATO (SS 109) ammunition and are suitable for 5.56 mm standard weapon for firing, which can use 5.56 mm NATO Ammunition or INSAS Ammunition.



Physical Characteristics

(a) CARTRIDGE	
Calibre	5.56 x 45 mm
Length	57.4 ± 0.6 mm
(b) CASE	
Type	Rimless, Brass 70:30, Bottle Necked, Boxer
Length	45.0 mm
(c) BULLET	
Type	Guiding Metal envelope FMJ, Steel Insert and Lead core
Mass	4.0 gm
(d) PROPELLANT	Ball Powder Double Base (NG & NC)
(e) PRIMER	Lead Styphnate base, Boxer type

Performance Characteristics

(a) Pressure (Radial)	342 Mpa (Avg) 356 Mpa (Max)
(b) Velocity at 25 m from standard test barrel	910 ± 10 m/s.
(c) Consistency Mean Figure of Merit at 457 m from standard test barrel	16.5 cm or less
(d) Penetration at 700 mtrs	90% of rounds shall penetrate 3.45 mm NATO standard MS Plate to hardness 95-123 VPN
(e) Action time (Hang Fire)	0.003 second max
(f) Extreme Temperature range	-54 to +52 deg C

Quality

Various strict quality checks are adopted during manufacture. All the components are proved and inspected separately in empty stages before they are taken for Filling/Assembly.



EQUIPMENT CATALOGUE

Shelf Life

The shelf life of Ammunition is 15 years.

Packing

20 Cartons . are packed in a paper Carton and 40 such cartons in one H2A Box, hermetically sealed. Box H2A Size- 311 X 156 X 194 mm

Hazard Classification

Compatibility group	5
Hazard Division	1.4
Fire fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



CARTRIDGE 14.5 MM TRAINING AMMUNITION

This ammunition is used as training device for Artillery personnel both individual training of gun crews, observers and fire controllers and combined training of Artillery personnel within a unit.



Specification

Mass of complete round	67 g	
Length	65 mm (Approx.)	
Mass of projectile	59 + 1 g	
Mass of propellant	Velocity	Range
Charge I - .2 g	115 m/s	894 m
Charge II - .3 g	125 m/s	994 m
Charge III - .33 g	135 m/s	1146 m

Chamber Pressure

The average chamber pressure must not exceed 1300 bar at 294 K \pm 2 K.

Function

With time Fuze

The delay time i.e. the time between firing and the detonative deflagration of the smoke charge must not deviate more than 15% from the delay time specified.

Packing

10 rounds are to be packed into a cardboard box. 20 such cardboard boxes (200 rounds) are to be packed in a case for transportation.

Complete round consists of Cartridge Case, Primer No. VI, propellant charge and projectile.

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

CARTG SIGNAL 16MM RED/GREEN/WHITE



Technical Specification

Estimated Mass	Red : 12.88 grams Green : 13.43 grams White : 12.00 grams
Net expl content	Red : 6.526 grams Green : 6.026 grams White : 4.026 grams
Length of cartg	39.0-0.2 mm
Diameter	16.6-0.1 mm
Height of burst	60 m
Duration of burning	3.5 sec (min)
Weapon	13 mm 1A hand projector
Shelf Life	5 years

Role

Cartridge 16 mm belongs to the family of signalling ammunition. These are used extensively in battle field for communication, locating position and distress signalling, coded communication.

Function

Cartridge 16 mm is very handy signal. Ammunition fired from a 13 mm hand projector where the ammunition is screwed and fired by triggering. It is used by land, navy and airforce personal for all purpose of signalling.

Advantages

Packed in a pouch containing 6 cartridges, 2 of each colour alongwith projector. Very handy to carry and operate. Easy night identification.

Quality

Quality Assurance System on the product is based in accordance with ISO Standard ISO-9001 IS-2500/BS-6000 Related JSS/BIS/IND (ME) store specn./drawings.

Safety

The ammunition is safe in all respects during handling storage and transportation.

Reliability

Ammunition is produced to a tight AQL. The ammunition has achieved a high degree of reliability.

Packing

Packing consists of inner and outer packages. 6 cartgs. are packed in polythene bag and hermetically sealed. Four polythene bags are packed in a carton. 8 such cartons are thus packed in a steel box hermetically sealed. 4 such steel boxes thus packed in a carrier. Weight - 27.5 Kgs.

Stowage Dimension

667 mm x 327 mm x 205 mm. Holding 768 cartgs.

Hazard Classification

Compatibility	G
Hazard division	1.2
Fire fighting	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

CARTRIDGE SIGNAL 1" RED/GREEN/ILLG.



Technical Specification

Estimated Mass	Red : 45.5grams Green : 45.5 grams illg : 54.5 grams
Net expl content	Red : 16.142 grams Green : 16.848 grams illg : 20.736 grams
Length of cartg	Red - Green-68.58mm, illg-97.79mm
Diameter	26.29(H)mm, 25.9 (L)mm
Height of burst	36.5 m
Duration of burning	6.5 sec (min)
Weapon	Signal Pistol 1"
Shelf Life	10 years

Role

Cartridge 1" belongs to the family of signalling ammunition. These are used extensively in battle field for communication, locating position and distress signalling. These are also used for colourful display.

Function

Cartridge 1" in fired from a pistol.

Advantages

Ammunition can be fired directly by hand pistol. Can be used in land air and sea. Ammunition is fit for air drop and sea worthy transportation. Easy to handle and convenient to carry by an individual. Easy for night identification.

Quality

Quality Assurance System on the product is based in accordance with ISO standard ISO-9001 IS-2500/BS-6000 Related JSS/BIS/IND(ME)spec./Store drawings.

Safety

The ammunition is safe in all respect during handling operation and transportation.

Reliability

The ammunition has achieved a high degree of reliability & consistency.

Packing

Packing consists inner and outer standard packages. In the inner polythene bags 4 cartridges are packed. 12 such polythene bags are packed in 1 steel box hermetically sealed. 4 such steel boxes are packed in a steel outer carrier 6A containing 192 cartridges. The packing is fit for air drop and sea worthy transportation. Each Package contains illg 192 or R/G 288 cartridges packed in carrierr 6A.

Stowage Dimension

667 mm x 327 mm x 205 mm. Holding 192 cartridges weighing 24 kgs.

Hazard Classification

Compatibility	G
Hazard division	1.2
Fire fighting	2

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>

CARTRIDGE SA 12.7 MM API AND APIT



General

This small arms ammunition is fired from the 12.7mm Anti aircraft machine gun (HCB 12.7mm) which is mounted on commanders cupola T-72 tanks. The design of this ammunition is similar to a small complete round. It includes cartridge case, percussion cap, propellant charge and bullet with spotting and tracer composition.

The cartridge case of the brass is rimless type, formed cap chamber at the base provided with two flash holes and an anvil. The mouth of the case is coned on to the body of the bullet. Percussion cap is Berdan type consisting of a brass cap in which is loaded, a cap composition (i.e. FA 956) in form of pellet which is Lead Styphnate based. The propellant charge is made up of Nitrocellulose having multi tubular.

The bullet is of the composite type and streamlined. It consists of two parts which are contained in outer envelope of gliding metal. The first part consists of steel core which is enclosed in outer lead sleeve. In case of API and incendiary composition is placed inside the GM envelope before insertion of steel core and lead sleeve assembly. The end position of the envelope is then turned over. In case of APIT bullet there is an addition tracer capsule at the boat tail end of the bullet. The ammunition is manufactured as per No7E21.000Ty.

Physical Characteristics

PARAMETER	API	APIT
Total length of ammunition	147 mm (Maximum)	147 mm (Maximum)
Total mass of ammunition	137.00g (Maximum)	132.00g (Maximum)
Mass of bullet	49.00g (Maximum)	44.8g (Max)
Mass of case	64.60g	64.60g
Mass of cap	0.990g	0.990g
Explosive filling in Cap	0.095g (Max) Dry	0.095g (Max) Dry



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

Explosive filling in bullet	1.05 g Incendiary compo	2.785 g Tracer & Incendiary compo
Propellant (ACM)	15.17 g (as reqd)	15.17 g (as reqd)
Net explosive content	16.145 g (Max)	18.93 g

Performance Characteristics

(a) Pressure Average	303.8 Mpa (Max)
(b) Mean Velocity from 558 mm Barrel at 25 m from muzzle	817 m/s
(c) Consistency (Mean Figure of Merit at 100 m)	18 cm or less
(d) Extreme temperature performance	Ambient & 50 deg C

Quality

The raw materials used for components are tested by independent Quality Assurance Department. During manufacturing stage, quality surveillance by both producer and services representative are provided. All the major components i.e case cartridge, bullet filled, cap filled and propellant are test fired and only passed proof components are taken into final assembly of the ammunition. The complete rounds are also proved dynamically for (a) Velocity, (b) Pressure, (c) Armour piercing, (d) Consistency, (e) Tracer functioning.

Safety

The cap being percussion type, gets initiated only if gets a blow. The ammunition is therefore safe during manufacture, transit and storage.

Shelf Life

The shelf life of the Ammunition is 7 years.

Packing

80 rounds are packed in 16 cartons and these 16 cartons are packed in one steel box. 4 such steel boxes are packed in one steer carrier.

Stowage Dimensions

Packing steel box size	311 X 156 X 196 mm
Packing outer carrier size	677 X 327 X 205 mm
Gross weight outer package	62 Kg
Net weight	38.52 Kg
Volume of outer package	0.045 cu meter





EQUIPMENT CATALOGUE

Hazard Classification

Compatibility Group	S
Hazard division	1.4
Fire Fighting classification	4

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan, Government of India, Ministry of Defence
10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80 F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.com>



EQUIPMENT 81 MM MORTAR

A lightweight weapon, which can be easily deployed. The base plate is star shaped with rotating socket in the centre and three sets of ribs and spades which provide all round traverse without movement of the plate and ensures equipment stability in all types of ground conditions. The special steel mount is provided with buffer assembly, cross leveling device and elevating and traversing gears.



Performance

- | | |
|-------------------------------------------------|---------------------|
| a) Maximum Muzzle Velocity | 295 M/sec. |
| b) Rate of Fire: | |
| i) With relaying the Mortar for every round | 6 to 8 rds/minute |
| ii) Without relaying the Mortar for every round | 20 rds/minute (max) |

c) Range

Charge	Max. Range	Charge	Max. Range
0	0550 M	5	3725 M
1	1275 M	6	4175 M
2	1980 M	7	4625 M
3	2640 M	8	5000 M
4	3200 M		

6000 M with improved version

- | | |
|------------------------------------------------------------|------------------------------------|
| d) Life: | |
| i) Max No. of EFC's which may be fired between Examination | 2000 |
| ii) Condemnation limit Bore Dia | 81.91 mm |
| e) Maximum Service Pressure | 600 Kg/Sq.cm.
Copper (3.80 tsi) |

Physical Characteristics

- | | |
|------------------------------------------------------------------------------------------------------------|---------------------|
| a) Weights: | |
| i) Total Wt. of the Equipment with sight and Accessories including Boxes transit for Barrel and Base Plate | 135 Kgs |
| ii) Total Wt. of the Equipment without sight and accessories | 40.6 Kgs (89.55lbs) |
| iii) Total Wt. of the Barrel (with Breech Block) | 14.5 Kgs (32 lbs) |
| iv) Total Wt. of the Mount | 11.7 Kgs (25.8 lbs) |

- v) Total Wt. of the Base Plate 14.4 Kgs (31.75 lbs)
- vi) Total Wt. of the sight heavy Mortar Cased IC 4.7 Kgs
- vii) Total Wt. of the sight without the case 2.5 Kgs
- b) Length of the Barrel with Breech Block 1550 mm (61 in)
- c) Calibre of Barrel H.81.44 mm/
L 81.40 mm
- d) Elevation limits 30 d to 85 d (or 533
mils to 1511 mils)
- e) Traverse (right or left)
- i) By moving the Bipod 360 degree
- ii) Without moving the Bipod 7° 30' to 18° 30'

Position of Clamping Collar
Angle of Elevation

	45°	60°	75°
Top	7° 30'	9°	16°
Middle	10°	11° 30'	16° 30'
Bottom	12°	14° 15'	18° 30'

b) Height:

- i) For loading in unprepared position of Base plate at 45° Elevation - 47"
at 85° Elevation - 66"
- ii) For loading in prepared position of Base Plate at 45° Elevation - 40"
- g) Striker Protrusion L 1.5. mm, H 1.8 mm
- h) Recoil Absorbing arrangement by Shock absorbers (i.e. the mechanical spring type with two guide Rods / tubes forms an elastic link between the Barrel and the bipod)
- l) Detachment 3 men

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

E: ofbtrade@dataone.in

F: +91-33-2248 1748/2210 8235

w: <http://www.ofb.gov.in>

MINE PROTECTED VEHICLE



Technical Data

Length	6.00 M
Width	2.90 M
Height	3.07 M
Ground Clearance	305 mm
Speed	85 KMPH Max
Patrol Speed	50 KMPH
GVW /Pay Load	11 Tons/1400 Kgs
Seats	10 + 2
Range	1000 Km
Fordability	1000 mm
Protection Level	Mine Blast 14 Kgs TNT under wheels 10 Kgs TNT under Hull
Small Arms	7.62 SLR Rifle firing from a distance of 10 meters on all sides of vehicle
LMG/MMG	Rotating Turret provided

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

EQUIPMENT 120 MM MORTAR

A very effective light artillery weapon which fires HE, smoke and illuminating ammunition. Capable of being carried manually over short distances and transported by animal pack, towed behind a jeep and para-dropped. Provided with a base plate consisting of upper plate having a rotating socket and two housings for the clamping collar pivot axis. The lower part has three sets of ribs and spades which provide stability to the plate.



Performance

(a) Maximum Muzzle Velocity:

- | | |
|-----------------------|---------|
| i) With HE M-44 Bomb | 331 M/S |
| ii) With PEPA LP Bomb | 305 M/S |

(b) Rate of fire:

- | | |
|-------------------------------------------------|--------------------|
| i) By gravity firing | |
| (a) With relaying the Mortar for every round | 5 to 6 rds/minute |
| (b) Without relaying the Mortar for every round | 8 to 10 rds/minute |
| ii) By lanyard firing | |
| (a) With relaying the Mortar for every round | 3 to 4 rds/minute |
| (b) Without relaying the Mortar for every round | 5 to 6 rds/minute |

(C) Range
PEPA LP

Charge	HE M-44 Assistance	Without Rocket Assistance	With Rocket
0	1360 m	-	-
1	2200 m	-	-
2	3050 m	2530 m	-
3	3850 m	3425 m	6150 m
4	4750 m	4175 m	7180 m
5	5550 m	4800 m	7800 m
6	6150 m	5370 m	8450 m
7	6650 m	5900m*	8950 m

*10000 with improved version

(d) Life	5000rds (Provisional)
(e) Maximum Service Pressure HE-M 44 Bomb	820 Kg /Sq.cm
PEPA LP Bomb	850 kg /Sq.cm
(f) Maximum Towing Speed	50 Km/hr

Physical

(a) Weights :

i) Total Wt. of the Equipment with sight and accessories	421 Kgs
ii) Total Wt. of the Equipment without Sight and accessories	402 Kgs
iii) Total Wt. of the Barrel (With Breech Piece)	68 Kgs
iv) Total Wt. of the Mount	86 Kgs
v) Total Wt. of the Base Plate	80 Kgs
(vi) Total Wt. of the Carriage with Wheels	137 Kgs
vii) Total Wt. of the Carriage Without Wheels	93 Kgs
viii) Total Wt. of the Wheels	44 Kgs
ix) Total Wt. of the Towing Ring	8 Kgs
x) Total Wt. of the Base Plate Clamping collar	6 Kgs
xi) Total Wt. of the Travelling Shield	17 Kgs
xii) Total Wt. of the Army sight (APX-L-811) with Case	3 Kgs
xiii) Total Wt. of the Army sight (APX-L-811) Without Case	1.7 Kgs
xiv) Total Wt. of the IA Heavy Mortar Sight Cased (IMR30GA)	4.7 Kgs
xv) Total Wt. of the IA Heavy Mortar Sight without Case	2.5 Kgs
xvi) Total Wt. of the Accessories	16 Kgs

b) Length :

i) Length of Barrel with Breech Piece	1750 mm
ii) Total Length of Equipment in TOW	2565 mm
c) Calibre of Barrel	120.15 mm

d) Elevation:

i) Elevation Limits	45 o to 85 o
ii) Elevation per turn of Hand Wheel	18 min. 20 sec.
e) Maximum width of Equipment	1585 mm
f) Ground Clearance in Tow	260 mm
g) Height :	
i) In Tow	1195 mm
ii) For loading in unprepared position of base Plate	
At 45 degree Elevation	1460 mm
At 80 degree Elevation	1945 mm
iii) For loading in prepared position of Base Plate	
At 45 degree Elevation	1145 mm
At 80 degree Elevation	1675 mm

h) Striker Protrusion	1.9 mm Min. Max. 2.5 mm
l) Recoil Absorbing arrangement	Shock Absorber

J) Traverse

1) Distance between top face of Breech and Upper Collar Shock absorber.	Elevation (approx) (approx)	Top traverse (approx)	Traverse per Turn of Hand Wheel (approx)
200 mm	55 d 10'(min) 85 d (max)	22 d 55' 31 d 40'	22' 30'
400 mm	46 d 35'(min) 74 d 10'(max)	18 d 30' 24 d 20'	18' 25'
500 mm	42 d 05'(min) 68 d 10'(max)	16 d 45' 22 d 12'	17' 22'
2) With moving bipod		360 degree	

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.


T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>

EQUIPMENT 105/37 IFG E1 AND 105/37 LFG E2



S. No	Characteristics	EQPT105/ 37mm IFG E1	EQPT 105/ 37mm LFG E2
1.	Calibre	105 mm	105 mm
2.	Barrel length	3890.5 mm	3890.5 mm
3.	Mass of Barrel	587.7 kgs	396 kgs
4.	Mass of Ordnance	840 kgs	716 kgs
5.	Mass of Eqpt	3400 kgs	2380 kgs
6.	Range	17425 Metres	17200 Metres
7.	Elevation	-3 deg. To +73 deg	-5 deg. To +73 deg
8.	Traverse	30 deg. Left 30 deg. Right	I) 5 deg. Left 5 deg. Right II) 360 deg. Traverse on Firing platform
9.	Rate of Fire		
	i) Normal	3 Rds/min	4 Rds/min
	ii) Intense	5 Rds/min (upto 10 mins)	6 Rds/min (upto 10 mins)
10.	Sustained Fair		
	i) Upto Charge 5	1Rd/min (For 2 hrs.)	1Rd/min (For 2 hrs.)
	ii) For Charge Super	1Rd/2 min (For 2 hrs.)	1Rd/2 min (For 2 hrs.)
11.	Time into and out of action	1 min	2 to 3 min
12.	Detachment	7	7
13.	Recoil system	Hydraulic Rotating Valve	Rotating Valve type



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

	Buffer	type Controlled Hydroposumatic	Hydroposumatic Telescopic
14.	Muzzle brake type	Double baffle	Double baffle
15.	Overall length	7240 mm	7216 mm 5054 mm (Folded Back Position)
16.	Maximum Width	1980 mm	1820 mm
17.	Chamber Capacity	5.178 litres	5.178 Litres
18.	Loading Angle	All angles	All angles

Contact Person

Marketing & Export Division

Ordnance Factory Board

Ayudh Bhawan

Government of India

Ministry of Defence

10A, S. K. Bose Road, Kolkata – 700 001, India.

T: +91-33-2248 9027 / 2248 2103 / 2248 5077-80

F: +91-33-2248 1748/2210 8235

E: ofbtrade@dataone.in

w: <http://www.ofb.gov.in>



PRECISION ELECTRONICS LIMITED

Address : D-10, Sector 3, Noida - 201 301
Gautam Budh Nagar, India

Website : www.pel-india.com

Head : Nikhil Kanodia
President

Telephone : +91-120-2520516 / 4325299

Fax : +91-120-2524337

Mobile : +91-9910383148

Email : nikhil.kanodia@pel-india.com

ORGANISATION PROFILE:

Precision Electronics Limited (PEL) established in 1979, is a Defence Licensee company that provides of Communication & Electronics Products, Solutions for Mission Critical and Critical Infrastructure protection and provides on ground service to the User on behalf of the Foreign Equipment supplier. PEL has formed partnerships with global majors viz Raytheon of USA, IAI/Elta & Elbit of Israel, Ultra Electronics of Canada etc. Our footprint covers all the three services and the Defence Design Development Agency (DRDO).

Our two plants situated in Noida (UP) and in Roorkee (Uttarakhand) are state of art facilities that are approved by the Defence inspection agency (DGQA) are ISO 9001:2015 and AS 9100D accredited.

Precision is Technocrat driven with strong in-house design and engineering capability. It has designed secured MILCOM systems that are deployed by the Indian Army, voice and data recorders that meet the mission critical requirement of the Air force and have undertaken turnkey assignments for securing the Naval bases.

2MB PCM MULTIPLEXER (Model: PFM-3440M)



- PFM3440M is Flexible (Versatile) Transmission equipment, which aggregates various legacy voice and data interfaces onto a trunk channel which could be TDM or IP.
- It is a ruggedized as per JSS-55555 Table L2B for land use and is "Equipment in Service" of the Indian Army
- System works on TDM backplane driving E1 signals with Time Slot Interchange (TSI) capability at 2Mbps and Nx64 Kbps time slots.
- Network Management with cross-connect feature makes it versatile system to integrate with Network and user Interface circuits.

Characteristics of Equipment

- Expandability: up to 8 Mbps
- Access Flexibility: host of various type of voice and data interfaces
- Media Flexibility: supports connectivity to Cu, Optical etc.
- Usability: in Tactical and Peace-time usage
- Future proofing: for supporting Networked force structures
- High Reliability: through redundancies (Power & Control), MIL-spec construction and Hot-swappable Cards
- Built-in Time Slot Interchange (TSI) for Add-Drop functionality between tributary & E1
- Legacy interoperability
- Configuration data storage in non-volatile memory
- PEL View (GUI Based) management software using SNMP protocol



- Ethernet/ Console ports (for in-band/out-band) Configuration & Management
- Local Craft Terminal (LCT) for Monitoring & Configuration
- Indigenous capability to provide upgrades and lifecycle support
- Versatile User Interfaces:
 - Voice: 2W FXO / 2W FXS / 2W Magneto / 2W-4WE&M / 2W hotline
 - Data: G.SHDSL 64 to 2048 Kbps, 64Kbps Co-Directional, V.35, RS-232/V.24 / Bridge / Router Interfaces

Contact Person

Amit Mittal

Sr. DGM (Technical)

T: +91-120 2555176/177

M:+919910383135

F: +91-120 2554337

E: amit.mittal@pel-india.com



PUNJ LLOYD RAKSHA SYSTEMS PRIVATE LIMITED

- Address** : 78, Institutional Area, Sector - 32
Gurgaon, Haryana - 122 001, India
- Website** : www.punjllloydgroup.com
- Head** : Ashok Wadhawan
Head Defence
- Telephone** : +91-124-2620123
- Fax** : +91-124-2620111
- Mobile** : +91-8800440558
- Email** : ashokwadhawan@punjllloyd.com

ORGANISATION PROFILE:

Punj Lloyd Raksha Systems Pvt Ltd (PLR) a joint venture company between Punj Lloyd and Israel Weapon Industries (IWI) is India's first private Small Arms manufacturer. Entire range of World Class Weapons such as TAVOR series Assault Rifles, three caliber X95 Assault Rifle and SMG, NEGEV Light Machine Gun, the well known GALIL series of Assault/Sniper Rifles and UZI PRO are to be manufactured in India.

PLR is proud to have rolled out first lot of Indigenous 5.56x45 mm X-95 Assault Rifles from its manufacturing plant. A State-of-the-Art laboratory has also been established by PLR to cater for Maintenance, Repair and Overhaul (MRO) of Optoelectronic equipment.

Punj Lloyd has created an ecosystem for upgrading and manufacturing Artillery Guns. World class upgun solution to upgrade 130 mm Russian Guns into 155 mm / 45 calibre guns by the company achieve ranges up to 40 km. The company's upgrade solution for the existing ZU 23 mm 2B Air Defence Guns by replacing the manual laying system with EOFCS gives it capability to engage aerial targets during day and night in the plain, desert and mountainous terrain.

Punj Lloyd has its presence felt in the Scanning and Imaging systems as well. The company has been awarded an order to supply five Full Body Truck Scanners from MHA and also has a solution for through the wall detection / imaging Systems.



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

SMALL ARMS

Punj Lloyd Raksha (PLR) Systems Pvt Ltd is the first Indian private company to receive the license to manufacture Small Arms & Ammunition in India.

Punj Lloyd Raksha brings to India world-class production, design and development of unrivalled weapons. World renowned weapons like the innovative TAVOR Assault Rifle, three caliber X95 Assault Rifle and SMG, the reliable NEGEV Light

Machine Gun, the well-known GALIL ACE Assault Rifle, the GALIL Sniper Rifle, the brand new DAN Bolt Action Sniper Rifle and the legendary UZI SMG and its latest evolution UZI PRO will be produced for domestic and international markets at Punj Lloyd Raksha Systems Manufacturing Plant. All these weapons are in compliance with the most stringent military standards (MIL STD) and ISO 9000 standards.

These weapons are already in service with all Indian elite forces like Indian Army Special Forces, Garud (IAF), MARCOS (Indian Navy), COBRA Force (CRPF), BSF to name a few.



Contact Person

R K Sharma

AGM (Defence)

T: +91-124 2620123

M: +91-8826313475

F: +91-124 2620111

E: rksharma@punjlloyd.com



X95 5.56 X 45MM | 5.45 X 39MM | 9X19MM ASSAULT RIFLE | CARBINE | SMG

X95 is an innovative firearm and is manufactured out of high strength steel impact modified polymer, providing a strong but light weapon. It incorporates advanced technology that allows conversion among three different calibre within minutes and it saves training time, spare parts and reduces overall cost.



Advantages

- Bull pup configuration
- Rear center of gravity
- Fully ambidextrous
- The only three calibre weapon in the world 5.56x45mm | 5.45x39mm 19x19mm
- 360° picatinny rail
- Low recoil, enhanced stability when firing
- Enhanced ergonomics: can be shot single handed or with both hands
- Six points for support: stable while shooting in prone position, sitting, kneeling and standing, firing under arms and from hip
- Modularity: a versatile weapon system that can be modified for a variety of operation and scenario
- Short weapon with long barrel

Features

- Simple field stripping into only two parts, no need for special tools
- Last round catch
- Easy and fast to mount 40mm grenade launcher, no need for special tools
- 100% interchangeability
- Flip up back up sight
- Closed bolt gas on piston head, rotating bolt firing operation

Contact Person

R K Sharma

AGM (Defence)

T: +91-124 2620123

M: +91-8826313475

F: +91-124 2620111

E: rksharma@punjloyd.com

GALIL SNIPER 7.62 X 51 MM



GALIL SNIPER distinguishes itself as the ultimate weapon having proficiency to fire accurately at long distances of 1000m targeting small, mobile or concealed objectives. The semi automatic attribute enables multi-target acquisition. The GALIL Sniper has proven to be a decisive factor in dense and extreme arenas.

Advantages

- 7.62x51 mm calibre
- 10125 round magazine capacity
- X10 MIL-STD day telescope
- Backup sight including tritium for night combat
- Two stage trigger
- Muzzle brake / jump compensator
- Reliable scope mount : no deviation after dismounting and remounting

Features

- Foldable and adjustable bipod
- Adjustable hand grip
- Adjustable butt monopod
- Ergonomic pistol grip
- Foldable butt stock with adjustable cheek rest
- Combat carrying bag including sniper's mattress

Contact Person

R K Sharma

AGM (Defence)

T: +91-124 2620123

M: +91-8826313475

F: +91-124 2620111

E: rksharma@punjllloyd.com

TAVOR 5.56X45MM / 7.62X51MM - ASSAULT RIFLE

TAVOR Assault Rifles have been rigorously tested on all terrain and performed flawlessly, demonstrating traits of superior precision, accuracy, reliability and enhanced human ergonomics.



Advantages

- Bull pup configuration
- Optimized ergonomic design
- Rear centre of gravity
- Fully ambidextrous
- Long picatinny rail version
- 30 round NATO magazine capacity
- Day to night optic conversion without re-zeroing
- Foldable back up sights which include tritium for night combat
- Manufactured out of high strength impact modified polymer, providing a strong but light frame
- Six points for support: stable while shooting in prone position, sitting, kneeling and standing, firing under arms and from hip
- Minimum operator and armourer level maintenance, cost effective

Features

- Simple field stripping into only two parts, no need for special tools
- Last round catch
- Corrosion resistant metal parts
- 100% interchangeability
- Flip up back up sight
- Integrated reflex sight (optional)
- Also available in Semi Automatic version

Contact Person

R K Sharma

AGM (Defence)

T: +91-124 2620123

M: +91-8826313475

F: +91-124 2620111

E: rksharma@punjllloyd.com

NEGEV 5.56 X 45MM | 7.62 X 51MM LIGHT MACHINE GUN

NEGEV is a robust and reliable assault LMG with powerful target acquisition and accurate performance in the modern battlefield. Its semi-automatic feature empowers its user in Close Quarter Battle (CQB) operations safely.



Advantages

- Two operation modes:
- Semi automatic mode for accurate and fast controlled fire for CQB
- Automatic mode for maximum firepower
- Safety mechanisms which minimize uncontrolled fire
- Can be fired from a variety of mounts, special helicopter airborne mounts, vehicle or naval mount
- Enables firing with folded butt stock
- Tritium night sights
- Picatinny rails for optical devices and diverse accessories

Features

- Gas regulator for additional power in adverse conditions
- Fed from an assault drum, belt chain or magazine
- Robust and durable bipod
- Quickly dismantle in the field for maintenance
- Low silhouette
- Backup iron sights
- Adjustable butt stock and cheek rest
- Safety mechanisms

Contact Person

R K Sharma

AGM (Defence)

T: +91-124 2620123

M: +91-8826313475

F: +91-124 2620111

E: rksharma@punjloyd.com

ACE



The ACE line of Assault Rifle is based on the reliable, proven mechanism of the famous GALIL Assault Rifle, which was the main assault rifle of the IDF.

The weapon was designed to incorporate enhanced human engineering and ergonomics, making it the outstanding assault rifle for the emerging unstable realities of modern combat. These attributes empower the ACE Assault Rifle to obtain high accuracy and reliability under the most extreme conditions.

Advantages

- Short, lightweight Assault Rifle available in different lengths
- It has 5.56x45mm NATO standard 17.62x39mm/7.62x51 mm
- 360° picatinny rail
- Proven reliability under adverse and extreme conditions
- Easy-to-use by right or left-handed shooters
- Modern streamlined ergonomic design

Features

- Tritium night sight
- Telescopic butt stock
- Muzzle break | jump compensator [7.62 x 51 mm calibre only]
- Simple maintenance: no tools required when stripping the weapon
- Last round catch [5.56 x 45 mm caliber only]
- Available in Semi-Automatic

Contact Person

R K Sharma

AGM (Defence)

T: +91-124 2620123

M: +91-8826313475

F: +91-124 2620111

E: rksharma@punjllloyd.com



EQUIPMENT DISPLAY

EQUIPMENT CATALOGUE

OPTRONICS



Punj Lloyd Raksha is in collaboration with Meprolight that has the entire range of Opto Electronic systems to offer. Day sights, Image Intensifier, Uncooled Thermal Imaging devices act as a force multiplier in increasing the efficacy of any Small Arm.

PLR has also established facilities/laboratory to carry out **Maintenance, Repair and Overhaul (MRO) of Small Arms and Sights cum Associated Accessories** manufactured by IWI and Meprolight. The company is fully geared up to take on MRO at the plant location or insitu to meet the urgent requirement of our customers. Infrastructure in terms of work space, technical manpower, spares back up and Special Maintenance Tools (SMTs) have been put in place.



Contact Person

R K Sharma

AGM (Defence)

T: +91-124 2620123

M: +91-8826313475

F: +91-124 2620111

E: rksharma@punjlloyd.com



THROUGH-THE-WALL DETECTOR / IMAGING SYSTEMS



Through-the-wall Detector / Imaging Systems are compact radar-based devices, optimized for quick tactical decision making in urban operations. They provide real-time mission-critical information on live and static objects hidden behind walls and barriers, including presence of life in the room and room general layout. Military and law enforcement teams conducting urban operations require reliable information for determining the necessary tactical approach for successful mission execution. These scanners are excellent force multipliers to the law enforcing agencies during the time of hostage crisis and room intervention operations. They are also useful during natural or manmade disasters like earthquake or fire to detect life beyond the visual.

Xaver™ 100
Handheld, Through-Wall Life Detector



Xaver™ 400
Compact, Tactical Through-Wall Imaging System



Xaver™ 800
High Performance ISR Portable Through-Wall Imaging System



Contact Person

R K Sharma
AGM (Defence)
T: +91-124 2620123
M: +91-8826313475

F: +91-124 2620111
E: rksharma@punjllloyd.com



EQUIPMENT CATALOGUE

SIMULATOR DEVELOPMENT DIVISION

Address : Simulator Development Division, Trimulgherry Post
Secunderabad, Telangana - 500015, India

Head : Commandant, Simulator Development Division

Telephone : +91-40-27794273

Fax : +91-40-27795418

Email : itoffr-sdd-army@nic.in

ORGANISATION PROFILE:

Simulator Development Division based at Secunderabad focuses in the thrust areas of Simulators and Innovations for the Indian Army. It is working in the field of simulation for more than three decades and has developed simulators for varied applications such as driving simulators, firing simulators, medical simulators etc.



SM CARAPACE ARMOR (AN EOU OF SMPP PRIVATE LIMITED)

Address : M-17, N.D.S.E. Part II 110049 New Delhi India
Website : www.smgroupindia.com
Head : S. C. Kansal
Chairman & Managing Director
Telephone : +91-11-26254275, 41421577
Fax : +91-11-26262129
Mobile : +91-9910409147
Email : contact@smgroupindia.com

ORGANISATION PROFILE:

We take this opportunity to introduce the "SM Group of Industries"; India's pioneer in development of very crucial technologies for vital Defence products and in finding highly innovative solutions in some of the most challenging areas. Founded in 1985, SM Group is today one of the leading Industrial Groups in India having extensive manufacturing facilities spread over an area of 29 acres on National Highway-2 (in NCR, Delhi) and other parts of India. With more than 30 years of technology-driven innovation and sustained growth, SM Group has presence in diverse areas like:

- Personnel Protection
- Vehicle/Aircraft/Ship Armour
- Tank Munitions: 120mm and 125mm
- Artillery Munitions: 155mm Bofors Gun, 130mm and 105mm artillery guns

PERSONAL PROTECTION/BODY ARMOUR SOLUTIONS



Apart from Military, Para-Military & police forces in India, we already export Light Weight Body Armor, Ballistic Helmets, Armor Plates and Ballistic Shields to many countries like France, Netherland, Egypt, Turkey, Philippines, Saudi Arabia etc.

- **Body Armour**- Ballistic protection of NIJ Level IIIA to IV
- **Armor Plates** - Stand alone or ICW with protection of NIJ Level III, III SP and IV, all shapes and sizes
- **Ballistic Helmets** - For protection of NIJ Level IIIA, III, III+ & fragments, all designs (PASGT, ACH, MICH, TCH)
- **Ballistic Shields** - Protection of NIJ Level IIIA to IV

Contact Person

Ashish Kansal / Sujeet Kumar

Executive Director / General Manager

T: +91-11-26254275, 26498884

F: +91-11-26262129 / 26498884

M: +91-9910409147, 9810199147

E: contact@smgroupindia.com

AIRCRAFT/HELICOPTER/VEHICLE/BOAT ARMOR



Light weight armor solutions for SUVs/Passenger Cars, Aircraft/ Helicopter and Ships. We are currently supplying ready to fit cut kits of advanced ceramic-B4C plates (CaraSTOP) & composite/PE Plates (CaraPRO) for armoring of **Airbus A400M aircraft** and already supplied hundreds of cut kits for armoring of:

- A-109 Augusta, Chinook Helicopters
- Naval Fast Petrol Boats (FPBs)
- Military Vehicles, Tanks
- Special Purpose Vehicles-Missile Carriers, ATVs

Armour solutions offered are for protection of STANAG

Level -1 to 5 and Blast Protections.

Contact Person

Ashish Kansal / Sujeet Kumar

Executive Director / General Manager

T: +91-11-26254275, 26498884

F: +91-11-26262129 / 26498884

M: +91-9910409147, 9810199147

E: contact@smgroupindia.com

ADVANCED CERAMIC B4C (CARASTOP) PLATES FOR ARMOUR



SM Group is one of the very few OEMs in the world and only one in India who also manufacture raw materials used in Armour. The CaraSTOP-B4C ceramic which was developed by SM GROUP using in-house R&D is one of the lightest ceramic being exported to Armour manufacturers in Germany, Australia, South Korea, France, Israel, Poland etc. Its salient features are:

- Lightest Weight Ceramic for armor applications
- Multi-hit capability on monolithic plate
- Custom shape size and thickness as per application
- Being used successfully across the world

Contact Person

Ashish Kansal / Sujeet Kumar

Executive Director / General Manager

T: +91-11-26254275, 26498884

M: +91-9910409147, 9810199147

F: +91-11-26262129 / 26498884

E: contact@smgroupindia.com

TANK AND ARTILLERY MUNITIONS



We are among the first to develop and manufacture Combustible Cartridge Cases in India and we have played a key role in meeting the specific ammunition needs of the Indian Army for their main battle Tanks - Arjuna and T-72, T-90 series of Russian guns. We have certified manufacturing facilities for these tank and Artillery munitions and we have already supplied more than 2,00,000 combustible cartridge cases to Indian Army:

- Tank ammunition : 120MM and 125MM (FSAPDS and HESH)
- Artillery ammunition : 105MM and 155MM (LZ & HZ), 130MM (FVC and RVC)
- Mortar Bomb ammunition : Augmented Cartridges and Transparent Celluloid Sheets

Contact Person

Ashish Kansal / Sujeet Kumar

Executive Director / General Manager

T: +91-11-26254275, 26498884

M: +91-9910409147, 9810199147

F: +91-11-26262129 / 26498884

E: contact@smgroupindia.com



TATA AEROSPACE & DEFENCE

Address : Bombay House, 24 Homi Mody Street
Mumbai 400 001, India

Website : www.Tata.com

Head : Sukaran Singh

Telephone : +91-22-66657655

Fax : +91-11-23341585

Mobile : +91-9820995989

Email : ssingh@tata.com

ORGANISATION PROFILE:

Over the last 150 years, the Tata Group has established a remarkable story of Enterprise, Fortitude and Social Responsibility in India. The Group has pioneered to create strategic businesses that have gone a long way in nation-building. In the same spirit, in the field of Defence and Aerospace (D&A), the Tata Group is investing and organising to create Tata Aerospace & Defence (Tata A&D) to offer group-wide D&A integrated solutions.

Built on trusted strength and a clear vision of India's needs, the consolidated Tata A&D is one of the country's largest private Aerospace & Defence solutions provider. With the requisite capabilities, resources and scale, we are equipped to deliver end-to-end innovative solutions encompassing Systems, Hardware, Software, Technology, and Digital solutions; all of which can be fully integrated across the key platforms necessary to secure India's land, sea and skies for the future.

Tata A&D has a strong portfolio of partnerships with leading global Aerospace and Defence firms, making us an integral partner in the international supply chain and in some instances, a global single source provider for global Defence companies. In addition to our growing list of joint ventures and agreements with leading global equipment manufacturers, we are also deeply invested in development of indigenous defence platforms for the Indian Defence Forces which is central to our long-term capability building strategy.

The Tata Group has served as a trusted partner to India's armed forces for over six decades and will continue to provide the world-class standards of quality and delivery that the Tata name is known for.



2KW FUEL CELL SYSTEM



2kW Fuel Cell System (FCS) is an indigenously developed Proton Exchange Membrane Fuel Cell (PEMFC) based, clean, light-weight, silent, reliable and rugged power solution for Auxiliary Power Backup applications. The 2kW FCS is suitable for both Stationary and Mobile applications and can operate in Industrial as well as Military environments. It is ideal for deployment in Repair / Maintenance Depots, Border Outposts (BOP), Tracked / Wheeled Vehicles, Disaster Management Vehicles, Emergency Communication Systems, Command Posts and can be used as an Auxiliary Power Unit (APU) to provide long endurance and silent power backup without the risk of detection.

Characteristics of Equipment

- DC Output: 28V / 48V DC
- Power: 2kW rated, 2.3kW Peak
- Modular & Scalable to higher capacities
- Weight: ~20 kg
- Startup time: < 15 seconds
- Communication Interfaces: RS485, USB OTG
- High Altitude Operation: < 3000m ASL
- Zero emission (only water vapour)
- Silent, Very Low Thermal / IR Signature
- MIL-STD-810F & JSS-55555 Compliant
- PESO safety certified Hydrogen Cylinders

Contact Person

Manoj Karam

Head - Renewable Products & Solutions

T: +91-22 6751 3600 / Extn.: 3631

M: +91-8655879301

F: +91-22 6751 3638 / 6751 3667

E: mkaram@TataPowerSED.com

30W FUEL CELL SYSTEM



The 30W Fuel Cell System (FCS) is an indigenously developed Proton Exchange Membrane Fuel Cell (PEMFC) based, light-weight, silent, and rugged power solution for portable / back-pack applications, suitable for both Industrial as well as Military Environments. It offers the highest energy density (Watt-hrs/Kg) vis-à-vis battery solutions for applications where portable power is required for extended period of autonomy. It uses hot swappable Chemical Hydride Fuel Cartridges, where hydrogen is produced in-situ giving upto 15 hours of power with one cartridge. Coupled with light-weight Composite cylinders of Hydrogen, it can provide silent power for extended durations.

Characteristics of Equipment

- DC Output: 12~18.5VDC Adjustable
- 30W Rated Output Power
- 450Whr hot-swappable Fuel Cartridge
- Weight: ~ 2.3 kg (60% reduction vis-à-vis Battery solution)
- Communication Interfaces: RS485, USB OTG
- High Altitude Operation: < 3000m ASL
- Zero emission (only water vapour)
- Silent, Very Low Thermal / IR Signature
- MIL-STD-810F & JSS-55555 Compliant
- PESO safety certified Hydrogen Cylinders

FCS Weight Benefits vis Batteries			
	VRLA	LHM	FCS + Cartridges
Typical Solution Weight for 3600Watt-hr endurance (kg)	80	17.5	7.4
Energy Density (Wh/kg)	37.5	172	405

Contact Person

Manoj Karam

Head - Renewable Products & Solutions

T: +91-22 6751 3600 / Extn.: 3631

M:+91-8655879301

F: +91-22 6751 3638 / 6751 3667

E: mkaram@TataPowerSED.com

75W FUEL CELL SYSTEM



The 75W Fuel Cell System (FCS) is an indigenously developed Proton Exchange Membrane Fuel Cell (PEMFC) based, light-weight, silent, and rugged power solution for portable applications, suitable for both Industrial as well as Military Environments. It offers the highest energy density (Watt-hrs/Kg) vis-à-vis battery solutions for applications where portable power is required for extended period of autonomy. It uses hot swappable Chemical Hydride Fuel Cartridges, where hydrogen is produced in-situ giving upto 6 hours of power with one cartridge. Coupled with light-weight Composite cylinders of Hydrogen, it can provide silent power for extended durations.

Characteristics of Equipment

- DC Output: 12~18.5VDC Adjustable
- 30W Rated Output Power
- 450Whr hot-swappable Fuel Cartridge
- Weight: ~ 2.5 kg (60% reduction vis-à-vis Battery Solutions)
- Communication Interfaces: RS485, USB OTG
- High Altitude Operation: < 3000m ASL
- Zero emission (only water vapour)
- Silent, Very Low Thermal / IR Signature
- MIL-STD-810F & JSS-55555 Compliant
- PESO safety certified Hydrogen Cylinders

FCS Weight Benefits v/s Batteries			
	VRLA	Li-ion	FCS + Cartridges
Typical Solution Weight for 3000Watt-hr endurance (kg)	80	17.5	7.4
Energy Density (Wh/kg)	37.5	172	405

Contact Person

Manoj Karam

Head - Renewable Products & Solutions

T: +91-22 6751 3600 / Extn.: 3631

M:+91-8655879301

F: +91-22 6751 3638 / 6751 3667

E: mkaram@TataPowerSED.com

MOBILE EMERGENCY COMMUNICATION SYSTEM



Mobile Emergency Communication System (MECS) is a Robust / Rugged Unified Communication System which can be quickly deployed to provide connectivity to support Fire Fighters, Disaster Response Teams and Relief Operations, special Forces etc.

MECS is designed to enable cross-communication of messages between varieties of communication technologies, intended to optimise communication during emergencies. It uses Hybrid IPPBX having both VoIP and TDM Voice capabilities. It has a powerful Voice and Video DSPs to deliver high performance encoding and decoding and conferencing features. It can be integrated with existing legacy interfaces through gateways.

MECS also provides wireless communication using state of art 4th generation cellular technology (LTE) to its users. Users can seamlessly communicate between wired and wireless clients within the local network as well as can communicate with the remote control central through long distance backhails.

The system also supports latest encryption technologies for security and privacy of communication.

Salient Features

- Trusted platform based design with embedded security
- 12-Slot, 12U Chassis, 19 inch rack mountable
- Non-blocking Back Plane with switching capacity upto 640Gbps (1+1)
- Power option: 2.5 KW Generator OR Fuel Cell (1.7 KW)
- Rod Antenna for Tactical LTE deployment
- Designed for LTE Band 28 supported (703MHz - 803MHz), but can be tailored for other bands too.
- Indigenously designed external Four Sector Phased Array Antenna with High gain (18 dBi)

Contact Person

Aparesch Patra

Business Development Manager

T: +91-80-67859900 Extn.: 8604

M:+91-9930143795

F: +91-80-67859901 / 02

E: apatra@TataPowerSED.com

AQUILON UAV



Aquilon is a hand launched, man portable UAV, ideal for providing frontline troops with increased situational awareness. This quick to deploy, easy to use system is designed for fully autonomous operations from Launch through Mission Execution and Recovery. The UAV is equipped with Two-axis retractable stabilised gimbal with HD colour video or IR camera, thereby enabling operations by day and night.

Characteristics of Equipment

- Fully autonomous operations with pre-set search patterns
- Ruggedised Ground Control Station for harsh environments
- Low noise, Low visibility, Low operational footprint
- Quick and easy assembly of airframe

Maximum Take off Weight	Approx 4 kg
Time to launch	< 15 minutes
Operational footprint	2 soldiers and 2 lightweight backpacks
Total weight of the system	Approx 12 -15 kgs
Endurance	> 60 minutes
Range	> 10 km
Propulsion	Electric motor for covert operations
Power source	Non-spillable rechargeable Li-Po batteries
Launch & Recovery	Hand launch & Conventional belly landing on skids
Cruise speed	54 kmph or 900 metres / min
Maximum winds	10 - 15 knots
Operational height	100 m to 1,000 m AGL
Ceiling height	Upto 6000m / 20000ft Above Sea Level

Contact Person

V S Srinivasan

Designation: DGM – Business Development

T: +91-11-66222666

F: +91-11-23341585

M:+91-9999464003

E: vssrinivasan@tataadvancedsystems.com

TIME REFERENCE SYSTEM



- Provides Time Synchronisation between Master and Slaves over IP networks.
- Implements Precision Time Protocol (PTP) as per IEEE 1588, V2
- Timing accuracy in microsecond range suitable for real time control systems
- Employs Best Master Clock Algorithm for automatic selection of masters
- Software configurable for Master / Slave roles
- 1PPS input / output signals for connecting to external units
- Ruggedised for Military Applications

Characteristics of Equipment

- | | | |
|-----------------|---|-----------------------------------------------------|
| ● 1PPS | : | 1 x Input & 1x Output Over RS422 |
| ● Accuracy | : | Less than 5usec between Master to Slave |
| ● Ethernet Port | : | 1 x for 1588 V2 & 1x for Host Interface |
| ● Dimensions | : | 1U, 19" Rack Mountable |
| ● Weight | : | Less than 6Kg |
| ● Connectors | : | Mil Std 38999 |
| ● Power | : | 230V AC |
| ● Op. Temp | : | 0 ⁰ to 50 ⁰ C (-200 Optional) |
| ● Storage Temp | : | -30 ⁰ to 50 ⁰ C |
| ● Environmental | : | As per Mil-Std 810F |
| ● EMI/EMC | : | As per Mil-Std 461E |

Contact Person

R Chandrasekharan

Assistant Vice President

T: +91-8414-664603

M:+91-8885073084

F: +91-8414-664632

E: rchandrasekharan@novaintegrated.com

RUGGED COMPUTER



- Ruggedised for Military Applications
- Intel Quad Core Processor
- Hardware RAID 0/1/5/10 configurable
- 4 x USB 2.0 / 3.0 Ports
- 6 x 10/100/1000 Mbps Ethernet Ports
- 1 x RS232, 1 x RS232/422/485 configurable
- SSDs easy accessibility from front
- MIL DTL 38999 Circular Connectors
- Windows, Linux support

Characteristics of Equipment

- RAM : 8GB DDR4 @2133MHz
(Expandable up to 64GB)
- Disks : 1 x 128GB SSD , 3 x 256GB SSD
- VGA / DVI (Optional) resolution : Supported up to 1920 x 1200
- Dimensions : 3U* Height, 19" Rack Mountable
- Weight : Less than 15Kg
- Connectors : Mil Std 38999
- Power : 230V AC
- Op. Temp : 0^o to 50^o C
- Storage Temp : -30^o to 50^o C
- Environmental : As per MIL-STD 810F
- EMI/EMC : As per MIL-STD 461E

Contact Person

R Chandrasekharan

Assistant Vice President


T: +91-8414-664603

M:+91-8885073084

F: +91-8414-664632

E: rchandrasekharan@novaintegrated.com

TACTICAL RF NETWORK PLANNING TOOL



- Useful for pre-mission deployment planning
- Point to Point & Point to Multipoint Radio Line Of Sight (LOS) radio link design
- Frequency Range 20MHz – 20GHz
- Implements Enhanced Longley-Rice and ITU 380.530 RF propagation models. Seamless integration of GIS and propagation models
- Considers atmospheric conditions (Rain, Temperature, Pressure & Humidity)
- Provision to mark enemy locations. Estimates driving time based on vehicle speed and shortest path by road

Characteristics of Equipment

- Software Loaded in Rugged Laptop with Linux OS
- Intel® Core i3-2310M Processor (2.1GHz)
- Storage Disk & RAM : 320GB HDD & 4GB DDR3
- Display Size & resolution : 13.1" XGA sunlight-viewable touch screen LED with resolution support of 1024 x 768.
- Dimensions : 2U* Height, 19" Rack Mountable
- Weight : Less than 6Kg (with 19" Rack Mountable kit)
- Connectors : Mil Std 38999
- Power : 230V AC, Rechargeable Battery Builtin
- Op & St Temp : 0° to 50° C & 30° to 50° C
- Environmental : As per MIL-STD 810F
- EMI/EMC : As per MIL-STD 461E

Contact Person

R Chandrasekharan

Assistant Vice President

T: +91-8414-664603

M: +91-8885073084

F: +91-8414-664632

E: rchandrasekharan@novaintegrated.com

LIGHT-WEIGHT TACTICAL FIELD COMPUTER



Light-weight Tactical Field Computer (TFC^{lite}) is the latest generation of Rugged Computers that allows soldiers to get a real-time situational picture of their own battlefield assets and that of the enemy. TFC^{lite} is designed for applications where light weight is required without compromising high-processing power. The system has a removable mass storage that is fully encrypted and has other unique security features ensuring real-time data security.

TFC^{lite} has a 10.4" high-brightness rugged display with an integrated Touchscreen and host of communication interfaces. Internal expansion site allows for integration of new generation Wireless interfaces or accommodation of additional Storage devices. Dual hot-swappable Li-ion battery packs provide TFC^{lite} with the capability of uninterrupted power for continuous operation.

The unit is designed for use in extreme harsh environments encountered in the battlefield. It operates uninterrupted even when dropped from a height of four feet in any orientation and upto depths of 1m underwater.

Features

- 6th Gen Intel® Core™ i7 platform with upto 8GB RAM
- IP-67 sealing protection (1m water immersion)
- Drop resistant upto height of 4ft
- Dual hot-swappable battery backup
- Multiple RS-422, RS-232 and Ethernet interfaces
- Conduction cooled design, no fans
- JSS55555:2012 L3 compliant
- MIL-STD-461E compliant

Contact Person

Chetan J Shetty

Head – Radars & Mil Sub-systems

T: +91-80-67859931

M:+91-9243700549

F: +91-80-67859901 / 02

E: cjshetty@TataPowerSED.com

MOBILE RUGGED COMPUTER



Mobile Rugged Computer (MRC) is an Intel® Atom™ based Ruggedised Light-weight Tablet Computer suitable for use in harsh environments. The system is designed specifically for mobile applications and has interfaces such as GNSS, Ethernet, USB & multiple RS-422.

MRC has a 7" high-brightness rugged LCD and an anti-glare shock / scratch-resistant touchscreen. It also has a 10-key compact fixed function keyboard.

MRC is rugged and meets all JSS55555 requirements for drop resistance, shock, rain, temperature, humidity & vibration.

The MRC is thus a versatile and rugged computer which can be configured for different types of end applications in a very short time. Depending on the application interface requirements, the circular connector pin-out and peripherals can be customised.

Features

- Low power Intel® Atom™ Platform with up to 1GB of RAM
- Fully Conduction cooled design, no fans
- Light Weight
- Integrated Compact fixed function keypad
- IP-65 sealing protection

Contact Person

Chetan J Shetty

Head – Radars & Mil Sub-systems

T: +91-80-67859931

M: +91-9243700549

F: +91-80-67859901 / 02

E: cjshetty@TataPowerSED.com

WEARABLE MOBILE COMPUTER



Wearable Tactical Computer (WTC) is a Low Power ARM Cortex A9 or equivalent based Wearable Computer, suitable for use in harsh environments. It has a variety of communication interfaces such as Ethernet, USB and RS-422. It also has an Interface for acquiring and displaying video from electro-optic sights or platforms.

WTC has 5" integrated display of WVGA (800x480) resolution and a resistive Touchscreen for operation. There are two storage options available in WTC, 8GB Nand Flash for storing OS and Application and 32GB μ SD card for data logging.

WTC has 5MP rear camera for taking pictures and videos in an actual field scenario. This can be disabled or enabled as required in different configurations. WTC is ideal for wearing on the wrist of the mobile Warrior. It can also be used with a MOLLE type or PALS type pouch and fixed on the soldier BLCV.

Features

- ARM Cortex A9 or equivalent platform with 1GB RAM
- Low Power & high performance
- Variety of I/O Interfaces
- Fully Conduction cooled and sealed design

Contact Person

Chetan J Shetty

Head – Radars & Mil Sub-systems

T: +91-80-67859931

M: +91-9243700549

F: +91-80-67859901 / 02

E: cjsheetty@TataPowerSED.com

RAJAK TWS THERMAL WEAPON SIGHT



RAJAKTM TWS series of Weapon Sights are single channel TI (Un-cooled) based weapon-cum-observation systems in monocular configuration. This series of Weapon Sights comes in 3 variants – Long, Medium & Short Ranges (i.e., LR, MR & SR) depending upon the weapon being used (CQB Carbine, Assault, LMG, MMG, RL, Sniper, etc.). The smallest version i.e. RAJAK-TWS-SR can also be head / helmet mounted for short range observation.

Real-time video feed can be taken onto a console for remote observation and in-built video recording capability can also be provided as per user requirements.

Characteristics of RAJAK TWS series of Night Sights (Capability & Physical Characteristics in bullet points)

- **Variants:** LR, MR, SR
- **Weight:** 500g to 1.5kg (depending on the variant)
- **Ranges:** Upto 1500m human detection (depending on the variant)
- Sights use Uncooled TI Engine with 320x240/ 640x480 detector resolution @ 17 μ m pixel pitch

Contact Person

Anurag Agarwal

Program Director - Optronics & Border Management

T: +91-11-66778618

F: +91-11-43602735

M:+91-9212783930

E: aagarwal@TataPowerSED.com

RAJAK TBC DNL



RAJAK™ TBC-DNL-1 is a multifunction observation & surveillance system which encapsulates a Day camera, a Cooled TI camera, LRF, GPS, DMC in a rugged enclosure while keeping the system quite light weight (< 4kgs). It is capable of being mounted on a small PTZ motor for remote controlled operations and achieves ranges of upto 10km for vehicle detection in clear weather scenario.

The system comes in 2 variants – with and without LRF (i.e., DNL & DN). Real-time video-feed can be taken onto a rugged console for remote observation at upto 100m via Ethernet cable and upto 10km (Line of Sight) wirelessly, depending upon the types of Tx-Rx radios used. Thus the system can be remotely controlled & operated from a safe distance.

Characteristics of RAJAK DNL series of Multifunction Systems (Capability & Physical Characteristics in bullet points)

- **Variants:** DNL & DN
- **Weight:** ≤ 4kg (depending on the variant)
- **Ranges:** Upto 10km
- The equipment comprises of the following 5 Sensors in a single rugged MIL-STD housing:
 - Night Camera: Cooled TI Engine with 640x512 detector resolution @ 15µm pixel pitch
 - Day Camera: High Resolution Low Light Camera
 - GPS, DMC & Optional LRF

Contact Person _____

Anurag Agarwal

Program Director - Optronics & Border Management

T: +91-11-66778618

F: +91-11-43602735

M:+91-9212783930

E: aagarwal@TataPowerSED.com

RAJAK II-TUBE NVDS



RAJAKTM series of Image Intensifier (II-tube) Night Vision Devices (NVDs) use the latest **Gen-3 II-tubes with FOM of 1700+** and are best suited for Night Operations (observations, surveillance, reconnaissance & firing). Major classification of these NVDs is: Monoculars, Binoculars / Goggles and Weapon Sights. The end use configurations are: Hand-held, Head / helmet mounted or Weapon mounted for Night firing. The Weapon Sights come in variants viz. 1X, 3X, 4X & 6X and can be used on weapons such as CQB Carbine, Assault, LMG, MMG, RL, Sniper, etc. as per the operational requirement.

Characteristics of RAJAK II-series of NVDs (Capability & Physical Characteristics in bullet points)

- **Variants:** Monoculars, Binoculars / Goggles & Weapon Sights
- **Weight:** 320g to 1.5kg (depending on the variant)
- **Ranges:** Upto 700m human detection (depending on the variant)
- **Battery Endurance:** 8 hrs to 60 hrs (depending on the variant & operational requirement) using commercially available AA cells
- Sights use latest Gen-3 II-tubes with FOM of 1700+

Contact Person

Anurag Agarwal

Program Director - Optronics & Border Management

T: +91-11-66778618

F: +91-11-43602735

M:+91-9212783930

E: aagarwal@TataPowerSED.com

TATA MOTORS LIMITED

- Address** : Tata Motors Ltd.
Geetani Building , 11-19, Nagindas Master Road
Hutatma Chowk, Mumbai- 400001, India
- Website** : www.tatamotors.com
- Head** : V S Noronha
- Telephone** : +91-22 66561600
- Fax** : +91-22 66561611
- Mobile** : +91-9821246461
- Email** : noronha@tatamotors.com

ORGANISATION PROFILE:

Tata Motors Limited (BSE: TATAMOTORS), a USD 45 billion organization, is a leading global automobile manufacturer of cars, utility vehicles, buses, trucks and defence vehicles. Part of the USD 100 billion Tata group, Tata Motors is India's largest and the only OEM offering extensive range of integrated, smart and e-mobility solutions. Tata Motors has operations in the UK, South Korea, Thailand, South Africa, and Indonesia through a strong global network of 109 subsidiary and associate companies, including Jaguar Land Rover in the UK and Tata Daewoo in South Korea.

Tata Motors has been a strategic partner to the Indian Armed Forces since 1958. During World War II, India developed a series of Wheeled Armoured Carrier, Indian Pattern or ACV-IP better known as the 'Tatanagar'. The vehicles used Ford truck chassis imported from Canada and armour-plated hulls constructed by TELCO (Tata Motors) Between 1940 and 1944, 4,655 units were built at the Railway workshop with a special plant set up for Armour, Hull, Axle and Tyre tracks. Tata Engineering & Locomotive Company or TELCO (now Tata Motors) completed the last order in 1945 when it took over the railway workshop.

Tata Motors Product portfolio: Tata Motors is present across the military spectrum providing all categories of vehicles catering to the specific needs of the Indian Armed Forces - Light mobility, mobility, utility, platforms, engineering, special mission, Armoured, Command posts, NBC and ICVs.

It is the only Asian company to have this spread of competence. A leading supplier of mobility solutions, it has supplied over 100,000 vehicles to the Indian military and para-military forces thus far.

In addition to the Indian Army, Navy, Air force and various Para-military forces, the company now also supplies to the defence forces of other countries including Sri Lanka, Bangladesh, Nepal and Tanzania, and to UN peace-keeping forces in conflict zones in Africa.

MINE PROTECTED VEHICLE (MPV)



- Mine Protected Vehicle (MPV) used as an armored personnel carrier with blast protection to transport personnel with protections from landmine explosives and small arms fire.
- Approx. 90 vehicles are in service with export markets such as Nepal army, Bhutan Army, Mozambique Army and state police forces such as Maharashtra, Chhattisgarh, Arunachal Pradesh and Jharkhand Police.
- A wheeled vehicle, which will operate in explosive hazardous environments to support in area clearance operations, Explosive Hazards Teams in explosive hazards and reconnaissance operations.
- The vehicle has **Single Piece V-Shaped Joint less Hull** Construction to prevent hull ruptures and also to protect the crew gainst severe blast conditions.
- Firing Ports available all round the vehicle for better survivability.

Characteristics of Equipment

- (a) Protection -
 - Protection against 14 kg of TNT under belly and 21 Kg of TNT under wheels (STANAG 4569 level B3)
 - Ballistic - NIJ Level III
 - Seats - Blast attenuating
- (b) Seating capacity - 10+2 seater with optional 12+2 available
- (c) Engine - Powerful 245 HP @ 2500 rpm with latest emission norms



- (d) Tyres - Runflat tyres
- (e) Equipped with HVAC and Power steering
- (f) Provision for Roof Mounting Ring Mount, Machine Gun Turret & Gun Mount for counter insurgency operations.

Contact Person _____

Pranav Singh

General Manager - Combat Vehicles & Exports

T: +91-22-66561681

F: +91-22-66561611

M: +91-8097066500

E: pranav.singh@tatamotors.com



WHEELED AMPHIBIOUS PERSONAL CARRIER (WhAP 8x8)



- **VERSATILE AMPHIBIOUS PLATFORM CAPABLE FOR ALL MISSIONS AND MOUNTING OF ANY WEAPON SYSTEM.**
- WhAP (8X8) (Wheeled Amphibious Platform), an Infantry Combat Vehicle, designed for optimized survivability, all-terrain performance and increased lethality jointly with VRDE, Indian Defence Research and Development Organization (DRDO)
- **Universal type turret mounting provision to accommodate any type of turret with 360o of surveillance**
- WhAP will create a dramatic impact on the future battlefield with state of Art features suitable for combat operations and best in class mobility, firepower and safety feature

Characteristics of Equipment

- Modular & scalable design caters for a future increase in Gross weight from 22 tonnes to 26 tonnes.
- Powerful 600 HP engine.
- Independent hydro pneumatic suspension.
- Speed - 100 kmph on land and 10 kmph in amphibious mode.
- Seating capacity of 10+2 personnel



- **USPs**

- Blast Protection : Options of STANAG level II to IV
- Ballistic Protection : Options of NIJ Level III - IV {B6 - B7 or STANAG II - III}
- NBC protection option

Contact Person_____

Pranav Singh

General Manager - Combat Vehicles & Exports

T: +91-22-66561681

F: +91-22-66561611

M: +91-8097066500

E: pranav.singh@tatamotors.com



ZEN TECHNOLOGIES LIMITED

- Address** : B-42, Industrial Estate, Sanath Nagar
Hyderabad - 50018, India
- Website** : www.zentechnologies.com
- Head** : H J Kamath
Senior Vice President
- Telephone** : +91-40-23813281
- Fax** : +91-40-23813694
- Mobile** : +91-9845022146
- Email** : kamath.hj@zentechnologies.com

ORGANISATION PROFILE:

Zen Technologies Limited, incorporated in 1993, designs, develops manufactures world-class, state-of-the-art training simulators. Its mission is to provide its customers quality products and services. It has AS9100:2016 from DQS Inc., ISO 9001:2015 (QMS), ISO 14001:2015 (EMS), ISO/IEC 27001:2013 (ISMS) certifications. Zen Technologies appraised at the highest maturity Level 5 of the Capability Maturity Model® Integration for CMMI®-DEV 1.3 (Development).

Zen is at the forefront of applying new technologies and developing new products. It is actively involved in indigenization of technologies, which is beneficial to Indian Security Forces. Now Zen is the leader, offering Firearms, Tank, Driving, and Unmanned Aerial Vehicle (UAV) simulators & 30 products.

We provide a unique training solution the Combat Training Centre (CTC), wherein we provide a full training solution for the armed forces for obtaining perfection individually & as a team. Our solution assists in mission planning as well as provides a war-gaming solution for the senior commanders.

ZEN COMBAT TRAINING CENTRE (ZEN CTC)



Zen CTC is a one-stop training solution for Armed Forces and State police. The secure facility, equipped with modern training equipment/infrastructure, free from routine encumbrances and other disturbances, is designed to provide performance-oriented training in realistic, tactical and operational environment.

Characteristics of Equipment

- Operational Training In Geo-Specific 3D Terrain
- Specialise In CQB Drills
- Always Mission Ready To Neutralise Internal and External Threats
- Attain Marksmanship In Small Arms & Excellence In Crew Served Weapons Faster
- Validate Tactical Standard Operating Procedures
- Accelerate Adaptability of Units/Sub-units to New Op Roles & Terrain

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

ZEN ADVANCED WEAPONS SIMULATOR (ZEN AWESIM)



Zen AWeSim® is a state-of-the-art firearms simulator aimed at training recruits to Special Forces and Commandos. It recreates Small Arms firing range indoors. The simulator can be adapted to a number of firearms and the versatile simulator imparts basic training, hones firing skills, improves weapon handling skills and tests the skill level of trainees in complex and war-like scenarios.

Characteristics of Equipment

- Supports all direct-fire small arms
- All static and dynamic characteristics of the weapon are sustained Ballistics performance of the projectiles is replicated in terms of range, velocity/time of flight and trajectory
- Employs un-tethered recoil generation system Simulates firing sounds
- Firing Group analysis, with hold and aim graphic representation
- Close-up/zoom facility and auto display/recording of results
- Simulates environmental conditions such as wind, rain, fog and light conditions with time of day/night and moon phases
- Shows realistic effects of ammunition simulated at target end
- Incorporates use of white light illumination, trip flares and smoke/hand grenades and other munition for tactical exercises
- Provides all firing modes—single shot, burst/controlled burst and automatic fire available in the weapon being used
- Allows firing of mix of weapons in same detail, on targets at respective ranges of various weapons
- Facilitates training in combat tactical situations on video scenarios Allows selection of trainee for a lane and select target, range and bullets issued



- Provides comprehensive Scenario Builder and Video Editor modules
- Reports cant angle, trigger pressure and breathing pattern Provides telescopic sighting system for Rocket Launcher and Sniper Rifles
- Includes facility to record and playback a stopped training session Syncs with the firing positions of trainees (lying, kneeling and standing)
- Allows injection of faults to test trainees Has provision for night firing practices and use of night vision sights

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com



ZEN ANTI TANK GUIDED MISSILE SIMULATOR (ZEN ATGM)



Zen ATGM® Sim is an indoor simulator, designed and developed to meet the challenging training requirements of missile pilots. It trains recruits and hones the skills of trained pilots in handling and firing missiles. The guided missile simulator enables instructor to track the performance of trainees in real time.

Characteristics of Equipment

- Realistic missile dynamics.
- Integrates with an Infantry Combat Vehicle like BMP-II.
- Compatibility with MILAN/KONKURS/FAGOT missiles.
- Setting of training scenarios in accordance with the skill levels.
- Technical faults of missiles can be introduced to practice drills.
- Exact replica with actual controls.
- Trains recruits and hones the skills of trained pilots in handling and firing Missiles.
- Realistic sound effects and artificial illumination for night training.
- Offers a variety of targets, including aerial targets.

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

ZEN TACTICAL ENGAGEMENT SIMULATOR (ZEN TACSIM)

Zen TacSim® trains soldiers to utilize the skills acquired during training in field craft, battle drills and live-fire practice while carrying out operational exercises. It assimilates lasers fired from different weapon systems and effectively records the result of the engagement.



Characteristics of Equipment

- Modular & scalable system for training needs. Can exercise upto 3000 troops with supporting elements.
- Covers effectively a training area upto 5 kms diameter. Additional range obtained through repeaters.
- Excon and communication module equipment is light, portable & mobile. Can easily be mounted & transported cross-country on a light Jeep-like vehicle.
- Battlefield commanders can conduct briefings, analyse terrains, plan operations & test efficacy of plans.
- Rugged, simulates accurate firing of weapons/detection of hits & is tamper proof.
- Simulates minefields, artillery fire, booby traps/IEDs & grenade effects.
- Seamless transition from outdoor to indoor activity.
- Room Awareness Device (RAD) enables soldiers/sub-units to train in built-up area/indoors, where GPS is ineffective.
- Effect of direct fire weapons such as RL on building structures and troops inside buildings is simulated & effects recorded.

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

ZEN SMART TARGET SYSTEM (ZEN STS)



ZEN STS® is an electro-mechanical, software-driven, acoustical projectile detection and reporting system designed to be used at outdoor ranges for live Small Arms firing. The equipment is rugged, light-weight, easy to assemble and operate. It is available in wired and wireless configurations. The system can be operated with 230V AC 50 Hz or with DC battery power.

Characteristics of Equipment

- Immediate feedback of position of the shot on the Firing Point Equipment (FPE) and Master Control System (MCS).
- MCS can run multiple lanes with same or different exercises simultaneously.
- Can be employed for various target exercises on any existing firing range.
- Army Range Course (ARC) and Customized exercises can be operated.
- Grouping, Static, Timed & Snapshot exercises.
- Auto recording and replay of all exercises.
- Allows user to edit existing firing exercises.
- Displays Group size, MPI, Possible and Aggregate Scores.
- Target illumination for night firing.
- Reports can be printed from the MCS.
- Cross Fire detection.
- Displays possible and aggregate scores.
- Portable and easy to install.
- Eliminates need to man the firing range butt.



- Pop-up mechanism for snap-shot exercises.
- Available in both cable and wireless configuration.
- Zoom In/Out, Panning of the targets on both FPE and MCS.
- Quick analysis of firers performance and comparison with past firing records

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com



ZEN MULTI-FUNCTIONAL TARGET SYSTEM (ZEN MFTS)



Zen MFTS® is an electro-mechanical system of versatile targets which are programmable from Firer's End to perform various movements for firing practices. The system is designed for use both at outdoor and indoor shooting ranges. It is portable and easy to operate. It is a rugged, all-weather system and meets IP 65 standards.

Characteristics of Equipment

- Designed for Outdoor/Indoor live firing.
- Provides realistic environment for specialized training.
- Improved reflex shooting of the trainee.
- Capable of recording single shot slow fire, single shot rapid fire and fully automatic fire.
- Target exposure time can be set by the controller.
- Adjustable for various types of Infantry targets.
- Motion sensors for exposing target automatically on proximity of firer.
- Target illumination for night firing.
- All parts are sealed to avoid dust and moisture.
- Operating Temperature 0 to 50 degree Celsius

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

MODEL OF ZEN SHOOT HOUSE

Zen Shoot House is a safe indoor facility, built to meet the training needs of security personnel involved in operations to eliminate enemy/terrorist threat in closed environment of a built-up area. Shoot House is a concrete and brick/masonry structure with ballistic protection and other essential features like ballistic doors/windows, wooden staircase, elevator shaft, trap-door, rubber furniture and realistic equipment.



Characteristics of Equipment

- Creates realistic and dynamic live-fire training environment
- Ballistic tiles insulation enables 360 degrees internal live fire with high velocity small arms 5.56 & 7.62mm
- Variety of rubber/fibre sheet targets – static & multi-function
- Realistic rubber furniture/equipment as appropriate to settings
- Sliding/pivoting walls provided to quickly change internal layout for varied training
- Ballistic doors/windows, wooden staircase, elevator shaft, trap-door etc provided
- Ventillation/air circulation, varied lighting & sound suppression
- Video cameras to monitor & record all actions of trainees for AAR & critique
- High-end safety & security system, fire-retardant materials
- Generator & emergency lighting back-up
- Inter-communication between Instructor/Control Station & Trainees
- International safety standards compliant

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

ZEN SHOOTEDGE



ShootEdge® is synonymous to shooting without risk of exposure to retaliatory shooting by adversary. It is amplified by ability to maneuver behind a shield or protection thereafter fire for effect. These systems are necessary and are force multipliers in encounters with terrorists and insurgents in wide ranging situations from battles in built up areas to hostage situations.

Characteristics of Equipment

Getting into action. Simple to use, can be easily carried by a soldier, takes less than a minute to get it into action. Can be adapted for many weapons, it has the ability to be used in all possible eventualities in close combat.

Aimed Fire. Provides ability to shoot with accuracy and consistency from angles and enhances the effectiveness of encased weapon. Simple aiming methodology provides ability to scale up shooting skills and hence enable firer to become a marksman.

Firing from the Hip. The inherent ability and accuracy of the weapon to fire from the hip is maintained and gets better due to added parts of the system.

Night Firing. IR Camera enables effective firing in night, this lethal ability to fire at night from a covered position without exposure provides perceptible ascendancy over adversary.

Ease of Operation. ShootEdge is customized for a particular weapon and this enables ease of assembly in shortest possible time frame and getting the weapon into action.

Light Weight. The system is lightweight and can be carried along with a pistol into battles or encounters. ShootEdge comes with a sling that allows ease of carriage

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

ZEN HAND GRENADE SIMULATOR (ZEN HE36S)



Zen HE36S® is a patented hand grenade simulator that helps trainees develop a high degree of mind-body coordination, essential for effectively firing hand grenades and preventing accidents. It is a non-fragmenting and reusable hand grenade. It is useful for soldiers for handling, practicing lobbing techniques and reacting to the timing of the fuze. The simulator is of the same dimension, shape, weight, look and feel of the HE36 hand grenades used by Security Forces.

Characteristics of Equipment

- Overcomes the problem of shortage of grenade firing ranges.
- Option to either lob or fire with a rifle.
- Produces blast, flash, smoke and sound but does not fragment.
- Removes fear, improves reflexes and increases mind-body coordination.
- Fills gap between squad post training and live grenade throwing/firing to perfection.
- Allows 24X7 training in restricted space, saving time and logistics.
- Reusable up to 80-100 times.
- No serious casualties or injuries.
- Realistic training.
- Allows arming and disarming drills of grenade as in actuals.

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

ZEN CONTAINERIZED TUBULAR SHOOTING RANGE (ZEN CTSR)



Zen CTSR is a secure indoor substitute for live firing. It is self-contained, transportable and reduces considerably the area required for a range. It can also be used to test weapons or as a forensic ballistic test facility.

Characteristics of Equipment:

- Facilitates training with Small Arms
- Lets firers practise even in lying position
- Accommodates extension of the length of range with additional containers
- Includes a target system that detects bullets' points of hits and displays them on Firing Point Equipment which is placed close to the firer
- Contains projection systems that beam selected target, terrain and range on to the detection system
- Offers a display system that enables Commander/instructor to view the activities of firers inside the container as well as bullet hits on targets
- Provides record-replay facilities for After Action Review

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com

ZEN CONTAINERIZED INDOOR SHOOTING RANGE (ZEN CISR)



Zen CISR is a self-contained, transportable, live-fire shooting facility. It is designed and built to include the target retrieval system/firearm judgmental training video simulator or to serve as a forensic ballistic test facility

Characteristics of Equipment

- Helps overcome logistics involved in outdoor shooting
- Cost-effective against indoor shooting ranges
- Offers facility to fire at target ranging from 25 metres to 300 metres or even upto 2000 meter with the help of the application software for scaling the target.
- Does not require construction of infrastructure
- Transportable
- Installation process is minimal
- Ventilation system ensures there is no health hazard from smoke/fire either for the trainee or staff inside the premises or even outside the CISR.
- Acoustic treatment to keep the noise to acceptable levels

Contact Person

Abhishek Agnihotri

Assistant Vice President- Business Development (Exports)

T: +91-40-23813281

F: +91-40-23813694

M: +91-8130020128

E: a.agnihotri@zentechnologies.com



About FICCI

Established 90 years ago, FICCI is the largest and oldest apex business organization in India. Its history is closely interwoven with India's struggle for independence, its industrialization, and its emergence as one of the most rapidly growing global economies.

A non-government, not-for-profit organization, FICCI is the voice of India's business and industry. From influencing policy to encouraging debate, engaging with policy makers and civil society, FICCI articulates the views and concerns of industry, reaching out to over 2,50,000 companies. FICCI serves its members from large (domestic and global companies) and MSME sectors as well as the public sector, drawing its strength from diverse regional chambers of commerce and industry.

The Chamber with its presence in 14 states and 10 countries provides a platform for networking and consensus-building within and across sectors and is the first port of call for Indian industry, policy makers and the international business community.

CONTACT US

Federation of Indian Chambers of Commerce and Industry (FICCI)

Federation House, 1, Tansen Marg, New Delhi - 110001

E: vivek.pandit@ficci.com, v.vaidhyanathan@ficci.com

T: +91-11-23487276/384 **F:** +91-11-23765333

W: www.ficci.in | www.ficcidefence.in